This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

**Usage guidelines**

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

**About Google Book Search**

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

1817
ARTES SCIENTIA VERITAS
LIBRARY OF THE
UNIVERSITY OF MICHIGAN
E PLURIBUS UNUM
TUEBOR
SI QUAERIS PENINSULAM AMOENAM
CIRCUMSPICE

Kames, Henry Home

THE

# GENTLEMAN FARMER.

BEING

An Attempt to improve

AGRICULTURE,

By ſubjecting it to the Teſt

OF

RATIONAL PRINCIPLES.

*Semper ego auditor tantum?*

JUV.

EDINBURGH:
Printed for W. CREECH, Edinburgh,
and T. CADELL, London.

MDCCLXXVI.

Libr.
Harding
12.20.42
46444

# EPISTLE

## TO

## Sir JOHN PRINGLE,

## Preſident of the ROYAL SOCIETY.

THERE are few perſons who rival Sir John Pringle in my eſteem: there are ſtill fewer whoſe friendſhip I value more. It is not, however, my purpoſe in this letter, to proclaim theſe things to the world; for what concern has the world with private connections? Ambition to have the patronage of the Royal Society to this work, is my motive for addreſſing you in this public manner. The plan it recommends, has been my guide many years; and ſucceſs has left me no doubt of its ſolidity. Your ſanction, my friend, will enſure it a gracious reception, from a body of learned men, who have diſtinguiſhed your literary merit by the greateſt honour they have to beſtow. It is my fervent deſire to be uſeful to my country: the ſtamp of that illuſtrious Society, will give a currency to the work:

every one will read; and every ſenſible farmer will profit by it.

Agriculture juſtly claims to be the chief of arts: it enjoys beſide the ſignal pre-eminence, of combining deep philoſophy with uſeful practice. The members of your Society cannot employ their talents more profitably for their country, or more honourably for themſelves, than in promoting and improving an art, to which Britain fundamentally is indebted for the figure it makes all the world over.

The


1817
ARTES
SCIENTIA
VERITAS
LIBRARY OF THE
UNIVERSITY OF MICHIGAN
E PLURIBUS UNUM
TUEBOR
SI QUAERIS PENINSULAM AMOENAM
CIRCUMSPICE

thority of former writers: opinions paſs curre from generation to generation; and no perſo enquires whether they wear the livery of truth Take the following ſhort ſpecimen, drawn from ſingle head, that of manures. Writers talk learnedly of lime, ſtone-marl, clay-marl, ſhell-marl and of other manures; and foretell how they wi operate upon ſoil, with the ſame aſſurance as i they could penetrate into their nature and eſſence. "Clay-marl," ſay they, "has more power to deſtroy acids and to produce ſalts, than ſtone-marl: *ergo*, a leſs quantity of it upon land is ſufficient. Marl extracts greaſe out of woollen cloth: greaſe is a ſpecies of oil: *ergo*, marl extracts oil from the air. A greater quantity of marl is laid on land, than of lime: *ergo*, it muſt have a greater effect in attracting vegetable food from the air. Shell-marl found under moſs, is compounded of earth and the alkaline ſalt of rotten wood. Becauſe clay is mixed with ſand in making brick, that mixture muſt be an enemy to vegetation. The mixing earth and lime with dung, makes an excellent compoſt. Rain makes flinty ſand firmer and more compact," &c. &c. Some of theſe propoſitions are erroneous, ſome at beſt doubtful.

And yet, they are but a few of many propoſitions, boldly aſſerted by writers, though they would require the elucidation of a Newton or a Boyle. So much I will vouch for myſelf, that I have not mentioned a ſingle article as certain, but what I have practiſed many years with ſucceſs: the inſtructions contained in this book, are founded on repeated experiments and diligent obſervation. If any particular happens to be mentioned that has not come under my inſpection, the reader is warned of it. In ſhort, it will ſoon be perceived, that this is not a bookſeller's production.

The dawn of a manufacture, is irkſomely ſlow in its progreſs to broad day. Indocility is difficult to be overcome: habitual indolence, ſtill more. Theſe obſtructions vaniſh in a manufacturing country. A boy learns by ſight his father's trade, even before he can ply his little hand about an inſtrument. He acquires activity by ſeeing others active: he comprehends not what it is to be idle. This obſervation is ſtrongly exemplified in agriculture. Some years ago, farmers in Scotland were ignorant and indolent; nothing to be ſeen but weeds and traſh, not a ſingle field in order. People habituated to ſuch objects, never once thought of doing better. Skill in agriculture is ſpreading gradually in Scotland; and young people acquire ſome knowledge by ſight, even before they think of practice. After ſuch advance, may we not hope, that our progreſs will now be rapid; and that agriculture will ſoon be as familiar among us, and as ſkilfully conducted, as in England? May this reflection animate our landed gentry; and inflame them with a deſire, to acquire riches to themſelves and luſtre to their country.

There certainly never was in Scotland a period, when good leſſons in huſbandry were more ſeaſonable than at preſent. This country, growing in population, affords not corn ſufficient for its inhabitants; and yet waſte land abounds, which ſome ſkill and much induſtry would fertilize. Is it not deplorable, that in the beſt-cultivated ſhires, large patches of land ſhould produce nothing but broom and whins, not from barrenneſs but from indolence? Can greater encouragement to induſtry be wiſhed, than a ready market for every thing the ſoil produces? how different from the condition of Scotland, not more than forty years ago! Can a landholder be employed more profitably for his country, or more honourably as well as profitably for himſelf, than to rouſe emulation among his tenants, by kind treatment, by inſtruction, by example, and by premiums? Let him ſtudy the rules contained in this little work, all of them plain and adapted to practice. Let him convene his tenants once a-year to a hearty meal; and engage them to follow theſe rules. What if he ſhould beſtow on the deſerving, a plough or a brake of the beſt conſtruction? Land cannot be improved at a cheaper rate. It was by ſuch means, that the late John Cockburn of Ormiſtown, promoted emulation and induſtry among his people. His patriotic zeal was rewarded: he lived to ſee his eſtate in a higher degree of cultivation, than even to this day is ſeen in any other part of Scotland. The ſame means were employed more extenſively, by the late Earl of Findlater: the ſkill and perſeverance of that nobleman, raiſed his tenants from a torpid ſtate, to a ſurpriſing degree of activity; and few can now vie with them, either for induſtry or knowledge. Had other landlords been equally active, how flouriſhing would agriculture have been in Scotland? Great ſums would annually have been received for corn; inſtead of being imported for ready money, a commodity that can very ill be ſpared. The field is ſtill open: let us join hearts and hands to redeem time wofully miſpent. I ſay again, that never was in Scotland, a period more favourable to agriculture than the preſent.

Agriculture is a very ancient art. It has been practiſed every where without intermiſſion; but with very little attention to principles. In ſtudying the principles laid down by writers, I found myſelf in a ſort of labyrinth, carried to and fro without any certain direction. After a long courſe of reading, where there was nothing but darkneſs and diſcrepance, I laid aſide my books, took heart, and like Des Cartes commenced my inquiries with doubting of every thing. I reſorted to the book of nature: I ſtudied it with attention: and the ſecond part of this work contains the reſult of my inquiries. It is far from my thoughts, to impoſe my opinions upon others: I pretend only to have reduced the theory of agriculture into a ſort of ſyſtem, more conciſe at leaſt, and more conſiſtent, than has been done by other writers. Many eyes are better than one; and if my theory ſhall be found erroneous, the many that have erred before, will ſerve in ſome meaſure to keep me in countenance. I am not however afraid of any groſs error. An *imprimatur* from one of the ableſt chymiſts of the preſent age, has given me ſome confidence of being in the right track*.

I have all along ſtudied brevity, as far as conſiſtent with perſpicuity; and therefore, have confined myſelf to matters, that I know to be of real uſe in practice. I am ambitious to have my plan followed, becauſe ſucceſsful experience has proved it to be ſolid: but I ſhould not hope for many readers, if I hazarded the tiring them with unneceſſary matters. Varro *de re ruſtica*, appears to be very ſparing of inſtruction; but rivals Ariſtotle himſelf in the ſubtilety of his diviſions. "Nunc "dicam agri quibus rebus colantur. Quas res "alii dividunt in duas partes, in homines et admi"nicula hominum: ſine quibus rebus colere non "poſſunt. Alii in tres partes, inſtrumenti ge"nus vocale, et ſemivocale, et mutum. Vocale, "in quo ſunt ſervi: ſemivocale, in quo ſunt bo"ves: multum, in quo ſunt plauſtra." Such puerile diviſions, may be of uſe to ſwell a volume; but give no inſtruction, and are extremely tireſome.

I cannot finiſh this preface without warmly recommending agriculture to gentlemen of land-eſtates; for whoſe uſe chiefly this work is intended. In every well-governed ſtate, agriculture has been duly honoured. In ancient Perſia, a feſtival was yearly celebrated, in which huſbandmen were freely admitted to the King's table. "From "your labours, ſaid the King, we receive our "ſuſtenance; and by us you are protected. Being mutually neceſſary to each other, let us, "like brethren, live together in amity." The great emperor of China, performs yearly the ceremony of holding the plough, to ſhow that no man is above being a farmer. The iſland Miletus, during many years, had been afflicted with factions: the government was ſettled by ſome wiſe men of Paros, a neighbouring iſland. Theſe men having ſurveyed the iſland, and marked the poſſeſſor of every well-cultivated farm, convocated an aſſembly of the people, and appointed theſe perſons to be governors. "The perſon," ſaid they, "who governs his private affairs with prudence and induſtry, is "qualified to govern thoſe of the public." The king of Tunis, invaded by a powerful enemy, promiſed to a neighbour who aſſiſted him, the philoſopher's ſtone. He ſent a plough, ſaying, That a plough was virtually the philoſopher's ſtone; for that it would produce rich crops, to procure gold in plenty.

---

* Dr Black profeſſor of chymiſtry in the college of Edinburgh.

In the view of profit, agriculture is fit for every man. But my preſent view is to recommend it, as of all occupations the moſt proper for gentlemen in a private ſtation. Matter crouds upon me; and I am at a loſs where to begin. Agriculture correſponds to that degree of exerciſe, which is the beſt preſervative of health. It requires no hurtful fatigue, on the one hand, nor indulges, on the other, indolence, ſtill more hurtful. During a throng of work, the diligent farmer will ſometimes be early and late in the field: but this is no hardſhip upon an active ſpirit. At other times, a gentleman who conducts his affairs properly, may have hours every day, to beſtow on reading, on his family, on his friends.

Agriculture is equally ſalutary to the mind. In the management of a farm, conſtant attention is required to the ſoil, to the ſeaſon, and to different operations. A gentleman thus occupied, becomes daily more active, and is daily gathering knowledge: as his mind is never ſuffered to languiſh, he is ſecure againſt the diſeaſe of low ſpirits.

But what I chiefly inſiſt on is, that laying aſide irregular appetites and ambitious views, agriculture is of all occupations the moſt conſonant to our nature; and the moſt productive of contentment, the ſweeteſt ſort of happineſs. In the firſt place, it requires that moderate degree of exerciſe, which correſponds the moſt to the ordinary ſucceſſion of our perceptions. Fox-hunting produces a ſucceſſion too rapid: angling produces a ſucceſſion too ſlow. Agriculture correſponds not only more to the ordinary ſucceſſion, but has the following ſignal property, that the farmer can direct his operations, with that degree of quickneſs and variety, which is the beſt ſuited to his own train of perceptions. In the next place, to every occupation that can give a laſting reliſh, hope and fear are eſſential. A fowler has little enjoyment in his gun, who miſſes frequently; and he loſes all enjoyment, when every ſhot is death: a poacher, ſo dextrous, may have pleaſure in the profit, but none in the art. The hopes and fears that attend agriculture, keep the mind always awake, and in an enlivening degree of agitation. Hope never approaches certainty ſo near, as to produce ſecurity; nor is fear ever ſo great, as to create deep anxiety and diſtreſs. Hence it is, that a gentleman farmer, tolerably ſkilful, never tires of his work; but is as keen the laſt moment as the firſt. Can any other employment compare with farming in that reſpect? In the third place, no other occupation rivals agriculture, in connecting private intereſt with that of the public. How pleaſing to think, that every ſtep a man makes for his own good, promotes that of his country! Even where the balance happens to turn againſt the farmer, he has ſtill the comfort that his country profits by him. Every gentleman-farmer muſt of courſe be a patriot; for patriotiſm, like other virtues, is improved and fortified by exerciſe. In fact, if there be any remaining patriotiſm in a nation, it is found among that claſs of men.

A gentleman-farmer who is diſpoſed to embelliſh his fields, has a great advantage over others. He can execute that pleaſing work at the cheapeſt rate, by employing upon it his farm-ſervants and cattle, every vacant hour. This ſlow method is indeed ill ſuited to the ardour of an Indian Nabob, impatient for enjoyment. But is not the advantage clearly on the ſide of the farmer? The refined pleaſure of embelliſhments, ariſes from a ſlow progreſs; which affords leiſure to feaſt the eye upon every new production.

In former times, hunting was the only buſineſs of a gentleman. The practice of blood made him rough and hard-hearted: he led the life of a dog, or of a ſavage; violently active in the field, ſupinely indolent at home. His train of ideas was confined to dogs, horſes, hares, foxes: not a rational idea entered the train, not a ſpark of patriotiſm, nothing done for the public, his dependents enſlaved and not fed, no huſbandry, no embelliſhment, loathſome weeds round his dwelling, diſorder and dirt within. Conſider the preſent mode of living. How delightful the change, from the hunter to the farmer, from the deſtroyer of animals to the feeder of men! Our gentlemen who live in the country, have become active and induſtrious farmers. They embelliſh their fields, improve their lands, and give bread to thouſands. Every new day promotes health and ſpirits; and every new day brings variety of enjoyment. They are happy at home; and they wiſh happineſs to all.

As the ſcene of the author's experience has all along been in Scotland, his native country; he is shy to recommend his plan of huſbandry to any but to his countrymen. He has, however, a thorough conviction, that giving allowance for ſlight variations of climate, his plan will ſuit England, France, Italy, and every other country ſituated within either of the temperate zones.

In arts and ſciences, a plentiful ſource of obſcurity and indiſtinctneſs, is the uſing a word in different ſenſes, without warning the reader of it. Conſidering what volumes have been compoſed on agriculture, it is amazing, how little preciſion is in the terms of art. Take the following inſtance. The word *furrow* is employed to ſignify not only the hollow made by the plough, but the earth taken out of that hollow, and alſo the hollow between ridges. Better coin words than write indiſtinctly. Let *furrow* be appropriated to the ſpace in which the plough moves, and alſo to the hollow between ridges; which will not occaſion any confuſion. But I venture to diſtinguiſh the earth moved by the plough, by the name of the *furrow-ſlice*. The ſmall hollows that appear between the ſlices when a ridge is ploughed, may be termed *ſeams*.

*Nota bene*, The Engliſh acre, the Linlithgow meaſure, the Dutch weight, are to be underſtood, where the contrary is not ſpecified.

CON.

# CONTENTS.

## PART I.

## Practice of Agriculture.

### CHAP. I.

### Inſtruments of Huſbandry.

Pag.
1. *The Plough*, - - 2
2. *The Brake*, - - 13
3. *The Harrow*, - - 15
4. *The Roller*, - - 21
5. *The Fanner*, - - 25

### CHAP. II.

### Farm Cattle and Carriages,

1. *Farm-Horſes*, - - 25
2. *Farm-Oxen*, - - 26
3. *Breeding Horſes and horned Cattle*, 39
4. *Wheel-Carriages*, - - 41

### CHAP. III.

Farm-Offices, - 46

### CHAP. IV.

### Preparing Land for Cropping.

1. *Obſtructions to cropping*, - 53
2. *Bringing into culture Land from the ſtate of nature*, - - 63

3. *Forming*

Pag.
3. *Forming Ridges*, - 68
4. *Clearing ground of weeds*, - 75

## CHAP. V.

Culture of Plants for Food. 81
Sect. 1. *Plants cultivated for fruit*, 83
1. *Wheat and Rye*, - *ib.*
2. *Oats*, - - 87
3. *Barley*, - - 91
4. *Beans*, - - - 95
5. *Peaſe*, - - 98
Sect. 2. *Plants cultivated for roots*, 101
1. *Turnip*, - - *ib.*
2. *Potatoes*, - - 106
3. *Carrot and Parſenip*, - 110
Sect. 3. *Plants cultivated for leaves*, 111

## CHAP. VI.

Culture of Graſs, 114

## CHAP. VII.

Rotation of Crops, 124

## CHAP. VIII.

Reaping Corn and Hay Crops, and ſtoring them up for uſe, - - 145

## CHAP. IX.

Feeding Farm-Cattle, 157
1. *Green food*, - - 158

Pag.
2. *Dry food,* - - 172
3. *Feeding for the butcher,* - 177
4. *The wintering of cattle not intended for immediate ſale,* - - 190
5. *Rules for buying and ſelling cattle and corn,* - - 193

## CHAP. X.

Culture of other Plants proper for a Farm. 200
Sect. 1. *Foreſt Trees,* - - *ib.*
1. *Raiſing trees by ſeed,* - 201
2. *Cuttings, layers, ſuckers,* 211
3. *Soil proper for trees,* 214
4. *Climate,* - - 216
5. *Time of planting trees in the field,* - - 218
6. *Manner of planting,* - 220
7. *Pruning,* - - 226
8. *Wood proper for inſtruments of huſbandry,* - - 230
Sect. 2. *Flax,* - - 233
Sect. 3. *Hops,* - - 235

## CHAP. XI.

Manures, 237

## CHAP. XII.

Fences, 250

## CHAP. XIII.

The proper ſize of a farm, and the uſeful accommodations it ought to have, - 267

### CHAP. XIV.

Pag.
What a corn-farm ought to yield in rent, 280

## PART II.

Theory of Agriculture. 290

### CHAP. I.

Preliminary Obſervations. 292
1. *Elective attraction and repulſion,* *ib.*
2. *Plants have a faculty to accommodate themſelves to their ſituation,* 304
3. *Change of ſeed and of ſpecies,* 309

### CHAP. II.

Food of Plants, and Fertility of Soil, 312

### CHAP. III.

Means of fertilizing Soils, 340
1. *Ploughing,* - - *ib.*
2. *Manures,* - - 347

## APPENDIX.

Art. 1. *Imperfection of Scotch huſbandry,* 359
Art. 2. *A board for improving agriculture,* 367
Art. 3. *General heads of a leaſe for a corn-farm,* - 378
Art. 4. *Plants and animals compared,* 385
Art. 5. *Propagation of plants* 398

# THE GENTLEMAN FARMER.

NAtural Hiſtory is confined to effects; leaving cauſes to Natural Philoſophy. From a number of effects, Natural Philoſophy aſcends by induction to the immediate cauſe; and from ſuch cauſes to what are more comprehenſive. Moſt writers on huſbandry handle it as a branch of Natural Hiſtory. Some, more bold, conſider it as alſo a branch of Natural Philoſophy: they begin with effects, and endeavour to unfold the cauſes or principles. In addreſſing this treatiſe to Gentlemen, I attempt both. This ſuggeſts a diviſion into two parts. In the firſt part, which indeed is the moſt uſeful, the beſt practice in every branch of huſbandry is carefully explained. In the ſecond, with timid ſteps and ſlow, I endeavour to trace out a few cauſes or principles that have an immediate influence upon practice.

# PART I.

## PRACTICE of AGRICULTURE.

IT is unneceſſary here to make a liſt of what is contained in this part. The particulars may be ſeen in the prefixed table.

## CHAPTER I.

## INSTRUMENTS of HUSBANDRY.

IN the natural courſe of ideas, the hand goes before the inſtrument, and the inſtrument before the operation. But as the nature of man is a ſubject too important and too extenſive to be ranged under any other head, I begin this treatiſe of agriculture with the inſtruments it employs.

### 1. The PLOUGH.

THIS is the moſt uſeful inſtrument that ever was invented. It is of more uſe than even the ſpinning-wheel: for men may make a ſhift for cloathing without that inſtrument, but a country cannot be populous without the plough.

The only plough uſed in Scotland, till of late, is a ſtrong heavy inſtrument, about thirteen feet from the handles to the extremity of the beam; and commonly above four feet from the back end of the head to the point of the ſock. It is termed the *Scotch plough*, to diſtinguiſh it from other forms; and it needs no particular deſcription, as it may be ſeen in every field. It may well be termed the *Scotch plough*; for of all forms it is the fitteſt for breaking up ſtiff and rough land, eſpecially where ſtones abound; and no leſs fit for ſtrong clays hardened by drought. The length of its head gives it a firm hold of the ground: its weight prevents it from being thrown out by ſtones: the length of the handles gives the ploughman great command to direct its motion: and by the length of its head, and of its mouldboard, it lays the furrow-ſlice cleverly over. The Scotch plough was contrived during the infancy of agriculture, and was well contrived: in the ſoils above deſcribed, it has not an equal.

But in tender ſoil it is improper, becauſe it adds greatly to the expence of ploughing, without any counterbalancing benefit. The length of the head and mouldboard encreaſe the friction, and conſequently it requires a greater number of oxen or horſes than are neceſſary in a ſhorter plough. There is another particular in its form, that reſiſts the draught: the mouldboard makes an angle with the ſock, inſtead of making a line with it gently curving backward. There is an objection againſt it no leſs ſolid, that it does not ſtir the ground perfectly: the hinder part of the wriſt riſes a foot above the ſole of the head; and the earth that lies immediately below that hinder part, is left unſtirred. This is ribbing land below the ſurface; ſimilar to what is done by ignorant farmers on the ſurface.

Theſe defects muſt be ſubmitted to in a ſoil that requires a ſtrong heavy plough; but may be avoided in a cultivated ſoil by a plough differently conſtructed. Of all the ploughs fitted for a cultivated ſoil free of ſtones, I boldly recommend a plough introduced into Scotland about twelve years ago, by James Small in Blackadder Mount, Berwickſhire; which is now in great requeſt; and with great reaſon, as it avoids all the defects of the Scotch plough. The ſhortneſs of its head and of its mouldboard leſſen the friction greatly: from the point of the ſock to the back part of the head it is only thirty inches; and the whole length, from the point of the beam to the end of the handles, between eight and nine feet. The ſock and mouldboard make one line gently curving; and conſequently gather no earth. Inſtead of a wriſt, the under edge of the mouldboard is in one plain with the ſole of the head; which makes a wide furrow, without leaving any part unſtirred. It is termed the *chain-plough*, becauſe it is drawn by an iron chain fixed to the back part of the beam immediately before the coulter. This has two advantages: firſt, by means of a muzzle it makes the plough go deep, or ſhallow; and next, it ſtreſſes the beam leſs than if fixed to the point, and therefore a ſlenderer beam is ſufficient. Theſe particulars will be better underſtood from inſpecting the annexed figure.

This plough may well be conſidered as a capital improvement; not only by ſaving expence, but by making better work. It is proper for loams, for carſe clays, and, in general, for every ſort of tender ſoil free of ſtones. It is even proper for opening up paſture-ground, where the ſoil has been formerly well cultivated.

To finiſh an account of the plough, I muſt add a word about the ſock. A ſpiked ſock is uſed in the Scotch plough, and is eſſential in ſtony land. But a feathered ſock ought always to be uſed in tender ſoil, free of ſtones; it cuts the earth in the furrow, and makes neat work. It is indiſpenſable in ground where roots abound, as it cuts them below the ſurface, and prevents their growing. I eſteem the feathered ſock to be a valuable improvement. The induſtrious farmer would even borrow money to clear his ground of ſtones, in order to introduce it: in a twenty-years leaſe, the profit of it would repay the expence tenfold.

Some ploughs are made with two ſmall wheels running in the furrow, in order to take off the friction of the head; and this plough is recommended in a book, intitled, *The complete farmer.* But all complicated ploughs are baubles; and this as much as any. The pivots of ſuch wheels are always going wrong; and beſide, they are choked ſo with earth, as to increaſe the friction inſtead of diminiſhing it.

If we look back thirty years, ploughs of different conſtructions did not enter even into a dream. The Scotch plough was univerſally uſed; and no other was known. There was no leſs ignorance as to the number of cattle neceſſary for this plough. In the ſouth of Scotland, ſix oxen and two horſes were univerſal; and in the north, ten oxen, ſometimes twelve. The firſt attempt to leſſen the number of oxen, was in Berwickſhire. The low part of that county abounds with ſtone, clay, and marl; the moſt ſubſtantial of all manures, which had been long uſed by one or two gentlemen. About twenty-five years ago it acquired reputation, and ſpread rapidly. As two horſes and two oxen were employed in every marl-cart; the farmer, in ſummer-fallowing and in preparing land for marl, was confined to four oxen and two horſes. And as that manure afforded plenty of ſucculent ſtraw for oxen, the farmer was ſurpriſed to find, that four oxen did better now than ſix formerly. Marling, however, a laborious work, proceeded ſlowly, till people were taught by a noted farmer in that country, what induſtry can perform by means of power properly applied. It was reckoned a mighty taſk to marl five or ſix acres in a year. That gentleman, by plenty of red clover

for

for his working-cattle, accompliſhed the marling fifty acres in a ſummer, once fifty-four. Having ſo much occaſion for oxen, he tried with ſucceſs two oxen and two horſes in a plough; and that practice became general in Berwickſhire.

Now here appears with luſtre the advantage of the chain-plough. The great friction occaſioned in the Scotch plough by a long head, and by the angle it makes with the mould-board, neceſſarily requires two oxen and two horſes, whatever the ſoil be. The friction is ſo much leſs in the chain-plough, that two good horſes are found ſufficient in every ſoil that is proper for it. And as good luck ſeldom comes alone more than bad, the reducing the draught to a couple of horſes has another advantage, that of rendering a driver unneceſſary; no ſlight ſaving at preſent, where a ſervant's wages and maintenance are very ſmart articles. This ſaving on every plough, where two horſes and two oxen were formerly uſed, will by the ſtricteſt computation be fifteen pounds Sterling yearly; and where four horſes were uſed, no leſs than twenty pounds Sterling. There is now ſcarce to be ſeen in the low country of Berwickſhire a plough with more than two horſes; which undoubtedly in time will become general. I know but of one further improvement, that of uſing two oxen inſtead of two horſes. That draught has been employed with ſucceſs in ſeveral places; and the ſaving is ſo great, that it muſt force its way every where. I boldly affirm, that no ſoil ſtirred in a proper ſeaſon, can ever require more than two horſes and two oxen, in a plough; even ſuppoſing the ſtiffeſt clay. In all other ſoils, two good horſes, or two good oxen abreaſt, may be relied on for every operation of the chain-plough.

A chain-plough of a ſmaller ſize than ordinary, drawn by a ſingle horſe, is of all the moſt proper for horſe-hoeing, ſuppoſing the land to be mellow; which it ought to be for that operation. It is ſufficient for making furrows to receive the dung; for ploughing the drills after dunging, and for hoeing the crop.

A ſtill ſmaller plough of the ſame kind, I warmly recommend for a kitchen-garden. It can be reduced to the ſmalleſt ſize, by being made of iron; and where the land is properly dreſſed for a kitchen-garden, an iron plough drawn by a horſe of the ſmalleſt ſize will ſave much ſpade-work. Strange is the effect of cuſtom without thought! Thirty years ago, a kitchen-garden was an article of luxury merely, becauſe at that time there could be no cheaper food than oat-meal. At preſent, the farmer maintains his ſervants at double expence, as the price of oat-meal is doubled; and yet he has no notion of a kitchen-garden, more than he had thirty years ago. He never thinks, that living partly on cabbage, kail, turnip, carrot, would ſave much oat-meal: nor does he ever think, that change of food is more wholeſome than vegetables alone, or oat-meal alone. I need not recommend potatoes, which in our late ſcanty crops of corn have proved a great bleſſing: without them the labouring poor would frequently have been reduced to a ſtarving condition. Would the farmer but cultivate his kitchen-garden with as much induſtry as he beſtows on his potato-crop, he needed never fear want; and he can cultivate it with the iron plough at a very ſmall expence. It may be held by a boy of twelve or thirteen; and would be a proper education for a ploughman. But it is the landlord who ought to give a beginning to the improvement. A very ſmall expence would encloſe an acre for a kitcken-garden to each of his tenants; and it would excite their induſtry, to beſtow an iron plough on thoſe who do beſt.

Nor is this the only caſe where a ſingle-horſe plough may be profitably employ'd. It is ſufficient for ſeed-furrowing barley, where the land is light and well dreſſed. It may be uſed in the ſecond or third ploughing of fallow, to encourage annual weeds, which are deſtroy'd in ſubſequent ploughings.

To procure food is indeed the chief object of the plough, but not its only object. Good roads are eſſential to internal commerce; and the expence of making them may be conſiderably leſſened by the plough. As this hitherto has been little thought of, an explanation is neceſſary. The method in uſe is, to form a road with the pick, the ſpade, and the wheelbarrow. Even where the pick is not neceſſary, you ſee ten or twelve men preſſing down the ſpade with the foot oftener than once before a ſufficient load of earth can be raiſed;—dearly bought by the workmen, and ſtill more dearly by the employer. Where a pick is neceſſary, there muſt be a great addition of hands; for ten pickmen are no more than ſufficient to looſen what can be thrown up with four or five ſpades. Now a great part of this labour may be ſaved by a plough. The Scotch plough, fortified with iron plates, and the head connected with the beam by a bar of iron, is an excellent inſtrument for making roads. Suppoſe a new road is purpoſed thirty feet wide, plough it up into a ridge, beginning in the middle; and plough it a ſecond time in the ſame manner. Where the ground is ſoft, and requires to be raiſed high, a very deep furrow is neceſſary. Where the ground is firm, a ſhallow furrow is ſufficient. After theſe two ploughings are finiſhed, if the ſides of the road be too ſteep, leave ſix feet in the middle, and go round the remainder in a third ploughing, gathering it toward the top. If the ſides be ſtill too ſteep, leave twelve feet in the middle, and gather up the remainder as in the former ploughing. If theſe operations be well conducted, the water-channels on each ſide of the road will be two feet lower than the ſurface of the adjacent ground. Smooth the road with a brake; and correct with a ſpade any remaining defects or inequalities, which is a very eaſy work. Thus the road is completely formed for a covering of gravel, or of ſtones beat ſmall.

A plough may alſo be uſed advantageouſly in making ditches for encloſing. In hard or gravelly ſoil, the immenſe coſt of picking and ſpading may be totally ſaved by the plough. The ſurface-earth is commonly ſoft: after it is removed with the ſpade, let a plough, drawn by three horſes in a line, go round and round the ſpace intended for the ditch, cleaving it as if it were a ridge. After the earth thus looſened is thrown up with the ſhovel, renew the ploughing and ſhovelling till you come within eight inches of the bottom; and to theſe eight inches apply the pick and ſpade. One precaution is neceſſary, that no more be ploughed at a time than can be thrown up the ſame day. If rain fall in any quantity, the ground tilled will become mud, very improper to be laid upon thorns. In this operation there is no occaſion for the coulter: it is rather an impediment. I eſteem this a valuable diſcovery for Scotland; which being more peſtered with high winds than England, requires more to be encloſed. The expence of incloſing with hedge and ditch the ordinary way, is great; and the ditch is the moſt expenſive part. Two thirds of the expence may

ved by the plough, in ground that requires
ng.

every caſe where earth is to be removed,
lough is uſeful; as for example in a gravel-
pened for high-roads. The gravel may be ſo
ned by the plough as to require a ſhovel only
illing it into the carts.

as any one ſtumbled on the thought of uſing
lough in planting young trees? The method
ve practiſed, is to mark out lines due north
ſouth, at intervals of ten or twelve feet. Let
furrows be made with the plough at the ſide
ch line. Lay the ſod of the eaſtmoſt furrow
the other two, which will raiſe a wall above
feet high. Plant along the furrow from
nce the ſod was removed, and the wall behind

thod here pointed out for planting firs, is the beſt preparation for raiſing all other barren trees.

## 2. The BRAKE.

THE brake is a large and weighty harrow, the purpoſe of which is to reduce a ſtubborn ſoil, where an ordinary harrow makes little impreſſion. It conſiſts of four ſquare bulls, each ſide five inches, and ſix feet and a half in length. The teeth are ſeventeen inches long, bending forward like a coulter. Four of them are inſerted into each bull, fixed above with a ſcrew-nut, having twelve inches free below, with a heel cloſe to the under part of the bull, to prevent it from being puſhed back by ſtones. The nut above makes it eaſy to be taken out for ſharping. This brake requires four horſes or four oxen. One of a leſſer ſize will not fully anſwer the purpoſe: one of a larger ſize will require ſix oxen; in which caſe the work may be performed at leſs expence with the plough. See the figure annexed.

This inſtrument may be applied to great advantage in the following circumſtances. In the fallowing ſtrong clay that requires frequent ploughings, a brakeing between every ploughing, will pulverize the ſoil, and render the ſubſequent ploughings more eaſy. In the month of March or April, when ſtrong ground is ploughed for barley, eſpecially if bound with couch-graſs, a croſs brakeing is preferable to a croſs-ploughing, and is done at half the expence. When ground is ploughed from the ſtate of nature, and after a competent time is croſs-ploughed, the brake is applied with great ſucceſs, immediately after the croſs-ploughing, to reduce the whole to proper tilth.

Let it be obſerved, that a brake with a greater number of teeth than above mentioned, is improper for ground that is bound together by the roots of plants, which is always the caſe of ground new broken up from its natural ſtate. The brake is ſoon choked, and can do no execution till freed from the earth it holds. A leſs number of teeth would be deficient in pulverizing the ſoil.

To ſet in a clear light the advantages of this inſtrument, we will ſtop a little to obſerve how inſufficient the common harrow is for any of the operations mentioned. It may anſwer for covering the ſeed, and may do tolerably well in light and free ſoil; but is altogether inſufficient for reducing ſtiff ſoil. The harrow with wooden teeth is a ridiculous inſtrument, fit to raiſe laughter inſtead of raiſing mould. The poor farmer labours with it, thinks he is doing an uſeful work, when all the time he is doing nothing. It ought to be prohibited by the landlord; for a tenant with ſuch an inſtrument cannot pay a rent that the farm properly cultivated will eaſily bear. Tho' the brake has been known above twenty years, yet none but gentlemen, and a few ſelect tenants, have ever thought of it: in ſome counties even the name remains unknown. It belongs to gentlemen of fortune, for their own intereſt, to make it more general. The neceſſity of ſome inſtrument, more effectual than the common harrow, for reducing a ſtubborn ſoil, has led farmers to put three or four harrows, one above another, in order to preſs the undermoſt into the ground. This ſubſtitute to the brake is far inferior in its effect; beſide, that the undermoſt harrow is torn to pieces in an inſtant. To conclude this article, a farmer who has no brake, wants a capital inſtrument of huſbandry. Its price above that of common harrows, bears no proportion to the profit.

## 3. The HARROW.

HARROWS are commonly conſidered as of no uſe but to cover the ſeed. They have another uſe ſcarce leſs eſſential, which is to prepare land for the ſeed. This is an article of importance for producing a good crop. And to ſhew how imperfectly either of theſe purpoſes is performed by the common harrow, take the following account of it.

The harrow commonly uſed is of different forms. The firſt I ſhall mention has two bulls, four feet long and eighteen inches aſunder, with four wooden teeth in each. A ſecond has three bulls and twelve wooden teeth. A third has four bulls, and twenty teeth, of wood or iron, ten, eleven, or twelve inches aſunder. Now, in fine mould the laſt may be ſufficient for covering the ſeed; but none of them are ſufficient to prepare for the ſeed any ground that requires ſubduing. The only tolerable form is that with iron teeth; and the bare deſcription of its imperfections will ſhew the neceſſity of a more perfect form. In the firſt place, this harrow is by far too light for ground new taken up from the ſtate of nature, for clays hardened with ſpring-drought, or for other ſtubborn ſoils: it floats on the ſurface, and after frequent returns in the ſame track, nothing is done effectually. In the next place, the teeth are too thick ſet, by which the harrow is apt to be choked, eſpecially where the earth is bound with roots, which is commonly the caſe. At the ſame time, the lightneſs and number of teeth keep the harrow upon the ſurface, and prevent one of its capital purpoſes, that of dividing the ſoil. Nor will fewer teeth anſwer for covering the ſeed properly. In the third place, the teeth are too ſhort for reducing a coarſe ſoil to proper tilth; and yet it would be in vain to make them longer, becauſe the harrow is too light for going deep into the ground. Further, the common harrows are ſo ill conſtructed, as to ride at every turn one upon another. Much time is loſt in diſengaging them. What pity is it, that an induſtrious farmer ſhould be reduced to ſuch an imperfect inſtrument, which is neither fit to prepare the ground for ſeed, nor to cover it properly. And I now add, that it is equally unfit for extirpating weeds. The ground is frequently ſo bound with couch-graſs, as to make the furrow-ſlice ſtand upright, as when old lea is ploughed: notwithſtanding much labour, the graſs-roots keep the field, and gain the victory. What follows? The farmer at laſt is reduced to the neceſſity of leaving the weeds in peaceable poſſeſſion, becauſe his field will no longer bear corn.

A little reflection, even without experience, will make it evident, that the ſame harrows, whatever be the form, can never anſwer all the different purpoſes of harrowing, nor can operate equally in all different ſoils, rough or ſmooth, firm or looſe. Looking back not many years above thirty, no farmer in Scotland had the ſlighteſt notion of different ploughs for different purpoſes. The Scotch plough was the only one known. Different ploughs are now introduced; and it is full time to think of different harrows. Rejecting the common harrows, as in every reſpect badly conſtructed, I boldly recommend the following. I uſe three of them of different forms, for different purpoſes. They are all of the ſame weight, drawn each by two horſes. Birch is the beſt wood for them, becauſe it is cheap, and not apt to ſplit. The firſt is compoſed of four bulls, each four feet ten inches long, three and a quarter inches broad, and three and a half deep; the interval between the bulls eleven and three fourths inches; ſo that the breadth of the whole harrow is four feet. The bulls are connected by four ſheths, which go through each bull, and are fixed by timber nails driven through both. In each bull five teeth are inſerted, ten inches free under the bull, and ten inches aſunder. They are of the ſame form with thoſe of the brake, and inſerted into the wood in the ſame manner. Each of theſe teeth is three pounds weight; and where the harrow is made of birch, the weight of the whole is ſix ſtone fourteen pounds Dutch. An erect bridle is fixed at a corner of the harrow, three inches high, with four notches for drawing higher or lower. To this bridle a double tree is fixed for two horſes drawing abreaſt, as in a plough. And to ſtrengthen the harrow, a flat rod of iron is nailed upon the harrow from corner to corner in the line of the draught.

The ſecond harrow conſiſts of two parts, connected together by a crank or hinge in the middle, and two chains of equal length, one at each end, which keep the two parts always parallel, and at the ſame diſtance from each other. The crank is ſo contrived, as to allow the two parts to ply to the ground like two unconnected harrows; but neither of them to riſe above the other, more than if they were a ſingle harrow without a joint.

In

inward; they may form an angle downward, but not upward. Thus they have the effect of two harrows in curved ground, and of one weighty harrow in a plain. This harrow is compoſed of ſix bulls, each four feet long, three inches broad, and three and a half deep. The interval between the bulls nine and a half inches; which makes the breadth of the whole harrow, including the length of the crank, to be five feet five inches. Each bull has five teeth, nine inches free under the wood, and ten inches aſunder. The weight of each tooth is two pounds; the reſt as in the former.

The third conſiſts alſo of two parts, connected together like that laſt mentioned. It has eight bulls, each four feet long, two and a half inches broad, and three deep. The interval between the bulls is eight inches; and the breadth of the whole harrow, including the length of the crank, is ſix feet four inches. In each bull are inſerted five teeth, ſeven inches free under the wood, and ten and a half inches aſunder, each tooth weighing one pound. The reſt as in the two former harrows. The figure of each is annexed.

Theſe harrows I hold to be a conſiderable improvement. They ply to curved ground like two unconnected harrows, and when drawn in one plain, they are in effect one harrow of double weight, which makes the teeth pierce deep into the ground. The imperfection of common harrows, mentioned above, will ſuggeſt the advantages of the ſet of harrows here recommended. The firſt is proper for harrowing land that has lain long after ploughing, as where oats are ſown on a winter-furrow, and in general for harrowing ſtiff land: it pierces deep into the ſoil by its long teeth, and divides it minutely. The ſecond is intended for covering the ſeed; its long teeth lays the ſeed deeper than the common harrow can do; which is no ſlight advantage By placing the ſeed conſiderably under the ſurface, the young plants are, on the one hand, protected from too much heat, and, on the other, have ſufficiency of moiſture. At the ſame time, the ſeed is ſo well covered that none of it is loſt. Seed ſlightly covered by the common harrows, wants moiſture, and is burnt up by the ſun; beſide, that a proportion of it is left upon the ſurface uncovered. The third harrow ſupplies what may be deficient in the ſecond, by ſmoothing the ſurface, and covering the ſeed more accurately. The three harrows make the ground finer and finer, as heckles do lint; or, to uſe a different compariſon, the firſt harrow makes the bed, the ſecond lays the ſeed in it, the third ſmooths the cloaths. Theſe advantages are certain. If any man doubt, let him try the experiment, and he will find the effect of them in his crops. I can ſay ſo with aſſurance from the experience of many years. They have another advantage not inferior to any mentioned;

they mix manure with the ſoil more intimately than can be done by common harrows; and upon ſuch intimate mixture depends greatly the effect of manure, as ſhall be explained afterward. To conclude, theſe harrows are contrived to anſwer an eſtabliſhed principle in agriculture, That fertility depends greatly on pulverizing the ſoil, and on an intimate mixture of manure with it, whether dung, lime, marl, or any other.

## 4. The ROLLER.

THE roller is an inſtrument of capital uſe in huſbandry, though ſcarcely known in ordinary practice; and, where introduced, it is commonly ſo ſlight as to have very little effect.

Rollers are of different kinds, ſtone, yetling, wood. Each of theſe has its advantages. I recommend the laſt, conſtructed in the following manner. Take the body of a tree, ſix feet ten inches long, the larger the better, made as near a perfect cylinder as poſſible. Surround this cylinder with three rows of fillies, one row in the middle, and one at each end. Line theſe fillies with planks of wood equally long with the roller, and ſo narrow as to ply into a circle. Bind them faſt together with iron rings. Beech wood is the beſt, being hard and tough. The roller thus mounted, ought to have a diameter of three feet ten inches. It has a double pair of ſhafts for two horſes abreaſt. Theſe are ſufficient in level ground: in ground not level, four horſes may be neceſſary. The roller without the ſhafts ought to weigh two hundred ſtone Dutch; and the large diameter makes this great weight eaſy to be drawn.

With reſpect to the ſeaſon for rolling. Rolling wheat in the month of April, is an important article in looſe ſoil; as the winter-rains preſſing down the ſoil leave many roots in the air. Barley ought to be rolled immediately after the ſeed is ſown; eſpecially where graſs-ſeeds are ſown with it. The beſt time for rolling a gravelly ſoil, is as ſoon as the mould is ſo dry as to bear the roller without clinging to it. A clay ſoil ought neither to be tilled, harrowed, nor rolled, till the field be perfectly dry. And as rolling a clay ſoil is chiefly intended for ſmoothing the ſurface, a dry ſeaſon may be patiently waited for, even till the crop be three inches high. There is the greater reaſon for this precaution, becauſe much rain immediately after rolling is apt to cake the ſurface when drought follows. Oats in a light ſoil may be rolled immediately after the ſeed is ſown, unleſs the ground be ſo wet as to cling to the roller. In a clay ſoil, delay rolling till the grain be above ground. The proper time for ſowing graſs-ſeeds in an oat-field, is when the grain is three inches high; and rolling ſhould immediately ſucceed whatever the ſoil be. Flax ought to be rolled immediately after ſowing. This ſhould never be neglected; for it makes the ſeed puſh equally, and prevents after growth, the bad effect of which is viſible in every ſtep of the proceſs for dreſſing flax. The firſt year's crop of ſown graſſes ought to be rolled as early the next ſpring as the ground will bear the horſes. It fixes all the roots preciſely as in the caſe of wheat. Rolling the ſecond and third crops in looſe ſoil, is an uſeful work; though not ſo eſſential as rolling the firſt crop.

The effects of rolling properly uſed, are ſubſtantial. In the firſt place, it renders a looſe ſoil more compact and ſolid; which encourages the growth of plants, by making the earth clap cloſe to every part of every root. Nor need we be afraid of rendering the ſoil too compact; for no roller that can be drawn by two or four horſes will have that effect. In the next place, rolling keeps in the moiſture, and hinders drought to penetrate. This effect is of great moment. In a dry ſeaſon, it may make the difference of a good crop, or no crop, eſpecially where the ſoil is light. In the third place, the rolling graſs-ſeeds, beſide the foregoing advantages, facilitates the mowing for hay. And it is to be hoped, that the advantage of this practice will lead farmers to mow their corn alſo, which will encreaſe the quantity of ſtraw, both for food and for the dunghill.

There is a ſmall roller for breaking clods in land intended for barley. The common way is, to break clods with a mell, which requires many hands, and is a laborious work. This roller performs the work more effectually, and at much leſs expence: let a harrowing precede, which will break the clods a little; and after lying a day or a day and half to dry, this roller will diſſolve them into powder. This however does not ſuperſede the uſe of the great roller after all the other articles are finiſhed, in order to make the ſoil compact, and to keep out the ſummer-drought. A ſtone roller four feet long, and fifteen inches diameter, drawn by one horſe, is ſufficient to break clods that are eaſily diſſolved by preſſure. The uſe of this roller in preparing ground for barley is gaining ground daily, even among ordinary tenants, who have become ſenſible both of the expence and toil of uſing wooden mells. But in a clay ſoil, the clods are ſometimes too firm, or too tough, to be ſubdued by ſo light a machine. In that caſe, a roller of the ſame ſize, but of a different conſtruction, is neceſſary. It ought to be ſurrounded with circles of iron, ſix inches aſunder, and ſeven inches deep; which will cut even the moſt ſtubborn clods, and reduce them to powder. Let not this inſtrument be conſidered as a finical refinement. In a ſtiff clay, it may make the difference of a plentiful or ſcanty crop.

### 5. The Fanner.

This inſtrument for winnowing corn was introduced into Scotland not many years ago. Formerly wind being our only reſource, the winnowing of corn was no leſs precarious than the grinding it at a windmill: people often were reduced to famine in the midſt of plenty. There was another bad effect: it was neceſſary to place a barn open to the weſt wind, however irregular or inconvenient the ſituation might be with regard to the other buildings. But it is needleſs to be particular upon that uſeful inſtrument; becauſe every farmer conſiders it now as no leſs eſſential than a plough or a harrow.

## C H A P. II.

## Farm Cattle and Carriages.

### 1. Farm-Horses.

A Horse fit for a waggon, cart, or plough, ought to be ſtrong, compact, and about fifteen hands high. A carter or a ploughman cannot perform the ſame work with horſes of leſs ſize; by which there is a conſiderable loſs, as he is paid by the year, not by the quantity of work he performs. Great attention ought to be given to the breaking a farm-horſe: good education will make him tractable, and obedient to the voice, without neceſſity of applying the whip: the former makes the whole team move at once; the latter moves the horſe only that feels it.

We ſtop a little to conſider the diſadvantage of ſmall and ill-fed horſes, common in Scotland. Two ſtout horſes in a plough will make as deep a furrow as four of what are commonly uſed; and yet the former are leſs expenſive both in price and maintenance. A gentleman cannot do better for his own intereſt, than to promote a good breed of farm-horſes: two good horſes will be a ſaving of L. 8 Sterling yearly, that is expended by uſing four weak horſes. I ſhall mention only the carriage of lime. One ſervant fills his cart with a hundred ſtone, which two good horſes can pull with eaſe. Another lays but the half upon his cart, becauſe his two weak horſes are able for no more. This is a double loſs to the maſter: he gets leſs work, not from the horſes only, but alſo from the ſervant.

## 2. FARM-OXEN.

THERE is not in agriculture any other improvement that equals the uſing oxen inſtead of horſes: they are equally tractable; and they are purchaſed and maintained at much leſs expence. As this improvement is obvious to the meaneſt capacity, one might expect to ſee every farmer greedily embracing it, as he would a feaſt after being famiſhed. Yet few ſtir. How is this to be accounted for? Men are led by cuſtom in chains; and in inſtances without number are fettered againſt their intereſt. "And why ſhould we pretend to be wiſer than our fathers?" they will ſay modeſtly, or rather obſtinately.

What warms me upon this ſubject, is the great conſumption of oats by work-horſes, which would be totally ſaved by uſing oxen only. Did our own product furniſh this conſumption, it were leſs to be regretted; but it is grievous to be reduced to the neceſſity of importing annually vaſt quantities of oats; all of which would be ſaved by employing oxen only in a farm. Nor is this all that would be ſaved, as ſhall be mentioned by and by.

But that I may not be accuſed of declaiming without foundation, I am willing to enter into a candid compariſon between horſes and oxen as employ'd in a farm. I begin with affirming, that an ox is as tractable as a horſe, and as eaſily trained to a plough or a cart. I have ſeen a couple of them in a plough going as ſweetly without a driver as a couple of horſes; directed by the voice alone without a rein. Oxen beſide are preferable for a ſteady draught, as they always pull to their ſtrength, without ever flinching: horſes, on the contrary, are apt to ſtop when they meet with unexpected reſiſtance. As oxen have leſs air and ſpirit in moving than horſes, their motion is concluded to be ſlower. They are leſs expeditious, it is true, in galloping, or perhaps in trotting; but as farm-work is performed by ſtepping, let the ſtep of a horſe and of an ox be compared, and the latter will be found not inferior, eſpecially where an ox is harneſſed like a horſe. Colonel Pool in Derbyſhire ploughs as much ground with three oxen, as the neighbouring farmers do with four or five horſes. In ſummer they eat nothing but graſs: in winter, they have hay or turnip when much wrought; ſtraw only when wrought moderately. About Bawtry, in Yorkſhire, four oxen in a plough do as much work as the ſame number of good horſes. In ſeveral places of Kent, an acre daily is ploughed with a team of oxen, ſometimes a quarter more. Near Beaconsfield, Mr Burke ploughs an acre in a day with four oxen; and his neighbours do no more with four horſes.

Hitherto the compariſon holds pretty equal. In one article oxen are clearly preferable. Their dung makes excellent manure; and by that means they always improve the paſture. Horſe-dung, on the contrary, burns where it falls, and hurts the paſture. Horſe-dung from the ſtable has a greater tendency to burn than to rot; and to make it uſeful, it requires to be carefully mixed with cooler materials.

But the chief advantage of oxen comes under the article of ſavings, which branch out into many particulars. In the firſt place, the price of a horſe fit for labour doubles that of an ox. An ox worth ſeven pounds, will perform as much ſolid work as a horſe worth fourteen. This is an important article: the labouring cattle are the moſt expenſive part of a farm-ſtock; and it is that expence which keeps back from farming, many men whoſe ſkill and induſtry would afford them a comfortable living. In that view, it is greatly the intereſt of landlords to promote oxen, as they tend to multiply candidates for a farm; which not only gives the landlord opportunity for a proper choice, but will raiſe every farm to its juſt value.

As an ox is cheaper than a horſe, ſo he is fed cheaper in proportion. He requires no corn, and he works to perfection upon cut graſs in ſummer, and upon hay in winter. He does well even upon oat-ſtraw. Thus by uſing oxen, a farmer can make money of his whole crop of oats, except what is neceſſary for maintenance of his family. The bulk of that product, on the contrary, is conſumed by farm-horſes. Even in the carſe of Gowry, the conſumption of oats on farm-horſes is ſo great, that at Perth and Dundee there are annually imported between four and five thouſand bolls of oat-meal.

A horſe is liable to many diſeaſes that an ox is free from. If he happen to turn lame, to which he is ſubjected from many accidents, he is rendered uſeleſs. An ox can always be turned to account; for if diſabled from work, he can be fatted for the ſhambles, and can be ſold for more, than was paid for him.

A horſe commonly turns uſeleſs for work in ten years, and the ſtock of horſes muſt be renewed every ten years at a medium, which is a deep article of expence to the farmer. Oxen laſt for ever; or, which comes to the ſame, they can be ſold to the butcher when paſt the vigour of work, and their price will be more than ſufficient to put young oxen in their ſtead.

Horſes require more attendance than oxen: they muſt be curried, combed, and rubbed down. Let oxen have their proper quantity of food, and they require no other care. It is ſufficient employment for a man to manage four or five horſes: he will manage with equal eaſe double the number of oxen.

The ſhoeing of horſes is no inconſiderable article. The expence of ſhoeing oxen is a mere trifle.

Theſe ſeveral articles of ſaving are ſummed up in a following table, and are very conſiderable. This ſum ought to go wholly to the landlord as additional rent. The tenant has no claim for any ſhare; becauſe after paying that additional rent, he has as much profit as he had formerly when he wrought with horſes.

By this mode of huſbandry, the advantage to the landlord is great; and to the kingdom much greater, by ſaving the importation of an immenſe quantity of oats. But the advantage of oxen is ſtill more extenſive: it reaches every manufacturer, and indeed the whole people. There muſt be a great increaſe of oxen to anſwer the purpoſes of farming: every one of theſe, after their prime is over, goes to the ſhambles: the markets are filled with beef, which not only lowers the price of beef, but of leather and tallow. The ſavings upon theſe articles would bring down the wages of our manufacturers, and conſequently the price of our manufactures in a foreign market; not to mention that cheap manufactures at home tend alſo to lower wages.

People differ in the manner of yoking oxen. In ſome places they are yoked by the tip of the horn; in ſome by the root. Theſe modes are viſibly inconvenient. When an ox draws by the ſhoulder like a horſe, his head is free, and his motion natural. When yoked by the horns, he lowers his head to the line of the draught: his poſture is conſtrained, and his ſtep ſhort. His neck indeed is ſtrong, but his ſhoulder is a better *fulcrum* for the draught. To yoke an ox by the ſhoulder, his harneſs ought to be the ſame with that of a horſe. The only difference is, that as his horns hinder the collar from being ſlipped over

ver his head, it muſt be open below, and buckled after it is on.

When the advantages of oxen for draught are ſo great, it cannot but appear ſtrange, that in Britain oxen have almoſt totally been laid aſide. Among the ancients, we read of no beaſts for draught but oxen. It was ſo in Greece, as early as the days of Heſiod; and it was ſo every where. The Dutch at the Cape of Good Hope plough with oxen, and exerciſe them early to a quick pace, ſo as to equal horſes in the waggon, as well as in the plough. They are uſed in the Eaſt Indies for carrying burdens; and they are fitter even than horſes for that ſervice, the back of an ox being convex, and conſequently more able to ſupport a weight than that of a horſe. All that is neceſſary in the furniture for the back, is a bit of wood or ſtiff leather, to prevent the load from falling down upon the neck. The only cauſe I can aſſign for preferring horſes, are bad roads, which were univerſal in Britain till lately. Being impracticable for carts during winter, the farmer carried his corn to market on horſeback. A proper furniture for the back of an ox was not thought of, though an eaſy invention. And horſes being thought neceſſary for carrying burdens, they were employed inſtead of oxen in every work: if employed at all, they are too expenſive ever to be ſuffered to be idle. Another circumſtance contributed. Becauſe oxen require no corn, it is commonly imagined that they ſcarce require any food. They are put off during winter with a bottle of dry ſtraw, which after the turn of the year affords very little nouriſhment. They become too weak for working; and yet, inſtead of bettering their food, it is vainly thought that multiplying their number in a plough will anſwer; and thus may be ſeen in ſeveral places yoked in a plough, ten or twelve weak animals that can ſcarce ſupport their own weight. We are now provided with good roads every where; and there is no longer the pretext of bad roads for preferring horſes. Corn is now carried to market in carts, for which oxen are no leſs proper than horſes. And it is hoped, that farmers will at laſt break through a bad cuſtom, and open their eyes to their own intereſt. Nothing is more deeply their intereſt than to lay aſide horſes totally in farm-operations, and to employ oxen. The tackſman profits firſt; but does not the landlord gain more, by enabling his tenants in new leaſes to pay a higher rent? Why then ſhould gentlemen loiter, while they can ſo eaſily advance their rent without oppreſſing their tenants? Why do they not encourage their tenants by example and precept, to follow a mode that is equally beneficial to themſelves and to their country? It will be hard indeed, if a ſingle tenant cannot be found to ſee his intereſt: if a landlord can prevail but upon one or two of his tenants to take the lead, the reſt will naturally follow. At any rate, he can force them to their own good, by prohibiting horſes in every new leaſe. It is a ſtrange ſort of ambition that moves gentlemen to ſpend their eſtates in the Houſe of Commons, where moſt of them are mere mutes, inſtead of ſerving their country and themſelves at home, which is genuine patriotiſm.

As computation is the touchſtone of profit and loſs, two computations are ſubjoined; one to ſatisfy the farmer of the ſum he will ſave by employing oxen inſtead of horſes; and one to ſhew what benefit will accrue to the public by the change. To ſet the firſt computation in a clear light, and to avoid fractions, I make the ſuppoſition, that a horſe put to work at the age of five may endure hard work for twelve years, which is a large allowance beyond the truth. An ox is put to work at the age of four, and at ſeven is in his prime, which is the proper time to feed for the ſhambles. The computation accordingly is framed upon a revolution of twelve years; during which period oxen are four times changed without any change of horſes. At the end of the period, both muſt be changed; and a new revolution goes on as before.

*TABLE, ſhewing how much a farmer ſaves by employing oxen inſtead of horſes.*

| | L. | s. | d. | L. | s. | d. |
|---|---|---|---|---|---|---|
| A Horſe of 5 years old is purchaſed or valued at | | | | 15 | 0 | 0 |
| To graſing ditto 24 weeks, at 2 s. 1 d. per week | 2 | 10 | 0 | | | |
| To corn in winter 15 weeks, 2 pecks per week, at 8 d. per peck | 1 | 0 | 0 | | | |
| To corn in ſpring 13 weeks, 4 pecks per week, at 10 d. per peck | 2 | 3 | 4 | | | |
| To ſhoeing and farrying one year | 0 | 12 | 6 | | | |
| To inſurance againſt lameneſs and death | 0 | 7 | 6 | | | |
| One year's maintenance | 6 | 13 | 4 | | | |
| Twelve years maintenance | | | | 80 | 0 | 0 |
| Total amount of the firſt coſt, and 12 years maintenance | | | | 95 | 0 | 0 |
| The horſe unfit for hard labour may be ſold for | | | | 3 | 0 | 0 |
| The expence of one horſe at the end of twelve years | | | | 92 | 0 | 0 |

*The expence of an Ox twelve years.*

| | L. | s. | d. | L. | s. | d. |
|---|---|---|---|---|---|---|
| Ox 4 years old purchaſed at - - | | | | 5 | 10 | 0 |
| graſing 24 weeks at 1 s. 6 d. per week - | 1 | 16 | 0 | | | |
| ſhoeing and farrying one year - | 0 | 4 | 6 | | | |
| inſurance againſt accidental death - | 0 | 2 | 6 | | | |
| ount of one year's maintenance - | 2 | 3 | 0 | | | |

By this table it appears, that the yearly expence of a farm-horſe exceeds that of an ox no leſs than L. 6 : 3 : 8. Now ſuppoſing four horſes neceſſary to a farm of 100 acres, rent L. 50 yearly, four good oxen well fed will perform the ſame work; and therefore the uſing the latter inſtead of the former will be an annual ſaving of L. 24, 14 s. 8 d. very near the half of the rent. And what will raiſe it above half of the rent, is the intereſt of the money laid out, which is conſiderably higher upon the horſe than upon the ox; but which is omitted in the foregoing table, to avoid an intricate calculation.

There is beſide an article that preponderates greatly for the ox. His dung enriches the ground on which he paſtures. Horſe-dung, on the contrary, is hurtful. This is an article of great importance.

N. B. The hay or ſtraw conſumed by the horſe in winter is not leſs than that conſumed by the ox; and therefore that article is left out with reſpect to both.

### *Computation of the yearly quantity of oats conſumed in Scotland by labouring horſes.*

FOR repairing the highways in Eaſt Lothian, each ploughgate of land is rated at a certain ſum; and there are in the county computed to be 1331 ploughgates. In every plough four horſes are employed; and many farmers employ additional horſes for harrowing, &c.; but ſuppoſing only four, the number of farm-horſes will be 5924. According to the preceding table, the yearly quantity of corn conſumed by a horſe is 5 bolls 2 pecks; conſequently the amount of the corn conſumed annually is 27,285½ bolls; which, computed at 12 s. a-boll, a moderate price, amounts to the ſum of L. 16,371, 6 s. Sterling.

Reckoning the horſes employed in all the other corn-countries in Scotland, their number will be at leaſt fifteen times as many as what are employed in Eaſt Lothian. Therefore, to find out the value of the oats conſumed in Scotland by work-horſes, multiply the ſaid ſum of L. 16,371, 6 s. Sterling by 16, which is L. 261,940, 16 s.; an immenſe ſum that would be ſaved to this nation by employing oxen in agriculture inſtead of horſes.

If I cannot prevail upon farmers to mind their own intereſt by employing oxen inſtead of horſes, I ſhall at leaſt make them bluſh, by comparing them with farmers no leſs obſtinate in another particular. A farmer was brought from Norfolk to the neighbourhood of Axminſter, who being diſguſted at the huſbandry practiſed there, commenced a better plan. His firſt attempt was, to make turnip a regular crop in rotation, and to hoe them twice in the Norfolk manner. He met with many obſtructions from perverſeneſs and aukwardneſs kindneſs of his ſervants; but by perſeverance, and working with them himſelf, he has prevailed. He now for many years has had exceeding good crops; which at the ſame time have improved the ſucceeding crops of barley. Of theſe facts his neighbours have been witneſſes near twenty years; and yet not one of them has followed his example. Can there be a ſtronger inſtance of prejudice, or rather ſtupidity?

### 3. Breeding Horses and Horned Cattle.

In good huſbandry, the greateſt profit that can be made of graſs is the breeding horſes for ſale. The profit will appear from the following table.

| | | | |
|---|---|---|---|
| The ſtallion, - - - - | L. 0 | 15 | 0 |
| Summer-graſs for the mare and foal, | 2 | 0 | 0 |
| Expence of the foal the firſt winter, | 1 | 15 | 0 |
| Summer-graſs ſecond year, - - - | 1 | 5 | 0 |
| Winter-graſs, - - - - | 0 | 15 | 0 |
| Summer-graſs third year, - - | 1 | 10 | 0 |
| Winter-graſs, - - - - - | 0 | 15 | 0 |
| Summer-graſs fourth year, - - | 1 | 15 | 0 |
| Winter-graſs with corn, - - | 1 | 10 | 0 |
| Total expence, | L. 12 | 0 | 0 |
| Being now riſing five years old, his value, - - - - | 16 | 0 | 0 |
| Clear profit, | L. 4 | 0 | 0 |

A young horſe after the firſt winter need not be houſed till the fourth winter, provided he have a ſhed to fly into in a ſtorm, with a little hay or ſtraw.

It is ſtill more profitable to buy young horſes three years old, and at five to diſpoſe of them, or work them in the farm.

A horſe is a great eater. In common outfield-graſs it will take two acres for his ſummer-paſture. And even where ground has been laid out with graſs-ſeeds, it will take an acre and a half after the ſixth or ſeventh year.

The breeding of horned cattle is alſo profitable, and has a peculiar advantage, viz. that a beaſt bred on a farm, thrives always beſt there. The profit appears from the following table.

| | | | | |
|---|---|---|---|---|
| For the bull, - - - | L. | 0 | 2 | 6 |
| For milk during ſummer, - - | | 1 | 0 | 0 |
| For wintering, - - - | | 0 | 10 | 0 |
| Summer-graſs ſecond year, - | | 0 | 16 | 0 |
| Winter-food, - - - | | 0 | 10 | 0 |
| Summer-graſs third year, - - | | 1 | 4 | 0 |
| Winter-food, - - - - | | 0 | 15 | 0 |
| Total expence, | L. | 4 | 17 | 6 |
| A young bullock entering his fourth year, will ſell for - - | | 7 | 0 | 0 |
| Clear profit, | L. | 2 | 2 | 6 |

4. WHEEL-

## Wheel-Carriages.

Wheel-Carriages for a farm are, waggons drawn by four horſes; carts by one, two, or three horſes; coups with oxen and horſes; and three-wheeled carts with one horſe. Till lately no farm-carriages were known in Scotland, but upon horſe-back; and in many places there are no other carriages.

Whatever ſtrength a horſe may have, yet the weight he can draw is determined by his own weight: in drawing, there is a certain weight that he cannot exceed without being raiſed off the ground; and therefore, to enable him to exert his whole ſtrength, ſome weight ought to be laid on his back. Nothing is more common than to ſee a carter mount the tram-horſe, when hard ſtrained in drawing up-hill. He imagines that he has the horſe more under command; but the true reaſon is, that the horſe draws more by having weight on his back. In the ordinary way of yoking two horſes in a line, the tram-horſe, who is burdened with part of the weight of the cart, draws much more than the horſe before can do. In that view, a cart with double trams, for yoking two horſes abreaſt, muſt be an improvement; becauſe a certain weight may be laid on the back of each, ſo as to enable them on occaſion to exert their utmoſt ſtrength.

I have taken ſome pains to know what can be drawn in a cart without ſtraining the horſes; but I find no uniformity. Two horſes in a cart, yoked in a line, uſually draw, from Borrowſtounneſs to Glaſgow, three thouſand weight. From Stirling to Glaſgow they draw but twenty-four hundred weight. Alexander Monteith, a carter in the neighbourhood of Carron, has, with two horſes, repeatedly drawn from Banton, in the pariſh of Kilſyth, to Carron, four thouſand four hundred weight, each hundred weight conſiſting of one hundred and twenty pounds Avoirdupois. He commonly draws thirty-ſeven or thirty-eight hundred weight. The carts between Borrowſtounneſs and Glaſgow carry from ten to fifteen hundred weight with a ſingle horſe. And with the ſame draught they carry about Edinburgh twelve hundred weight of coals. They carried formerly no more but that weight with two horſes yoked in a line. Mr Orr of Barrowfield, for carrying his coals to market, uſes ſingle-horſe carts with wheels ſix feet high. Every cart carries eaſily twenty-one hundred weight to the place of unloading, which is diſtant from the coal-pit about two Engliſh miles; and this is done ſix times every day. The inequality of theſe weights ſhows the inaccuracy of carters who have not come to any preciſe knowledge of what horſes can perform in a cart. In the mean time, till more exact experiments be made, we ſhall take a middle rate, which is the three thouſand weight drawn by two horſes from Borrowſtounneſs to Glaſgow, the half of which for a ſingle horſe is fifteen hundred weight; though, conſidering the weight that lies upon the back of a ſingle horſe in a cart, his part of the draught may be well computed at ſixteen hundred weight.

This leads to a compariſon between a waggon and ſingle-horſe carts of the ordinary make. To keep within bounds, we may fairly take it for granted, that in a well-conſtructed cart, a ſingle horſe of moderate ſeize will command fourteen hundred weight; conſequently that ſix horſes in ſix carts will draw eight thouſand four hundred weight. Let us now ſee what is drawn in a waggon with ſix horſes. The ordinary weight in this country are four tons, or eight thouſand weight; and I am informed it is the ſame about London. At that rate, ſix horſes in ſix ordinary carts, draw four hundred weight more than ſix horſes in a waggon. At the ſame time, in a turnpike-road, a man and a boy are ſufficient to manage the former as well as the latter.

But, to carry on the compariſon, ſmall carts have another advantage, which is, that they admit high wheels; and it is eaſy to adjuſt the wheels to the height of the horſe, by making the axle go through the middle of the cart, or higher if neceſſary, to make the horſe draw horizontally. It is a great eaſe to the horſe to make the axle go through the centre of gravity; for by that means the weight on the horſe's back is the ſame going up-hill or down-hill. A waggon carrying four or five tons, is incapable of that improvement; for high wheels able to ſupport ſuch a weight, would require a ſtrength of timber that would be intolerable, eſpecially in going up-hill. Here appears in a conſpicuous light the advantage of ſingle carts with high wheels above a waggon. Upon Mr Orr's practice, I take it for granted, that with wheels ſix feet high, a ſingle horſe will carry eaſily twenty-one hundred weight for a whole ſeaſon. But let us ſtate only two thouſand weight, or a ſingle ton, is not the concluſion fair, that in ſuch carts ſix horſes will draw a third more than in a waggon?

Thus, ſingle-horſe carts are clearly preferable to a waggon with reſpect to the burden they can carry; and they are ſtill more preferable with reſpect to the highways. A turnpike-road would be eaſily made, and more eaſily ſupported, were none but ſingle-horſe carts admitted, or were the toll doubled or tripled upon waggons. This ſpeculation merits the moſt ſerious attention of the legiſlature. To preſerve turnpike-roads in perfect order, a ſingle act of parliament would be ſufficient. The Iriſh have taken the lead in this important article. We ought to follow without a moment's delay.

The proportion that ought to be laid on a horſe's ſhoulders to have the greateſt command of the draught, remains to be aſcertained by experiments.

ment. But I gueſs, that a horſe who can draw fourteen hundred weight without any load on his back, will with equal eaſe draw ſixteen hundred, by laying on his back five or ſix ſtone of that weight.

A wheel-carriage is a great ſaving to the farmer, much greater than in a curſory view will be imagined. A cart with two horſes carries five bolls of ſhell-lime. I talk of ordinary carts with two horſes in a line; for two horſes abreaſt in trams will carry much more. The ſame quantity on horſeback requires ſix horſes. To the former one man is ſufficient; to the latter, one to every two horſes. Now, ſuppoſing a man and a cart with two horſes, to be hired for three ſhillings a-day, which is leſs than ordinary, the expence of the lime on horſeback is nine ſhillings; in a cart, no more but three. Here is a ſaving of ſix ſhillings upon every five bolls. And ſuppoſing forty-eight cart-loads of lime to be led in a ſummer, which is a moderate computation even in a farm that employs but a ſingle plough, the ſaving amounts to L. 14, 8 s. which alone is ſufficient to convert a loſing farm into a profitable one. I have been a witneſs to the carrying on horſeback 700 loads of coals, a man to every two horſes; the expence of which amounts to L. 52, 10 s. ſuppoſing a man to be hired at eight pence a-day, and a horſe at fourteen pence. That quantity can be carried in carts with two horſes for L. 21 : 2 : 11. The ſame calculation is applicable to grain. A cart with two horſes will carry to market ſix bolls of barley, which, when carried on horſeback, require ſix horſes. A ſingle plough in tolerable ſoil well cultivated, will afford for ſale a hundred bolls of grain, which carried in carts makes a ſaving of L. 4 Sterling.

The uſe of a three-wheeled cart drawn by a ſingle horſe, is to remove earth, or to carry manure to a near field. One horſe ſerves two of theſe carts: when he returns after unloading, the other is ready filled. But this work is ſo ſevere for a ſingle horſe, that the field ought to be ſmooth and level; or inclining downward, which is ſtill better.

I ſhall only add upon this head, that the ſacks commonly uſed in Scotland for corn, are too heavy. In England ſmall ſacks are uſed, which one man can eaſily load or unload.

## CHAP. III.

## FARM-OFFICES.

IN this country there are few traces of ſkill or contrivance in farm-houſes; no regard to a centric ſituation, nor to a dry ſpot, nor to ventilation. Our farm-offices are ſet down ſtraggling and confuſed as if by accident; here a barn, there a ſtable. Imperfection in form is more excuſable,

cuſable, there being few good examples to copy from: every where to be ſeen cow-houſes ſo aukwardly formed, as that in order to clean them the cattle muſt be turned to the door; and ſo ſtrait that they muſt dung upon each other. And laſtly, after all the labours of the year, no place contrived for keeping corns dry.

Though to a ſtack-yard dryneſs of ſituation and free ventilation are eſſential; yet ſo little are theſe circumſtances regarded, that a ſtack-yard is always adjacent to the dwelling-houſe, whether the ſpot be wet or dry. It is at the ſame time carefully ſurrounded with trees, as if to prevent ventilation, and as if water dropping from the branches on the corn-ſtacks were ſalutary to them.

A kitchen-garden is of importance to a farm, as will appear afterward. There is indeed always a kitchen-garden, but very little attended to. The chief attention is to ſurround it with trees; and yet the neceſſary effect of excluding free air, is to dwarf the plants, and to give them a bad taſte.

It ſeems to be the opinion of our farmers, that a dunghill cannot be too moiſt; for it is commonly put in a hole, and conſequently ſurrounded with water: the richeſt parts are imbibed by the water, and both evaporate together, leaving the dunghill little better than a *caput mortuum*. Water at the ſame time, in any quantity, is far from contributing to putrefaction. I have ſeen a ſheaf of ſtraw, after lying ſix months in water, ſo tough as to be fit for making ropes.

The foregoing defects are but imperfectly remedied in the lateſt conſtructions. The form moſt in requeſt is three ſides of a ſquare; the houſes for the farm-cattle on the eaſt, the barn on the weſt, and ſheds on the north, the dunghill occupying the middle of the ſquare. The ſtables are too far from the barn; the dung lies ſcattered, and trodden upon by the cattle; and the expence of roofing is great.

Theſe particulars are mentioned as an introduction to the following plan; preferable upon two accounts; firſt, as leſs expenſive; and next, as more convenient. The plan is, to erect a houſe of two ſtories, the under ſtory for a ſtable, and the upper for a barn. The door of the ſtable fronts the eaſt; that of the barn the weſt, having a ſtair that leads up to it. The ſtack-yard joins the barn, with free air to the north, weſt, and ſouth. Round this building are ſheds for cattle laid to the walls, with roofs ſloping from the eaſing. The ſheds ſhould be twelve feet wide, ſufficient for the ſize of any farm-beaſt; and the outward wall may be ſeven feet high or ſo. There is place for ſix ſheds, one on each gable, and two on each ſide-wall, leaving an interval for the doors of the barn and ſtable.

There will be found a great ſaving in this plan, compared with the other mentioned. To form a juſt compariſon, they ought to be equally capacious; the two barns ought to be of the ſame ſize, and there ought to be room for the ſame number of cattle. The expence of each is annexed; and the ſaving on the plan recommended is no leſs than L. 94 : 2 : 2 Sterling. This is an important article to every gentleman who poſſeſſes an eſtate in a corn-country; for no article is heavier than the building farm-houſes. Next as to convenience. In the ordinary form, where the barn is on one ſide of a court, and the ſtables on the oppoſite ſide, the time conſumed in carrying ſtraw to the cattle is almoſt entirely ſaved in the plan propoſed; there being holes in the barn-floor over every ſtall, covered with a moveable board, through which ſtraw is let down to the cattle; and this leaves nothing to the ploughman or carter, but to attend to the working of his cattle. In general, ſuch work ought to be avoided that muſt be left to the diſcretion of ſervants to carry on faſt or ſlow, without any effectual check. With reſpect to threſhing, a timber-floor has great elaſticity; and I am made certain from experience, that a third part more may be threſhed on it than on an earthen floor, which has no elaſticity. At the ſame time, the frequent ſweeping of an earth-floor raiſes the finer parts of the earth, which mix with the grain: this is totally prevented in cleaning corn upon a timber-floor. Further, the dampneſs of an earthen floor corrupts the grain; it can-

be kept a fortnight from vegetating, eſpecially if
up to the damp wall. Sacks give no ſecurity;
hey rot if allowed to ſtand in the barn any
. A barn in a ſecond floor is excellent for
enting all theſe evils: one end contains a
of corn, the middle is for threſhing, and the
r end for cleaning the corn when threſhed.
ve this end there is a loft for holding the
ned corn, to which there is eaſy acceſs by a
; and here corn may be kept in ſafety for
ths.

will be objected againſt this plan, that there
court for a dunghill, where winterers are
monly fed. But this I have purpoſely avoid-
for it will be ſeen afterward, in the inſtruc-
s given for the feeding of cattle, that to keep

To form a juſt notion of the propereſt method for preſerving wood, I muſt premiſe, that it will laſt equally well in air and in water; but it muſt be kept conſtantly in the one or the other. What deſtroys wood is the alternate action of air and water. Obſerve a ſtake driven into the ground: the part that conſumes firſt, is not that within the ground, nor that freely out of it, but the ring at the ſurface of the ground, to which air and moiſture have equal acceſs. The ſame where one piece of wood is mortiſed into another: the part that decays firſt, is where the two pieces join, which is open to the air, and at the ſame time lodges moiſture. The ſame is obſerveable in the putrefaction of a dunghill: the parts from which either air or water is excluded, never rot. I muſt premiſe in the next place, that though in a mortiſe the parts joined rot the ſooneſt, yet the mortiſed part, from which both air and water are excluded, decays ſooner than that which is open to the air, ſuppoſing it to be kept dry.

Hence it follows, that to preſerve wood in the moſt perfect manner, it ought to be ſheltered from rain, and expoſed as much as poſſible to the ventilation of dry air. This ſuggeſts the beſt conſtruction of a houſe for preſerving inſtruments of huſbandry. It ought to be erected in the higheſt ſpot, free to every wind: it ought to have a roof ſupported on pillars; the ſides ought to be conſtructed like thoſe of a drying-houſe at a bleach-

field,

field, with moveable boards for admitting air and excluding rain. Three feet or ſo may be left open at bottom; becauſe ſo low down no rain can penetrate to do miſchief. Need I add, that before laying up any inſtrument, it ought to be carefully cleaned and dried?

### *Expence of farm-offices round a farm-yard.*

| | | | |
|---|---|---|---|
| Building 18 roods 2 yards, at L. 1, 5 s. per rood, - - - | L. 23 | 6 | 4 |
| Logwood, 1120 feet, at 12 d. per foot, - - - - | 56 | 0 | 0 |
| Deals, 1148, at 12 d. per yard, | 57 | 8 | 0 |
| Binding the roof and ſarking, at 2 d. per yard, - - - - - | 9 | 11 | 4 |
| Slates, 52,000, at 16 s. per 1000, | 41 | 12 | 0 |
| Nails, 86,000, at 5 s. per 1000, - | 21 | 10 | 0 |
| Slating 31 roods 32 yards, at 16 s. 8 d. per rood, - - - - | 26 | 0 | 10 |
| 8 doors, at 7 s. each, - - | 2 | 16 | 0 |
| | L. 238 | 4 | 6 |

### *Expence of the form recommended.*

| | | | |
|---|---|---|---|
| Building 13 roods 6 yards, at L. 1, 5 s. per rood, - - - | L. 16 | [illegible] | 0 |
| Logwood, 615 feet, at 12 d. per foot, | 30 | 15 | 0 |
| Carried forward, | L. 47 | 3 | 0 |

| | | | |
|---|---|---|---|
| Brought forward, L. | 47 | 3 | 0 |
| Deals for farking, 576 yards, at 12 d. per yard, - - - - | 28 | 16 | 0 |
| Binding the roof, 2 d. per yard, | 4 | 16 | 0 |
| Slates, 32,400, at 16 s. per 1000, - | 25 | 18 | 8 |
| Nails, 43,000, at 5 s. per 1000, - | 10 | 15 | 0 |
| Slating 19 roods 4 yards, at 16 s. 8 d. per rood, - - - - | 16 | 13 | 0 |
| Deals for flooring, 85, at 16 d. each, | 6 | 1 | 8 |
| Laying the floor, 88 yards, at 6 d. per yard, - - - - - | 2 | 4 | 0 |
| Doors 5, at 7 s. each, - - | 1 | 15 | 0 |
| L. | 144 | 2 | 4 |

*N. B.* The expence of the houſe for holding the huſbandry inſtruments, is not taken into this account; becauſe every farm ought to be provided with ſuch a houſe, whatever be the conſtruction of the other farm-offices.

## CHAP. IV.

## PREPARING LAND for CROPPING.

### 1. OBSTRUCTIONS to CROPPING.

IN preparing land for cropping, the firſt thing that occurs to the writer and to the huſbandman, is to conſider the obſtructions to regular ploughing,

ploughing. The moſt formidable of theſe, are ſtones lying above or below the ſurface, which are an impediment to a plough, as rocks are to a ſhip. Did not cuſtom account for it, how ſtrange would it appear, that few proprietors or tenants in Scotland think of clearing their land of ſtones. Stones above the ſurface may be avoided by the ploughman, though not without loſs of ground; but ſtones below the ſurface are commonly not diſcovered till the plough be ſhattered to pieces, and perhaps a day's work loſt. The clearing land of ſtones is therefore neceſſary to prevent miſchief. And to encourage the operation, it is attended with much actual profit. Take the following particulars. The ſtones are uſeful for fences: when large they muſt be blown, and commonly fall into parts proper for building. And as the blowing, when gunpowder is furniſhed, does not exceed a halfpenny for each inch that is bored, theſe ſtones come generally cheaper than to dig as many out of the quarry. In the next place, as the ſoil round a large ſtone is commonly the beſt in the field, it is purchaſed at a low rate by taking out the ſtone. Nor is this a trifle; for not only is the ground loſt that is occupied by a large ſtone, but alſo a conſiderable ſpace round it, to which the plough has not acceſs without danger. A third advantage is greater than all the reſt; which is, that the ploughing can be carried on with much expedition, when there is no apprehenſion occaſion of ſtones: in ſtony land, the plough muſt proceed ſo ſlow, as not to perform half of its work.

To clear land of ſtones, is in many inſtances an undertaking too expenſive for a tenant who has not a very long leaſe. As it is profitable both to him and to his landlord, it appears reaſonable that the work ſhould be divided, where the leaſe exceeds not nineteen years. It falls naturally upon the landlord to be at the expence of blowing the ſtones, and upon the tenant to carry them off the field.

It is vain to think of drawing any conſiderable rent, till a farm be cleared of ſtones. Why then do gentlemen neglect this means of improving their land? In a leaſe, let it be a proviſo, that the landlord or his ſteward be advertiſed of every ſtone that obſtructs the plough. When a number of theſe are marked, let an artiſt be employed to bore and to blow; and the landlord has done his part. I engage that he will make twenty *per cent.* of the money laid out in this operation.

Another obſtruction is wet ground. Water is a good ſervant, but a bad maſter. It may improve gravelly or ſandy ſoils; but it ſours a clay ſoil, and converts low ground into a moraſs, unfit for any purpoſe that can intereſt the huſbandman.

A great deal has been written upon different methods of draining land, moſtly ſo expenſive as to be ſcarce fit for the landlord, not to mention the tenant.

One way of draining without expence when land is to be encloſed with hedge and ditch, is to direct the ditches ſo as to carry off the water. But this method is not always practicable, even where the diviſions lie convenient for it. If the run of water be conſiderable, it will deſtroy the ditches, and lay open the fences, eſpecially where the ſoil is looſe or ſandy.

If ditches will not anſwer, hollow drains are ſometimes made, and ſometimes open drains, which muſt be made ſo deep as to command the water. The former is filled up with looſe ſtones, with bruſh-wood, or with any other porous matter that permits the water to paſs. The latter is left open, and not filled up. To make the former effectual, the ground muſt have ſuch a ſlope as to give the water a briſk courſe. To execute them in level ground is a groſs error: the paſſages are ſoon ſtopped up with ſand and ſediment, and the work rendered uſeleſs. This inconvenience takes not place in open drains: but they are ſubject to other inconveniencies: They are always filling up, to make a yearly reparation neceſſary; and they obſtruct both ploughing and paſturing.

I venture to recommend the following drain as the beſt in all views. It is an open drain made with the plough, cleaving the ſpace intended for the drain over and over, till the furrow be made

of

of a ſufficient depth for carrying off the water. The ſlope on either ſide may by repeated ploughings be made ſo gentle as to give no obſtruction either to the plough or to the harrow. There is no occaſion for a ſpade, unleſs to ſmooth the ſides of the drain, and to remove accidental obſtructions in the bottom. The advantages of this drain are manifold. It is executed at much leſs expence than either of the former; and it is perpetual, as it never can be obſtructed. In level ground, it is true, graſs may grow at the bottom of the drain; but to clear off the graſs once in four or five years, will reſtore it to its original perfection. A hollow drain may be proper between the ſpring-head and the main drain, where the diſtance is not great; but in every other caſe the drain recommended is the beſt.

Where a level field is infeſted with water from higher ground, the water ought to be intercepted by a ditch carried along the foot of the high ground, and terminating in ſome capital drain.

The only way to clear a field of water that is hollow in the middle, is to carry it off by ſome drain ſtill lower. This is commonly the caſe of a moraſs fed with water from higher ground, and kept on the ſurface by a clay bottom.

A clay ſoil of any thickneſs is never peſtered with ſprings; but it is peſtered with rain, which ſettles on the ſurface as in a cup. The only remedy is high narrow ridges, well rounded. And to clear the furrows, the furrow of the foot-ridge ought to be conſiderably lower, in order to carry off the water cleverly. It cannot be made too low; as nothing hurts clay ſoil more than the ſtagnation of water on it; witneſs the hollows at the ends of crooked ridges, which are abſolutely barren. Some gravelly ſoils have a clay bottom, which is a ſubſtantial benefit to a field when in graſs, as it retains moiſture. But when in tillage, ridges are neceſſary to prevent rain from ſettling at the bottom; and this is the only caſe where a gravelly ſoil ought to be ridged.

Clay ſoils that have little or no level, have ſometimes a gravelly bottom. For diſcharging the water, the only method I can think of, is, at the end of every ridge to pierce down to the gravel, which will abſorb the water. But if the furrow of the foot-ridge be low enough to receive all the water, it will be more expeditious to make a few holes in that furrow. In ſome caſes, a field may be drained, by filling up the hollows with earth taken from higher ground. But as this method is expenſive, it will only be taken where no other method anſwers. Where a field happens to be partly wet, partly dry, there ought to be a ſeparation by a middle ridge, if it can be done conveniently. And the dry part may be ploughed, while the other is drying.

The low part of Berwickſhire is generally a brick clay, extremely wet and poachy during winter,

ter. This in a good meaſure may be prevented by proper incloſing, as there is not a field but can be drained into lower ground, all the way down to the river Tweed. But as this would leſſen the quantity of rain in a dry climate, ſuch as is all the eaſt ſide of Britain, it may admit of ſome doubt whether the remedy would not be as bad as the diſeaſe.

Broom and whins are great obſtructions to cropping. Broom is an evergreen ſhrub that thrives beſt in ſandy ſoil; and there it grows ſo vigorouſly, as ſcarce to admit any graſs under it. A plant of broom that has arrived to its full ſize, dies when cut over: but this does not root out broom, becauſe it grows from ſeed lodged in the ground; beſide, that there can be no cropping while the ſtumps remain. An effectual way to root out this plant, is, after cutting the great ſtems cloſe to the ground, to carry them off the field. And the ground may be cleared of the roots, by a Scotch plough with a ſpiked ſock, drawn by two oxen and two horſes.

The field thus cleared may bear a crop of oats, or two; and with proper manure may be continued in tillage, or laid down with the ſeed of paſture-graſſes. The latter is preferable from the nature of the ſoil, which is commonly ſandy.

But as the ſeed of broom lies long in ſuch ſoil without rotting, the farmer may reckon upon a plentiful crop from the ſeed along with the graſs.

To pull up the young broom with the hand, is an expenſive work; and for a large field it is difficult to procure hands. Another method practiſed is, to cut the young broom with a ſythe. But the broom comes up next year in double quantity; for it ſprings from young roots, though not from old.

Sheep are fond of broom, and devour greedily every young ſhoot. In a paſture-field, a few buſhes make a ſhelter; and the cropping of ſheep prevents them in a good meaſure from ſpreading. Broom has a ſingular effect upon ſheep: it makes them drunk ſo effectually, that when heated a little with driving, they tumble over, and lie without motion. This ſuggeſts a method of rooting out the young broom that grows with the paſture-graſſes, which is to paſture the field with ſheep. If any eſcape the firſt year, there will not be left a veſtige after the ſecond. Beſide the eaſineſs of this method, it is profitable, as there is no food more nouriſhing to ſheep than young broom.

Where it is neceſſary or convenient to keep the field in corn, horſe-hoeing is the only way to ſubdue broom. This ſort of huſbandry encourages every ſeed to vegetate; and the frequent ploughings that are neceſſary in a drilled crop, deſtroy broom as well as other weeds. Some may eſcape the firſt year, but they cannot eſcape ſubſequent horſe-hoeing.

A whin is a fine evergreen ſhrub, carrying a ſweet-ſmelling flower all the year, except in froſt. But in huſbandry, beauty is not regarded in oppoſition to profit. This ſhrub ſpreads wonderfully in poor ſoil; and when once eſtabliſhed, requires both art and labour to extirpate it. The roots of broom puſh downward; and for that reaſon, probably, broom ſprings not from the root. The roots of a whin, on the contrary, puſh horizontally, to the diſtance ſometimes of ten or twelve feet. While the plant is growing, it draws the whole juices from the roots; but when cut down, theſe juices puſh up ſuckers from every root that lies near the ſurface. And hence the difficulty of extirpating whins.

The beſt method is, to ſet fire to the whins in a windy day during froſt. Froſt has the effect to wither whins, and to make them burn readily: the harder the froſt, the better. Cut over the ſtumps with a hatchet, and wait till the ground be ſoftened with rain. At that time, a firm plough with a ſtrong draught, will ſhatter all the roots into ſhreds, which will be brought above ground with a heavy brake. The expence of this operation is ſmall, compared with the common method of rooting out whins with a hoe; and it is the leſs to be grudged, as being done in wet weather, when the plough cannot be otherwiſe employed. Oxen are the fitteſt for this operation; becauſe they make a ſteady draught, and do not, like horſes, give way when they meet with unexpected reſiſtance.

If the field be ſoon laid down in graſs, whins will ſpring up in abundance, not only from ſeed, but from the ſmall fibres that may have eſcaped the plough and brake. Paſturing with ſheep is the only remedy: and it is an effectual remedy, if applied immediately after the whins ſpring; for ſheep are no leſs fond of whins than of broom; and if there be a ſufficient number, they will not leave a ſingle plant above ground. Their ſpringing for years need not be repined at; for in their infant ſtate they are excellent food, equal to any plant that grows. If this method be neglected till the whins have grown into wood, ſheep come too late; they will feed on the tender parts, but the buſh continues healthy; of which we have examples every where in open fields.

But if graſs be not immediately wanted, horſe-hoeing huſbandry is the moſt effectual method for clearing a field from whins. And when a field is once enriched by labour and manure, one need not be afraid of whins, as a poor ſoil is only proper for them.

Whins are a food ſo nouriſhing, not only to ſheep but to horned cattle, that a poor ſoil cannot be better employed than in bearing crops of them: they are eat pleaſantly in their infant-ſtate, while the prickles are yet ſo tender as not to hurt the mouth.

Having touched the article of food, though foreign to the preſent chapter, I am excited to obſerve, that the tops of the oldeſt whins, cut off with a hedge-bill, make a hearty food for cattle when boiled. And to encreaſe the doze, thiſtles, every bulky weed, and the roots of cabbage, may be boiled with the whins. This I am informed is an ordinary practice in Germany.

Molehills may be juſtly conſidered as an obſtruction to cropping. It is therefore beneficial to deſtroy moles; and the ſimpleſt way is, to lay hold of the young, which are always found in molehills larger than ordinary. Buffon is uncertain whether they breed more than once a-year; but ſays, that young moles are found from April to Auguſt. What I found, were generally between the firſt of May new ſtyle and the firſt of May old ſtyle.

### 2. BRINGING INTO CULTURE LAND from the STATE of NATURE.

THE following method of improving a moor is contained in a letter addreſſed to me by an expert farmer. "I began with ploughing as much of "the moor as I had a proſpect of dung for. It "was croſs-ploughed next ſpring, and well harrowed. About Midſummer, it was ploughed "again in the direction of the firſt ploughing, and "well harrowed. It was ploughed the fourth

" time before winter, but not harrowed. It got " the fifth ploughing in the ſucceeding April, at " which time the ſward was well broken and rot" ted. It was dunged liberally; and after plough" ing the dung into the ground, I ſowed turnip. " New ground, however poor originally, never " diſappointed me of a rich crop of turnip the firſt " year, barley or oats the ſecond, and clover and " rye-graſs the third. And yet there are ſeveral " late inſtances of turnip failing in the beſt infield " grounds, among my neighbours and in my own " farm. In the year 1759, unwilling to truſt the " whole of my turnip-crop to the moor, I prepared " and dunged part of my beſt infield, and ſowed " it with turnip. Not a ſingle drill appeared from " the firſt ſowing; and but a ſcanty crop from " the third: in the moor not a ſingle drill failed. " I was anxious to diſcover the cauſe: I could " not attribute the difference to ſoil or ſituation, " which were in favour of the infield; and the " management was the ſame. The black fly, it " is true, had deſtroyed the infield crop; but I " was puzzled why they had abſtained from the " moor. Upon examining narrowly the two " fields, I diſcovered that the black flies in the " infield were young and very ſmall, not able to " fly, but only to creep or hop about. Not a " ſingle fly could be ſeen in the moor. This led " me to the following ſpeculation. Nature has " taught the various tribes of flies and inſects, to

" depoſit their eggs in places the beſt adapted for
" the production and nouriſhment of their young.
" Warm and rich grounds anſwer theſe purpoſes
" the beſt: moor-grounds are cold and barren.
" I reflected further, that when once theſe inſects
" chuſe for their habitation a rich ſoil where there
" is plenty of food, they depoſit their eggs there;
" and the race is propagated from year to year.
" A vacuity of ten or twelve yards in one of the
" moor-drills ſeemed not to ſquare with my theory.
" But upon enquiry I found, that a ſmall
" ſhower of rain had ſtopped the holes of the
" drill-box a little time."

So far my correſpondent. His method is good; but it is laborious; and the ſoil with three ploughings may be rendered as proper for turnip, as with the ſix he gave it. The following alteration is what I propoſe. Let the moor be opened in winter when it is wet; which has one convenience, that the plough cannot be employed at any other work. In ſpring, after froſt is over, a ſlight harrowing will fill up the ſeams with mould, to keep out the air and rot the ſod. In that ſtate let it lie the following ſummer and winter, which will rot the ſod more than if laid open to the air by ploughing. Next April, let it be croſs-ploughed, braked, and harrowed, till it be ſufficiently pulverized. Let the manure laid upon it, whether lime or dung, be intimately mixed with the ſoil by repeated harrowings. This will make a fine bed for the turnip-ſeed, if ſown broad-caſt. But if drills be intended, the method muſt be followed that is directed afterward in treating more directly of the culture of turnip.

Repeated experience has convinced me, that turnip in mooriſh ground runs no riſk from the black fly, nor probably in any ground newly broken up. It is an old obſervation of gardeners, that their plants thrive beſt in new ground; for what other reaſon, than that they have no enemies to deſtroy them? It muſt give pleaſure to thoſe who wiſh proſperity to their country, to be informed, that mooriſh grounds of a tolerable ſoil are fit for producing turnip; a profitable crop of itſelf, and ſtill more profitable by preparing the ground for ſubſequent crops. Conſidering the immenſe quantity of moor in Scotland, it muſt give pain to think how little progreſs is made in its cultivation. We ſee a fair example given near twenty years ago, neither expenſive nor intricate. Why does not every farmer exert his utmoſt induſtry upon ſo valuable an improvement? Cuſtom fetters men in chains. To break looſe from ſlavery, a man muſt be bleſſed by nature with a ſuperior degree of underſtanding and activity. Such men there are, though rare: their example will be imitated; and it is a pleaſing proſpect, that our barren moors will in time be converted into good ſoil, productive of nouriſhment for man and beaſt: villages will ariſe, and population go on its in a rapid courſe. I preſent to the view of my reader an immenſe moor between Greenlaw in Berwickſhire, and Fala in Mid Lothian, as a deſireable ſubject for an improving farmer, now that there is acceſs to lime by a turnpike-road. As the ſoil for the moſt part is too ſhallow for paring and burning, it may be cultivated according to the directions given above. At the ſame time there are many ſwampy ſpots, which upon paring and burning will yield a great quantity of aſhes, to be laid upon the dry parts; and theſe aſhes make the very beſt manure for turnip. The method for preparing ſwampy land for turnip is deſcribed below, in treating upon the culture of turnip. A ſucceſsful turnip-crop, fed on the ground with ſheep, is a fine preparation for laying down a field with graſs-ſeeds. It is an improvement upon this method, to take two or three ſucceſſive crops of turnip, which will require no dung for the ſecond and following crops. This will thicken the ſoil, and enrich it greatly. In that high country, where rain ſuperabounds, the profitable crop is graſs, not corn. And farms in that country, after being improved, ought to be divided into incloſures of fifty or ſixty acres. Sheep require a hundred acres, to give them ſpace for an extenſive walk; and in ſuch an incloſure any fence keeps them in *.

The

---

* Scotland probably was moſtly covered with trees before

The beſt way of improving ſwampy ground after draining, is paring and burning. But where the ground is dry, and the ſoil ſo thin as that the ſurface cannot be pared, the beſt way of bringing it into tilth from the ſtate of nature, as mentioned above, is to plough it with a feathered ſock, laying the graſſy ſurface under. After the new ſurface is mellowed with froſt, fill up all the ſeams by harrowing croſs the field, which by excluding the air will effectually rot the ſod. In this ſtate let it lie ſummer and winter. In the beginning of May after, a croſs ploughing will reduce all to ſmall ſquare pieces, which muſt be pulverized with the brake, and make it ready for a May or June crop. If theſe ſquare pieces be allowed to lie long in the ſap without brakeing, they will become tough and not be eaſily reduced.

### 3. FORMING RIDGES.

THE firſt thing that occurs on this head, is to conſider what grounds ought to be formed into

---

before the commencement of agriculture; from which we ought to expect its ſurface to be generally vegetable ſoil. Yet moſt of it is barren earth, without any mixture of vegetable ſoil. Did ſuch large tracts never carry trees? I can hardly think ſo, as trees are found growing in the moſt barren ſpots. Yet in America, which abounds with trees, one in ſome places may travel ſeveral hundred miles without ſeeing a tree. This appears difficult to be accounted for.

ridges, and what ought to be tilled with a flat ſurface. Dry ſoils, which ſuffer by lack of moiſture, ought to be tilled flat, which tends to retain moiſture. And the method for ſuch tilling, is to go round and round from the circumference to the centre, or from the centre to the circumference. This method is advantageous in point of expedition, as the whole is finiſhed without once turning the plough. At the ſame time, every inch of the ſoil is moved, inſtead of leaving either the crown or the furrow unmoved, as is commonly done in tilling ridges. Clay ſoil, which ſuffers by water ſtanding on it, ought to be laid as dry as poſſible by proper ridges. A loamy ſoil is the middle between the two mentioned. It ought to be tilled flat in a dry country, eſpecially if it incline to the ſoil firſt mentioned. In a moiſt country, it ought to be formed into ridges, high or low according to the degree of moiſture, and tendency to clay.

In grounds that require ridging, an error prevails, that ridges cannot be raiſed too high. High ridges labour under ſeveral diſadvantages. The ſoil is heaped upon the crown, leaving the furrows bare: the crown is too dry, and the furrows too wet: the crop, which is always beſt on the crown, is more readily ſhaken with the wind, than where the whole crop is of an equal height: the half of the ridge is always covered from the ſun, a diſadvantage which is far from being ſlight in a cold climate,

climate. High ridges labour under another diſadvantage in ground that has no more level than barely ſufficient to carry off water: they ſink the furrows below the level of the ground; and conſequently retain water at the end of every ridge. The furrows ought never to be ſunk below the level of the ground. Water will more effectually be carried off, by leſſening the ridges both in height and breadth: a narrow ridge, the crown of which is but eighteen inches higher than the furrow, has a greater ſlope, than a very broad ridge where the difference is three or four feet.

Next of forming ridges where the ground hangs conſiderably. Ridges may be too ſteep as well as too horizontal; and if to the ridges be given all the ſteepneſs of a field, a heavy ſhower may do irreparable miſchief. One inſtance I was witneſs to. A hanging field had been carefully dreſſed with lime and dung for turnip. The turnip was fairly above ground, when a fatal ſummer-ſhower ſweeped down turnip, lime, dung, and a quantity of the tender ſoil, leaving the land bare. To prevent ſuch miſchief, the ridges ought to be ſo directed croſs the field, as to have a gentle ſlope for carrying off water ſlowly, and no more. In that reſpect, a hanging field has greatly the advantage of one that is nearly horizontal; becauſe in the latter, there is no opportunity of a choice in forming the ridges. A hill is of all the beſt adapted for directing the ridges properly. If the ſoil be gravelly, it may be ploughed round and round, beginning at the bottom and aſcending gradually to the top in a ſpiral line. This method of ploughing a hill, requires no more force than ploughing on a level; and at the ſame time removes the great inconvenience of a gravelly hill, that rain goes off too quickly; for the rain is retained in every furrow. If the ſoil be ſuch as to require ridges, they may be directed to any ſlope that is proper.

In order to form a field into ridges that has not been formerly cultivated, the rules mentioned are eaſily put in execution. But what if ridges be already formed, that are either crooked or too high? After ſeeing the advantage of forming a field into ridges, people were naturally led into an error, that the higher the better. But what could tempt them to make their ridges crooked? I anſwer, Not of deſign, but by the lazineſs of the driver ſuffering the cattle to turn too haſtily, inſtead of making them finiſh the ridge without turning. There is more than one diſadvantage in this ſlovenly practice. Firſt, the water is kept in by the curve at the end of every ridge, and ſours the ground. Next, as a plough has the leaſt friction poſſible in a ſtraight line, the friction muſt be increaſed in a curve, the back part of the mouldboard preſſing hard on the one hand, and the coulter preſſing hard on the other. In the third place, the plough moving in a ſtraight line, has the greateſt command in laying the earth over.

But where the ſtraight line of the plough is applied to the curvature of a ridge in order to heighten it by gathering, the earth moved by the plough is continually falling back, in ſpite of the moſt ſkilful ploughman.

The inconveniencies of ridges high and crooked, are ſo many, that one would be tempted to apply a remedy at any riſk. And yet, if the ſoil be clay, I would not adviſe a tenant to apply the remedy upon a leaſe ſhorter than two nineteen years. In a dry gravelly ſoil, the work is not difficult, nor hazardous. When the ridges are cleaved two or three years ſucceſſively in the courſe of cropping, the operation ought to be concluded in one ſummer. The earth, by reiterated ploughings, ſhould be accumulated upon the furrows, ſo as to raiſe them higher than the crowns: they cannot be raiſed too high, for the accumulated earth will ſubſide by its own weight. Croſs-ploughing once or twice, will reduce the ground to a flat ſurface, and give opportunity to form ridges at will. The ſame method brings down ridges in clay ſoil: only let care be taken to carry on the work with expedition; becauſe a hearty ſhower before the new ridges are formed, would ſoak the ground in water, and make the farmer ſuſpend his work for the remainder of that year at leaſt. In a ſtrong clay, I would not venture to alter the ridges, unleſs it can be done to perfection in one ſeaſon.

In the operation of flattening ridges, there is a circumſtance that has ſcarce ever been attended to. Ridges are evidently an improvement of art; and ſo is manure. The ſoil muſt have been exhauſted by frequent cropping before either ridges or dung were attempted; and after ridges were formed, the ſoil under the crowns muſt have continued in its exhauſted ſtate, being deprived of the benefit both of ſun and rain. We find theſe conjectures verified by experience. When a ridged field is made level as originally, the ſoil immediately under the crown, which had the thickeſt covering, is commonly exceedingly poor. Farmers, ſenſible of this, never fail to give more dung to that part than to the reſt of the field. But a more effectual remedy is, to pierce deeper than the original ſurface with the ſpade or plough, in order to bring up virgin ſoil. This ſoil is generally good; and the whole is made equally fertile, by mixing it with the exhauſted ſoil in croſs ploughing and harrowing. In the low country of Berwickſhire, I frequently uſed this remedy, and never was diſappointed. In making ditches there for draining, I have brought up a brick-clay lying four feet under the ſurface, which, without being mellowed either by ſun or froſt, carried oats of a ſurpriſing ſize. Wild plants may be ſeen every where much larger than ordinary, growing even in gravel thrown up from the bottom of a new-made ditch.

Let it be a rule, to direct the ridges north and ſouth if the ground will permit. In this direction, the eaſt and weſt ſides of the ridges, dividing the ſun equally between them, will ripen at the ſame time.

It is a great advantage in agriculture, to form ridges ſo narrow, and ſo low, as to admit the crowns and furrows to be changed alternately every crop. The ſoil neareſt the ſurface is the beſt; and by ſuch ploughing, it is always kept near the ſurface, and never buried. In high ridges, the ſoil is accumulated at the crown, and the furrows left bare. Such alteration of crown and furrow, is eaſy where the ridges are no more but ſeven or eight feet broad. This mode of ploughing anſwers perfectly well in ſandy and gravelly ſoils, and even in loam. But it is not ſafe in clay ſoil. In that ſoil, the ridges ought to be twelve feet wide and twenty inches high; to be preſerved always in the ſame form by caſting, that is, by ploughing two ridges together, beginning at the furrow that ſeparates them, and ploughing round and round till the two ridges be finiſhed. By this method, the ſeparating furrow is raiſed a little higher than the furrows that bound the two ridges. But at the next ploughing, that inequality is corrected, by beginning at the bounding furrows, and going round and round till the ploughing of the two ridges be completed at the ſeparating furrow.

4. CLEAR-

## CLEARING GROUND of WEEDS.

THE farmer views plants in a very different light from the botaniſt. All are weeds with the farmer, that give obſtruction to the plants he propagates in his farm. Theſe I diſtinguiſh into two kinds, that require different management, viz.—annuals,—and all that have a longer exiſtence, which I ſhall comprehend under the general name of *perennials*. It is vain to expect a crop of corn from land over-run with couch-graſs, knot-graſs, or other perennial weeds; and yet the time may be remembered, when, among Scotch farmers, it was a diſputed point, whether ſuch weeds were not more profitable than hurtful. Some found them profitable in binding their light land: the getting a plentiful crop of ſtraw and hay for their cattle, weighed with others. I ſhould be aſhamed of expoſing ignorance ſo groſs in my countrymen, could I not ſay, that they now underſtand the matter better, though few of them hitherto have arrived at the perfection of cleaning. Summer-fallow is the general method; and excellent it is, though it doth not always prove effectual. The roots of couch-graſs in particular are long, and full of juice: if a ſingle joint be left in the ground, it never fails to ſpring. Here the common harrow is of very little uſe, its teeth being too wide. The time relied on by our farmers for deſtroying couch-graſs, is in preparing for barley. After the harrow has raiſed part of a root above ground, men, women, and children, are employed to pull it up. There are only two objections to this method: the expence is one; and another is, that after all this expence, many roots are left in the ground. In order to pave the way for rooting out perennials effectually, and with little expence, I take liberty to introduce a new inſtrument, which I term a *cleaning harrow*. It is of one entire piece, like the firſt of thoſe mentioned above, conſiſting of ſeven bulls, four feet long each, two and one fourth inches broad, two and three fourths deep. The bulls are united together by ſheths, ſimilar to what are mentioned above. The intervals between the bulls being three and three fourths inches, the breadth of the whole harrow is three feet five inches. In each bull are inſerted eight teeth, each nine inches free below the wood, and diſtant from each other ſix inches. The weight of each tooth is a pound, or near it. The whole is firmly bound by an iron plate from corner to corner in the line of the draught. The reſt as in the harrows mentioned above. The ſize, however, is not invariable. The cleaning harrow ought to be larger or leſs according as the ſoil is ſtiff or free. See the figure annexed.

To give this inſtrument its full effect, ſtones of ſuch a ſize as not to paſs freely between the teeth, ought to be carried off, and clods of that ſize ought to be broken. The ground ought to be dry, which it is commonly in the month of May.

In preparing for barley, turnip, or other ſummer-crop, begin with ploughing and croſs-ploughing. If the ground be not ſufficiently pulveriſed, let the great brake be applied, to be followed ſucceſſively with the harrows, N° 1. and N° 2. In ſtiff ſoil rolling may be proper, once or twice between the acts. Theſe operations will looſen every root, and bring ſome of them to the ſurface. This is the time for the harrow, N° 3. conducted by a boy mounted on one of the horſes, who trots ſmartly along the field, and brings all the roots to the ſurface: there they are to lie for a day or two till perfectly dry. If any ſtones or clods remain, they muſt be carried off in a cart. And now ſucceeds the operation of the cleaning harrow. It is drawn by a ſingle horſe, directed by reins, which the man at the oppoſite corner puts over his head, in order to have both hands free. In this corner is fixed a rope, with which the man from time to time raiſes the harrow from the ground, to let the weeds drop. For the ſake of expedition, the weeds ought to be dropt in a ſtraight line croſs the field, whether the harrow be full or not; and ſeldom is a field ſo dirty but that the harrow may go thirty yards before the teeth are filled. The weeds will be thus laid in parallel rows, like thoſe of hay raked together for drying. A harrow may be drawn ſwiftly along the rows, in order to ſhake out all the duſt; and then the weeds may be carried clean off the field in carts. But we are not yet done with theſe weeds: inſtead of burning, which is the ordinary practice, they may be converted into uſeful manure, by laying them in a heap with a mixture of hot dung to begin fermentation. What better politic than to make a friend of a foe! At firſt view, this way of cleaning land will appear operoſe; but upon trial, neither the labour nor expence will be found immoderate. So far from it, that I believe it will not be eaſy to name any other way of cleaning ground effectually, that coſts ſo little. At any rate, the labour and expence ought not to be grudged; for if a field be once thoroughly cleaned, the ſeaſons muſt be very croſs, or the farmer very indolent, to make it neceſſary to renew the operation in leſs than twenty years. In the worſt ſeaſons, a few years paſture is always under command; which effectually deſtroys triennial plants, ſuch as thiſtles and couch-graſs.

Fog is one of the moſt pernicious weeds that enter into a graſs-field: in a very dry ſoil, it uſurps upon the good plants, wears them out, and covers the whole ſurface. I have tried lime and dung to very little purpoſe. Coal-aſhes do better: they keep back the fog a few years; but it recovers ſtrength gradually as the aſhes loſe their influence, and prevails as much as before. Some writers talk of rolling, becauſe fog is never ſeen on a foot-path. They do not advert, that the continual treading of feet on a narrow path, conſolidates the ground more, and makes it more retentive of moiſture, than rolling can do. Nor do they advert, that fog is the moſt plentiful in dry ground, where the weightieſt roller makes no impreſſion. As fog proſpers the moſt on the drieſt ground, the laying the field under water a whole winter, will deſtroy it. There is reaſon however to ſuſpect, that the fog will encroach again, when the moiſture is exhauſted, and the ſoil returns to its arid ſtate; not to mention the many fields that lie out of the reach of water. One infallible method there is; which is, to cover the ground an inch thick with ſoil retentive of moiſture, and to mix it with the original ſoil by the plough and harrow. Thus will fog be baniſhed, and the ſoil at the ſame time enriched. But the good ſoil here muſt be at hand; it would be too expenſive to bring it from a diſtance. Lucky it is, after all, that there ſtill remains an infallible method, which, inſtead of being expenſive, is extremely profitable. It will be made evident afterward, in laying down rules for rotation of crops, that a quick ſucceſſion of corn and graſs, is more profitable, than to allow any ground to continue long in either. Therefore, as ſoon as fog begins to prevail, plough up the ground for a crop of corn *.

Next, of annual weeds, which are propagated by ſeed. As ſeeds cannot be gathered out of the ground like roots, the only way of deſtroying them, is to promote their vegetation; which lays them open to be extirpated by the plough or harrow. For want of induſtry, annual weeds prevail in many parts of this iſland, in the beſt ſoils eſpecially. To view a crop near a town, end of May or beginning of June, one would believe it to be a crop of charlock or wild muſtard. Theſe plants, it is true, loſe their ſplendid appearance after their flowering is over; but they remain to encumber the ground. As they ripen, and drop their ſeed long before the corn is ripe, they multiply more and more. They not only rob the ground, and ſtarve the good grain, but prevent circulation of air about the roots, which is a great impediment to vegetation. Freedom of circulation is one of the cauſes that make drilled crops ſucceed ſo well. What muſt have been the con-

---

* The following method is propoſed by Dr Home for deſtroying fog. "Shut up the incloſure from the middle of May till the beginning of December; feed it till April, and then ſave it for a crop of hay. The fog, being ſo long covered with graſs, is cut off from the benefit of the air, and dies." I doubt. Overſhadowing the fog may retard its progreſs; but as it does not correct the dryneſs of the ſoil, it is not likely to extirpate the fog.

dition of corn-land in Scotland before fallowing was known!

And now to the deſtruction of ſuch weeds. Summer-fallow, among its other advantages, does this effectually, by obſerving the following method. Begin with ploughing in April as ſoon as the ground is dry; and let the brake ſucceed croſs the field; which by pulveriſing the ſoil, will promote the vegetation of every ſeed. As ſoon as the weeds appear, which may be in ten or twelve days according to the ſeaſon, plough and brake as before: the plough will make many ſeeds vegetate; the brake ſtill more. Proceed in the ſame courſe while any weeds appear. In the heat of ſummer, rolling not only promotes vegetation by keeping in the moiſture, but bruiſes the clods which lock up many ſeeds.

This proceſs requires the following precaution. Avoid ploughing or brakeing when the ground is wet. The ſtirring wet ground hardens it, excludes the ſun and air, and prevents vegetation.

## CHAP. V.

## CULTURE OF PLANTS FOR FOOD.

THE articles hitherto inſiſted on, are all of them preparatory to the capital object of a farm, that of raiſing plants for the nouriſhment of

man,

man, and of other animals. Theſe are of two kinds; culmiferous, and leguminous, differing widely from each other. Wheat, rye, barley, oats, ryegraſs, are of the firſt kind: of the other kind are peaſe, beans, clover, cabbage, and many others. Culmiferous plants, ſays Bonnet, have three ſets of roots. The firſt iſſue from the ſeed, and puſh to the ſurface an upright ſtem; another ſet iſſue from a knot in that ſtem; and a third, from another knot, nearer the ſurface. Hence the advantage of laying ſeed ſo deep in the ground as to afford ſpace for all the ſets. Leguminous plants form their roots differently. Peaſe, beans, cabbage, have ſtore of ſmall roots, all iſſuing from the ſeed, like the undermoſt ſet of culmiferous roots; and they have no other roots. A potato and a turnip have bulbous roots. Red clover has a ſtrong tap-root. The difference between culmiferous and leguminous plants with reſpect to the effects they produce in the ſoil, will be inſiſted on afterward, in the chapter concerning rotation of crops. As the preſent chapter is confined to the propagation of plants, it falls naturally to be divided into three ſections: Firſt, plants cultivated for fruit; Second, plants cultivated for roots; Third, plants cultivated for leaves.

## SECTION I.

### PLANTS CULTIVATED FOR FRUIT.

WHEAT, oats, barley, beans, and peaſe, are the plants that are moſtly cultivated in Scotland for fruit. I begin with wheat.

### 1. WHEAT and RYE.

ANY time from the middle of April to the middle of May, the fallowing for wheat may commence. The moment ſhould be choſen, when the ground, beginning to dry, has yet ſome remaining ſoftneſs: in that condition, the ſoil divides eaſily by the plough, and falls into ſmall parts. This is an eſſential article, deſerving the ſtricteſt attention of the farmer. Ground ploughed too wet, riſes, as we ſay, *whole-fur*, as when paſture-ground is ploughed: where ploughed too dry, it riſes in great lumps, which are not reduced by ſubſequent ploughings; not to mention, that it requires double force to plough ground too dry, and that the plough is often broken to pieces. When the ground is in proper order, the farmer can have no excuſe for delaying a ſingle minute. This firſt courſe of fallow, muſt, it is true, yield to the barley-ſeed; but as the barley-ſeed is commonly over the firſt week of May, or ſooner, the ſeaſon muſt be unfavourable if the fallow cannot be reached by the middle of May.

As clay ſoil requires high ridges, theſe ought to be cleaved at the firſt ploughing, beginning at the furrow, and ending at the crown. This ploughing ought to be as deep as the ſoil will admit; and water-furrowing ought inſtantly to follow: for if rain happen before water-furrowing, it ſtagnates in the furrow, neceſſarily delays the ſecond ploughing till that part of the ridge be dry, and prevents the furrow from being mellowed, and roaſted by the ſun. If this firſt ploughing be well executed, annual weeds will riſe in plenty. About the firſt week of June, the great brake will looſen and reduce the ſoil, encourage a ſecond crop of annuals, and raiſe to the ſurface the roots of weeds moved by the plough. Give the weeds time to ſpring, which may be in two or three weeks. Then proceed to the ſecond ploughing about the beginning of July; which muſt be croſs the ridges, in order to reach all the ſlips of the former ploughing. By croſs-ploughing, the furrows will be filled up, and water-furrowing be ſtill more neceſſary than before. Employ the brake again about the 10th of Auguſt, to deſtroy the annuals that have ſprung ſince the laſt ſtirring. The deſtruction of weeds is a capital article in fallowing: yet ſo blind are people to their intereſt, that nothing is more common, than a fallow field covered with charlock and wild muſtard, all in flower, and ten or twelve inches high. The field having now received two harrowings and two brakeings, is prepared for manure, whether lime or dung, which without delay ought to be incorporated with the ſoil, by repeated harrowing and a gathering furrow. This ought to be about the beginning of September; and as ſoon after as you pleaſe the ſeed may be ſown.

As in ploughing a clay ſoil it is of importance to prevent poaching, the hinting furrows ought to be done with two horſes in a line. If four ploughs be employed in the ſame field, to one of them may be allotted the care of finiſhing the hinting furrows. What will one think, who has never been in the Highlands, of four horſes abreaſt in a plough, the driver going backward, and ſtriking the horſes on the head to make them come forward? The ignorant and illiterate are ſtrangely dull in point of invention: but let the moſt ſtupid practice turn once cuſtomary, and it is rivetted in them for ever. Is it not obvious, that four horſes abreaſt muſt tread down the new-moved ſoil, and reduce it to as firm a ſtate as before the plough entered?

Next of dreſſing loam for wheat. Loam, being a medium between ſand and clay, is of all ſoils the fitteſt for culture, and the leaſt ſubject to chances. It does not hold water like clay; and when wet it dries ſooner. At the ſame time it is more retentive than ſand of that degree of moiſture which promotes vegetation. On the other hand, it is more ſubject to couch-graſs than clay, and to other weeds; to deſtroy which, fallowing is ſtill more neceſſary than in clay.

Beginning the fallow about the firſt of May, or as ſoon as barley-ſeed is over, take as deep a furrow as the ſoil will admit. Where the ridges are ſo low and narrow as that the crown and furrow can be changed alternately, there is little or no occaſion for water-furrowing. Where the ridges are ſo high as to make it proper to cleave them, water-furrowing is proper. The ſecond ploughing may be at the diſtance of five weeks. Two crops of annuals may be got in the interim, the firſt by the brake, and the next by the harrow; and by the ſame means eight crops may be got in the ſeaſon. The ground muſt be cleared of couch-graſs and knot-graſs roots, by the cleaning harrow, deſcribed above. The time for this operation is immediately before the manure is laid on. The ground at that time being in its looſeſt ſtate, parts with its graſs-roots more freely than at any other time. After the manure is ſpread, and incorporated with the ſoil by brakeing or harrowing, the ſeed may be ſown under furrow, if the ground hang ſo as eaſily to carry off the moiſture. To leave it rough without harrowing, has two advantages: it is not apt to cake with moiſture; and the inequalities make a ſort of ſhelter to the young plants againſt froſt. But if it lie flat, it ought to be ſmoothed with a ſlight harrow after the ſeed is ſown, which will facilitate the courſe of the rain from the crown to the furrow.

A ſandy ſoil is too looſe for wheat. The only chance for a crop is after red clover, the roots of which bind the ſoil; and the inſtructions above given for loam are applicable here. Rye is a crop much fitter for ſandy ſoil than wheat; and like wheat it is generally ſown after a ſummer fallow.

Laſtly, Sow wheat as ſoon in the month of October as the ground is ready. When ſown a month more early, it is too forward in the ſpring, and apt to be hurt by froſt: when ſown a month later, it has not time to root before froſt comes on, and froſt ſpews it out of the ground.

## 2. OATS.

As winter-ploughing enters into the culture of oats, I muſt remind the reader of the effect of froſt upon tilled land. Providence has neglected no region intended for the habitation of man. If in warm climates the ſoil be meliorated by the ſun, it is no leſs meliorated by froſt in cold climates. Froſt acts upon water, by expanding it into a larger ſpace. Froſt has no effect upon dry earth; witneſs ſand, upon which it makes no impreſſion. But upon wet earth it acts moſt vigorouſly; it expands the moiſture, which requiring more ſpace, puts every particle of the earth out of its place, and ſeparates them from each other. In that view, froſt may be conſidered as a plough ſuperior to any that is made, or can be made, by the hand of man: its action reaches the minuteſt particles; and, by dividing and ſeparating them, it renders the ſoil looſe and friable. This operation is the moſt remarkable in tilled land, which gives free acceſs to froſt. With reſpect to clay ſoil in particular, there is no rule in huſbandry more eſſential than to open it before winter in hopes of froſt. It is even adviſeable in a clay ſoil to leave the ſtubble rank, which, when ploughed in before winter, keeps the clay looſe, and admits the froſt into every cranny.

To apply this doctrine, it is dangerous to plough clay ſoil when wet; becauſe water is a cement for clay, and binds it ſo as to render it unfit for vegetation. It is however leſs dangerous to plough wet clay before winter than after. A ſucceeding froſt corrects the bad effects of ſuch ploughing: a ſucceeding drought encreaſes them. No rule is ſo eaſy to be followed as what I am inculcating; and yet no other is ſo frequently tranſgreſſed. Many farmers have a ſort of baſtard induſtry, that prompts activity without ever thinking of conſequences.

And now to the culture of oats, a culmiferous plant. The common method is, to ſow them on new-ploughed land in the month of March, as ſoon as the ground is tolerably dry. If it continue wet all the month of March, it is too late to venture them after. It is much better to ſummer-fallow and to ſow wheat in the autumn. But the preferable method, eſpecially in clay ſoil, is to turn over the field after harveſt, and to lay it open to the influences of froſt and air, which leſſen the tenacity of clay, and reduce it to a free mould. The ſurface-ſoil by this means is finely mellowed for reception of the ſeed; and it would be a pity to bury it by a ſecond ploughing before ſowing. In general, the bulk of clay ſoils are rich; and ſkilful ploughing without dung, will probably give a better crop than unſkilful ploughing with dung.

Hitherto of natural clays. I muſt add a word of carſe clays which are artificial, whether left by the ſea, or ſweeped down from higher grounds by rain. The method commonly uſed of dreſſing carſe clay for oats, is, not to ſtir it till the ground be dry in the ſpring, which ſeldom happens before the firſt of March; and the ſeed is ſown as ſoon after as the ground is ſufficiently dry for its reception. Froſt has a ſtronger effect on ſuch clays than on natural clay. And if the field be laid open before winter, it is rendered ſo looſe by froſt as to be ſoon drenched in water. The particles at the ſame time are ſo ſmall, as that the firſt drought in ſpring makes the ſurface cake or cruſt. The difficulty of reducing this cruſt into mould for covering the oat-ſeed, has led farmers to delay ploughing till the month of March. But we are taught by experience, that this ſoil ploughed before winter, is ſooner dry than when the ploughing is delayed till ſpring; and as early ſowing is a great advantage, the objection of the ſuperficial cruſting is eaſily removed by the harrow, N° 1. above deſcribed, which will produce abundance of mould for covering the ſeed. The ploughing before winter not only procures early ſowing, but has another advantage: the ſurface-ſoil that had been mellowed during winter by the ſun, froſt, and wind, is kept above. I have no experience of managing carſe clay in this manner; but to me it appears greatly preferable to the common practice.

The dreſſing a loamy ſoil for oats, differs little from dreſſing a clay ſoil, except in the following particular, that being leſs hurt by rain, it requires not high ridges; and therefore ought to be ploughed crown and furrow alternately.

Where there is both clay and loam in a farm, it is obvious from what is ſaid above, that the ploughing of the clay after harveſt, ought firſt to be diſpatched. If both cannot be overtaken that ſeaſon, the loam may be delayed till the ſpring with leſs hurt.

Next of a gravelly ſoil; which is the reverſe of clay, as it never ſuffers but from want of moiſture. Such a ſoil ought to have no ridges; but ploughed circularly from the centre to the circumference,

cumference, or from the circumference to the centre. It ought to be tilled after harveſt; and the firſt dry weather in ſpring ought to be laid hold of to ſow, harrow, and roll; which will preſerve it in ſap.

The culture of oats is the ſimpleſt of all. That grain is probably a native of Britain: it will grow on the worſt ſoil with very little preparation. For that reaſon, before turnip was introduced, it was always the firſt crop upon land broken up from the ſtate of nature.

Upon ſuch land, may it not be a good method, to build up on the crown of every ridge, in the form of a wall, all the ſurface-earth, one ſod above another, as in a fold for ſheep? After ſtanding in this form all the ſummer and winter, let the walls be thrown down, and the ground prepared for oats. This will ſecure one or two good crops; after which the land may be dunged for a crop of barley and graſs-ſeeds. This method may anſwer in a farm where manure is ſcanty.

## 3. BARLEY.

BARLEY is a culmiferous plant that requires a mellow ſoil. Upon that account, extraordinary care is requiſite where it is to be ſown in clay. The land ought to be ſtirred immediately after the foregoing crop is removed, which lays it open to be mellowed with the froſt and air. In that view, a peculiar ſort of ploughing has been introduced, termed *ribbing*; by which the greateſt quantity of ſurface poſſible is expoſed to the air and froſt. The obvious objection to this method is, that half of the ridge is left unmoved. And to obviate that objection, I offer the following method, which moves the whole ſoil, and at the ſame time expoſes the ſame quantity of ſurface to the froſt and air. This I eſteem a valuable improvement; and I am only in pain about making it to be clearly underſtood. As ſoon as the former crop is off the field, let the ridges be gathered with as deep a furrow as the ſoil will admit, beginning at the crown and ending at the furrows. This ploughing looſens the whole ſoil, giving free acceſs to the air and froſt. Soon after, begin a ſecond ploughing in the following manner. Let the field be divided by parallel lines croſs the ridges, with intervals of thirty feet or ſo. Plough once round an interval, beginning at the edges, and turning the earth toward the middle of the interval; which covers a foot or ſo of the ground formerly ploughed. Within that foot plough another round ſimilar to the former; and after that other rounds, till the whole interval be finiſhed, ending at the middle. Inſtead of beginning at the edges, and ploughing toward the middle, it will have the ſame effect to begin at the middle and to plough toward the edges. Plough the other intervals in the ſame manner. As by this operation the furrows of the ridges will be pretty much filled up, let them be cleaned and water-furrowed without delay. By this method, the field will be left waving like a plot in a kitchen-garden, ridged up for winter. In this form, the field is kept perfectly dry; for beſide the capital furrows that ſeparate the ridges, every ridge has a number of croſs-furrows that carry the rain inſtantly to the capital furrows. In hanging grounds retentive of moiſture, the parallel lines above mentioned ought not to be perpendicular to the furrows of the ridges, but to be directed a little downward, in order to carry rain-water the more haſtily to theſe furrows. If the ground be clean, it may lie in that ſtate winter and ſpring, till the time of ſeed-furrowing. If weeds happen to riſe, they muſt be deſtroyed by ploughing, or brakeing, or both; for there cannot be worſe huſbandry, than to put ſeed into dirty ground.

This method reſembles common ribbing in appearance, but is very different in reality. As the common ribbing is not preceded by a gathering furrow, the half of the field is left untilled, compact as when the former crop was removed, impervious in a great meaſure to air or froſt. The common ribbing at the ſame time lodges the rain-water on every ridge, preventing it from deſcending to the furrows; which is hurtful in all ſoils, and poiſonous in a clay ſoil. The ſtitching here deſcribed, or ribbing if you pleaſe to call it ſo, prevents theſe noxious effects. By the two ploughings the whole ſoil is opened, admitting freely air and froſt; and the multitude of furrows lays the ſurface perfectly dry, giving an early opportunity for the barley-ſeed.——But I have more to ſay in favour of the method propoſed. When it is proper to ſow the ſeed, all is laid flat with the brake, which is an eaſy operation upon ſoil that is dry and pulverized; and the ſeed-furrow which ſucceeds, is ſo ſhallow as to bury little or none of the ſurface-earth: whereas the ſtirring for barley is commonly done with the deepeſt furrow; and conſequently buries all the ſurface-ſoil that was mellowed by the froſt and air. Nor is this method more expenſive; becauſe the common ribbing muſt always be followed with a ſtirring furrow, which is ſaved in the method recommended. Nay, it is leſs expenſive; for after common ribbing, which keeps in the rain-water, the ground is commonly ſo ſoured, as to make the ſtirring a laborious work.

Where the land is in good order, and free of weeds, April is the month for ſowing barley. Every day is proper from the firſt to the laſt.

The dreſſing loamy ſoil and light ſoil for barley, is the ſame with that deſcribed; only that to plough dry is not altogether ſo eſſential as in dreſſing clay ſoil. Loam or ſand may be ſtirred a little moiſt: better, however, delay a week or two, than to ſtir a loam when moiſt. Clay muſt never be ploughed moiſt, even though the ſeaſon ſhould eſcape altogether. But this will ſeldom be neceſſary; for not in one year of twenty will it happen, but that clay is dry enough for ploughing ſome time in May. Froſt may correct clay ploughed wet after harveſt; but ploughed wet in the ſpring, it unites into a hard maſs, not to be diſſolved but by very hard labour.

The foregoing culmiferous plants are what are ordinarily propagated for food in Scotland. What follow are leguminous plants. And I begin with beans, being ſown the earlieſt in ſpring.

### 4. Beans.

The propereſt ſoil for beans is a deep and moiſt clay.

There was lately introduced into Scotland a method of ſowing beans with a drill-plough, and horſe-hoeing the intervals; which, beſide affording a good crop, is a dreſſing to the ground. But as that method is far from being general, I keep in the common track.

As this grain is early ſown, the ground intended for it ſhould be ploughed before winter, to give acceſs to the froſt and air; beneficial in all ſoils, and neceſſary in a clay ſoil. Take the firſt opportunity after January when the ground is dry, to looſen the ſoil with the harrow firſt deſcribed, till a mould be brought upon it. Sow the ſeed, and cover it with the ſecond harrow. The third will ſmooth the ſurface, and cover the ſeed equally. Theſe harrows make the very beſt figure in ſowing beans; which ought to be laid deep in the ground, not leſs than ſix inches. In clay ſoil, the common harrows are altogether inſufficient. The ſoil, which has reſted long after ploughing, is rendered compact and ſolid: the common harrows ſkim the ſurface: the ſeed is not covered; and the firſt hearty ſhower of rain lays it above ground. Where the farmer overtakes not the ploughing after harveſt, and is reduced to plough immediately before ſowing, the plough anſwers the purpoſe of the firſt harrow; and the other two will complete the work. But the labour of the firſt harrow is ill ſaved; as the ploughing before winter is a fine preparation, not only for beans, but for grain of every kind. If the ground ploughed before winter happen by ſuperfluity of moiſture to cake, the firſt harrow going along the ridges, and croſſing them, will looſen the ſurface, and give acceſs to the air for drying. As ſoon as the ground is dry, ſow without delaying a moment. If rain happen in the interim, there is no remedy but patience till a dry day or two come.

Carſe clay, ploughed before winter, ſeldom fails to cake. Upon that account, a ſecond ploughing is neceſſary before ſowing; which ought to be performed with an ebb furrow, in order to keep the froſt-mould as near the ſurface as poſſible. To cover the ſeed with the plough is expreſſed by the phraſe *to ſow under furrow*. The clods raiſed in this ploughing, are a ſort of ſhelter to the young plants in the chilly ſpring-months.

The foregoing method will anſwer for loams. And as for a ſandy or gravelly ſoil, it is altogether improper for beans.

Though I cannot recommend the horſe-hoing of beans, with the intervals that are commonly allotted for turnip, yet I warmly recommend the drilling them at the diſtance of ten or twelve inches, and keeping the intervals clean of weeds. This may be done by hand-hoeing, taking opportunity at the ſame time to lay freſh ſoil to the roots of the plants. But as this is an expenſive operation, and hands are not always to be got, I propoſe a narrow plough, drawn by a ſingle horſe, with a mouldboard on each ſide to ſcatter the earth upon the roots of the plants. This is a cheap and expeditious method: it keeps the ground clean; and nouriſhes the plants with freſh ſoil.

As beans delight in a moſt ſoil, and have no end of growing in a moiſt ſeaſon, they cover the ground totally when ſown broadcaſt, keep in the dew, and exclude the ſun and air: the plants grow to a great height, but carry little ſeed, and that little not well ripened. This diſplays the advantage of drilling, which gives free acceſs to the ſun and air, dries the ground, and affords plenty of ripe ſeed.

## 5. PEASE.

PEASE are of two kinds; the white, and the gray. The latter is what generally is cultivated in Scotland for fruit; and the latter only ſhall be here handled, leaving the former to gardeners.

There are two ſpecies of the gray kind, diſtinguiſhed by their time of ripening. One ripens ſoon, and for that reaſon is termed *hot ſeed*: the other, which is ſlower in ripening, is termed *cold ſeed*. Whether theſe be really different ſpecies, or be accidentally different only, is left to natural philoſophers.

Peaſe, a leguminous crop, is proper to intervene between two culmiferous crops; leſs for the profit of a peaſe-crop, than for meliorating the ground. Peaſe however in a dry ſeaſon will produce ſix or ſeven bolls each acre; but in an ordinary ſeaſon they ſeldom reach above two or two and a half. This leads me to think, that in a moiſt climate, which all the weſt of Britain is, red clover is a more beneficial crop than peaſe; as it makes as good winter-food as peaſe, and can be cut green thrice during ſummer. When huſbandry comes to be better underſtood, I have little doubt but that red clover will baniſh peaſe altogether, except in the warmeſt and drieſt ſpots.

A field intended for cold ſeed ought to be ploughed in October or November; and in February,

bruary, as ſoon as the ground is dry, the ſeed ought to be ſown on the winter-furrow. A field intended for hot ſeed, ought to be ploughed in March or April, immediately before ſowing. But if infeſted with weeds, it ought to be alſo ploughed in October or November.

Peaſe laid a foot below the ſurface will vegetate: but the moſt approved depth is ſix inches in light ſoil, and four inches in clay ſoil; for which reaſon, they ought to be ſown under furrow when the ploughing is delayed till ſpring. Of all grain, beans excepted, they are the leaſt in danger of being buried.

Peaſe differ from beans, in loving a dry ſoil and a dry ſeaſon. Horſe-hoeing would be a great benefit, could it be performed to any advantage; but peaſe grow expeditiouſly, and ſoon fall over and cover the ground, which bars ploughing. Horſe-hoeing has little effect when the plants are new ſprung; and when they are advanced to be benefited by that culture, their length prevents it. Faſt growing at the ſame time is the cauſe of their carrying ſo little ſeed: the ſeed is buried among the leaves; and the ſun cannot penetrate to make it grow and ripen. The only practicable remedy to obtain grain, is thin ſowing; but thick ſowing produces more ſtraw, and mellows the ground more. Half a boll for an Engliſh acre may be reckoned thin ſowing; three firlots, thick ſowing.

Notwithſtanding what is ſaid above, Mr Hunter,

ter, a noted farmer in Berwickſhire, has begun of late to ſow all his peaſe in drills; and he never fails to have great crops of corn as well as of ſtraw. He ſows double rows at a foot interval, and two feet and a half between the double rows, which admit horſe-hoeing. By that method, he has alſo good crops of beans on light land.

Peaſe and beans mixed are often ſown together, in order to catch different ſeaſons. In a moiſt ſeaſon, the beans make a good crop; in a dry ſeaſon, the peaſe.

The growth of plants is commonly checked by drought in the month of July; but promoted by rain in Auguſt. In July, graſs is parched; in Auguſt, it recovers verdure. Where peaſe are ſo far advanced in the dry ſeaſon as that the ſeed begins to form, their growth is indeed checked, but the ſeed continues to fill. If only in the bloſſom at that ſeaſon, their growth is checked a little; but they become vigorous again in Auguſt, and continue growing without filling till ſtopped by froſt. Hence it is, that cold ſeed, which is early ſown, has the beſt chance to produce corn: hot ſeed, which is late ſown, has the beſt chance to produce ſtraw.

The following method is practiſed in Norfolk, for ſowing peaſe upon a dry light ſoil, immediately opened from paſture. The ground is pared with a plough extremely thin, and every ſod is laid exactly on its back. In every ſod a double row of holes is made. A pea dropt in every hole lodges in the flay'd ground immediately below the ſoil, thruſts its roots horizontally, and has ſufficient moiſture. This method enabled Norfolk farmers, in the baren year 1740, to furniſh white peaſe to us at 12 s. per boll.

## SECT. II.

### Plants cultivated for Roots.

Plants of that kind commonly cultivated in the field, are turnip, potatoes, carrot, parſnip.

### 1. Turnip.

It animates me to have opportunity for giving directions about a crop, that the beſt farmers in this country have now taken into their plan of huſbandry; and that does not altogether eſcape even ſmall farmers. Nor am I acquainted with a ſingle inſtance in Scotland, where turnip fairly begun have been relinquiſhed.

The proper ſoil for turnip is a gravelly ſoil; and there it can be raiſed to the greateſt perfection, and with the leaſt hazard of miſcarrying. At the ſame time, there is no ſoil but will bear turnip when well prepared.

No perſon ever deſerved better of a country, than he who firſt cultivated turnip in the field.

No plant is better fitted for the climate of Britain; no plant proſpers better in the coldeſt part of it, and no plant contributes more to fertility. In a word, there has not for two centuries been introduced into Britain a more valuable improvement.

Of all roots, turnip requires the fineſt mould; and to that end, of all harrows froſt is the beſt. In order to give acceſs to froſt, the land ought to be prepared by ribbing after harveſt, as above directed in preparing land for barley. If the field be not ſubject to annuals, it may lie in that ſtate till the end of May; otherwiſe the weeds muſt be deſtroyed by a brakeing about the middle of April; and again in May, if weeds riſe. The firſt week of June, plough the field with a ſhallow furrow. Lime it if requiſite, and harrow the lime into the ſoil. Draw ſingle furrows with intervals of three feet, and lay dung in the furrows. Cover the dung ſufficiently, by going round it with the plough, and forming the three feet ſpaces into ridges. The dung comes thus to lie below the crown of every ridge.

The ſeaſon of ſowing muſt be regulated by the time intended for feeding. Where intended for feeding in November, December, January, and February, the ſeed ought to be ſown from the 1ſt to the 20th of June. Where the feeding is intended to be carried on to March, April, and May, the ſeed muſt not be ſown till the end of July. Turnip ſown earlier than above directed, flowers that very ſummer, and runs faſt to ſeed; which renders it in a good meaſure unfit for food. If ſown much later, it does not apple, and there is no food but from the leaves.

Though by a drill-plough the ſeed may be ſown of any thickneſs, the ſafeſt way is to ſow thick. Thin-ſowing is liable to many accidents; which are far from being counterbalanced by the expence that is ſaved in thinning. Thick-ſowing can bear the ravage of the black fly, and leave a ſufficient crop behind. It is a protection againſt drought, gives the plants a rapid progreſs, and eſtabliſhes them in the ground before it is neceſſary to thin them.

The ſowing turnip breadcaſt is univerſal in England, and common in Scotland, though a barbarous practice. The eminent advantage of turnip is, that, beſide a profitable crop, it makes a moſt complete fallow; and the latter cannot be obtained but by horſe-hoeing. Upon that account, I recommend with confidence the ſowing turnip in rows at three feet diſtance: wider rows anſwer no profitable end, ſtraiter rows afford not room for a horſe to walk in. When the turnip is about four inches high, annual weeds will appear. Go round every interval with the ſlighteſt furrow poſſible, at the diſtance of two inches from each row, moving the earth from the rows toward the middle of the interval. A thin plate of iron muſt be fixed on the left ſide of the plough, to prevent the earth from falling back, and burying the turnip. Next, let women be employed to weed the rows with their fingers, which is better, and cheaper done, than with the hand-hoe. The hand-hoe, beſide, is apt to diſturb the roots of the turnip that are to ſtand; and to bare them open to drought by removing the earth from them. The ſtanding turnip are to be at the diſtance of twelve inches from each other: a greater diſtance makes them ſwell too much; a leſs diſtance affords them not ſufficient room. A woman ſoon comes to be expert in finger-weeding. The following hint may be neceſſary to a learner. To ſecure the turnip that is to ſtand, let her cover it with the left hand; and with the right pull up the turnip on both ſides. After thus freeing the ſtanding turnip, ſhe may ſafely uſe both hands. Let the field remain in this ſtate, till the appearance of new annuals make a ſecond ploughing neceſſary; which muſt be in the ſame furrow with the former, but a little deeper. As in this ploughing the iron plate is to be removed, part of the looſe earth will fall back on the roots of the plants: the reſt will fill the middle of the interval, and bury every weed. When weeds begin again to appear, then is the time for a third ploughing, in an oppoſite direction, which lays the earth to the roots of the plants. This ploughing may be about the middle of Auguſt, after which, weeds riſe very faintly. If they do riſe, another ploughing will clear the ground of them. Weeds that at this time riſe in the row, may be cleared with a hand-hoe, which can do little miſchief among plants diſtant twelve inches from each other. I am certain however from experience, that it may be done cheaper with the hand *. And after the leaves of turnips in a row meet together, the hand is the only inſtrument that can be applied for weeding.

Tull was the father of horſe-hoeing huſbandry; and to deſert his method requires an apology. The apology I make is, that the method I preſcribe and have long practiſed, is more ſimple, leſs operoſe, and, as far as I can judge, equally ſucceſsful. Our farmers ought to be excited by every art to embrace the cultivation of turnip; and nothing will contribute more than to render it eaſy and ſimple. Tull's method is not a little intricate; and to its intricacy, I am perſuaded, is owing the neglect of it in England.

---

* Children under thirteen may be employed to weed turnip with the fingers. I have ſeen them go on in that work with alacrity; and a ſmall premium will have a good effect. Cuſtom, a ſecond nature, will lead them to think, that weeding turnip is no leſs neceſſary than ſowing them. For boys and girls above thirteen, a hand-hoe adapted to their ſize is an excellent inſtrument: it ſtrengthens the arms amazingly. In driving the plough, the legs only are exerciſed; but as the arms are chiefly employed in huſbandry, they ought to be prepared beforehand by gentle exerciſe.

In ſwampy ground, the ſurface of which is beſt reduced by paring and burning, the ſeed may be ſown in rows, with intervals of a foot. To ſave time, a drill-plough may be uſed that ſows three or four rows at once. Hand-hoeing is proper for ſuch ground; becauſe the ſoil under the burnt *ſtratum* is commonly full of roots, which digeſt and rot better under ground than when brought to the ſurface by the plough. In the mean time, while theſe are digeſting, the aſhes will ſecure a good crop.

The black fly is a great enemy to turnip; and I may juſtly ſay the only enemy, becauſe every other article can be ſecured, by ſkill and diligence in the huſbandman. In a rich and warm ſoil, where the black fly is inſtinctively directed to depoſit its eggs, I take it to be an unconquerable enemy. Our only ſecurity is, to change the field of battle, by raiſing turnip in a mooriſh ground, or in ground newly broken up, according to the directions given above *.

## 2. POTATOES.

THE choice of ſoil is not of greater importance in any other plant than in a potato. This plant in clay ſoil, or in rank black loam lying low without ventilation, never makes palatable food. In a gravelly or ſandy ſoil, expoſed to the ſun and to free air, it thrives to perfection, and has a good reliſh. But a rank black loam, though improper to raiſe potatoes for the table, produces them in great plenty; and the product is good and wholeſome food for horned cattle, hogs, and poultry. The ſpade is a proper inſtrument for raiſing a ſmall quantity, or for preparing corners or other places inacceſſible to the plough; but for raiſing potatoes in quantities, the plough is the only inſtrument.

---

* Chap. 3. § 2.

As two great advantages of a drilled crop, are, to deſtroy weeds, and to have a fallow at the ſame time with the crop, no judicious farmer will think of raiſing potatoes in any other way. In September or October, as ſoon as that year's crop is removed, let the field have a rouſing furrow, a croſs-brakeing next, and then cleared of weeds by the cleaning harrow. Form it into three-feet ridges, in that ſtate to lie till April, which is the proper time for planting potatoes. Croſs-brake it to raiſe the furrows a little. Then lay well-digeſted horſe-dung along the furrows, upon which lay the roots at eight inches diſtance. Cover up theſe roots with the plough, going once round every row. This makes a warm bed for the potatoes; hot dung below, and a looſe covering above, that admits every ray of the ſun. As ſoon as the plants appear above ground, go round every row a ſecond time with the plough, which will lay upon the plants an additional inch or two of mould, and at the ſame time bury all the annuals; and this will complete the ploughing of the ridges. When the potatoes are ſix inches high, the plough, with the deepeſt furrow, muſt go twice along the middle of each interval in oppoſite directions, laying earth firſt to one row, and next to the other. And to perform this work, a plough with a double mould-board will be more expeditious. But as the earth cannot be laid cloſe to the roots by the plough, the ſpade muſt ſucceed, with which four inches of the plants muſt be covered, leaving little more but the tops above ground; and this operation will at the ſame time bury all the weeds that have ſprung ſince the former ploughing. What weeds ariſe after, muſt be pulled up with the hand. A hoe is never to be uſed here: it cannot go ſo deep as to deſtroy the weeds without cutting the fibres of the plants; and if it ſkim the ſurface, it only cuts off the heads of the weeds, and does not prevent their puſhing again.

The ſhorteſt and moſt perfect method of taking up potatoes, is to plough once round every row at the diſtance of four inches, removing the earth from the plants, and gathering up with the hand all the potatoes that appear. The diſtance is made four inches to prevent cutting the roots, which are ſeldom found above that diſtance from the row on each ſide. When the ground is thus cleared by the plough, raiſe the potatoes with a fork having three broad toes or claws, which is better than a ſpade, as it does not cut the potatoes. The potatoes thus laid above ground, muſt be gathered with the hand. By this method ſcarce a potato will be left.

As potatoes are a comfortable food for the low people, it is of importance to have them all the year round. For a long time, potatoes in Scotland were confined to the kitchen-garden; and after they were planted in the field, it was not imagined at firſt that they could be uſed after the month of December. Of late years they have been found to anſwer even till April; which has proved a great ſupport to many a poor family, as they are eaſily cooked, and require neither kiln nor mill. But there is no cauſe for ſtopping there. It is eaſy to preſerve them till the next crop: When taken out of the ground, lay in the corner of a barn a quantity that may ſerve till April, covered from froſt with dry ſtraw preſſed down: bury the remainder in a hole dug in dry ground, mixed with the huſks of dried oats, ſand, or the dry leaves of trees, over which build a ſtack of hay or corn. When the pit is opened for taking out the potatoes, the eyes of what have a tendency to puſh, muſt be cut out; and this cargo will ſerve all the month of June. To be ſtill more certain of making the old crop meet the new, the ſetting of a ſmall quantity may be delayed till June, to be taken up at the ordi-

nary

any time before froſt. This cargo, having not arrived to full growth, will not be ſo ready to puſh as what are ſet in April.

If the crop happen to be exhauſted before the new crop is ready, the interval may be ſupplied by the potatoes of the new crop that lie next the ſurface, to be picked up with the hand; which, far from hurting the crop, will rather improve it.

### 3. Carrot and Parsnip.

Of all roots a carrot requires the deepeſt ſoil. It ought at leaſt to be a foot deep, all equally good from top to bottom. If ſuch a ſoil be not in the farm, it may be made artificially by trench-ploughing, which brings to the ſurface what never had any communication with the ſun or air. When this new ſoil is ſufficiently improved by a crop or two with dung, it is fit for bearing carrots. Beware of dunging the year when the carrots are ſown; for with freſh dung they ſeldom eſcape rotten ſcabs.

The only ſoils proper for that root, are a loam and a ſandy ſoil.

The ground muſt be prepared by the deepeſt furrow that can be taken, the ſooner after harveſt the better; immediately upon the back of which a ribbing ought to ſucceed as directed for barley. At the end of March or beginning of April, which is the time of ſowing the ſeed, the ground muſt be ſmoothed with a brake. Sow the ſeed in drills, with intervals of a foot for hand-hoeing; which is no expenſive operation where the crop is confined to an acre or two: but if the quantity of ground be greater, the intervals ought to be three feet, in order for horſe-hoeing.

In flat ground without ridges, it may be proper to make parallel furrows with the plough, ten feet from each other, in order to carry off any redundant moiſture.

At Parlington in Yorkſhire, from the end of September to the firſt of May, twenty work-horſes, four bullocks, and ſix milk-cows, were fed on the carrots that grew on three acres; and theſe animals never taſted any other food but a little hay. The milk was excellent: and, over and above, thirty hogs were fattened upon what was left by the other beaſts. I have this fact from undoubted authority.

The culture of parſnips is the ſame with that of carrots.

## SECT. III.

## Plants cultivated for Leaves.

THERE are many garden-plants of this kind. The plants proper for the field are cabbage, red and white, colewort, plain and curled. I know very little difference in the cultivation of theſe plants. And therefore, to ſave trouble, I ſhall confine myſelf to cabbage. The reader will eaſily apply to the other plants the directions to be given concerning cabbage.

Cabbage is an intereſting article in huſbandry, every ſoil being more or leſs proper for it. It is eaſily raiſed, is ſubject to few diſeaſes, reſiſts froſt more than turnip, is palatable to cattle, and ſooner fills them than turnip, carrot, or potatoes.

The ſeaſon for ſetting cabbage, depends on the uſe it is intended for. If intended for feeding in November, December, and January, plants procured from ſeed ſown the end of July the preceding year, muſt be ſet in March or April. If intended for feeding in March, April, and May, the plants muſt be ſet the firſt week of the preceding July, from ſeed ſown end of February or beginning of March the ſame year. The late ſetting of the plants retards their growth; by which means they have a vigorous growth the following ſpring. And this crop makes an important link in the chain that connects winter and ſummer green food. Let me obſerve by the by, that where cabbage for ſpring-food happens to be neglected, a few acres of rye ſown at Michaelmas will ſupply the want. After the rye is conſumed, there is time ſufficient to prepare the ground for turnip.

And now to prepare a field for cabbage. Where the plants are to be ſet in March, the field muſt be made up after harveſt, in ridges three feet wide. In that form let it lie all winter, to be mellowed with air and froſt. In March, take the firſt opportunity, between wet and dry, to lay dung in the furrows. Cover the dung with a plough, which will convert the furrow into a crown, and conſequently the crown into a furrow. Set the plants upon the dung, diſtant from each other three feet. Plant them ſo as to make a ſtraight line croſs the ridges, as well as along the furrows, to which a gardener's line ſtretched perpendicularly croſs the furrows will be requiſite. This will ſet each plant at the diſtance preciſely of three feet from the plants that ſurround it. The purpoſe of this accuracy, is to give opportunity for ploughing, not only along the ridges, but croſs them. This mode is attended with three ſignal advantages: it ſaves hand-hoeing, it is a more complete dreſſing to the ſoil, and it lays earth neatly round every plant.

If the ſoil be deep and compoſed of good earth, a trench-ploughing after the preceding crop will not be amiſs; in which caſe, the time for dividing the field into three-feet ridges as above, ought to be immediately before the dunging for the plants.

If weeds happen to riſe ſo cloſe to the plants as not to be reached by the plough, it will require very little labour to deſtroy them with a hand-hoe.

Unleſs the ſoil be much infeſted with annuals, twice ploughing after the plants are ſet will be a ſufficient dreſſing. The firſt removes the earth from the plants; the next, at the diſtance of a month or ſo, lays it back.

Where the plants are to be ſet in July, the field muſt be ribbed as directed for barley. It ought to have a ſlight ploughing in June before the planting, in order to looſen the ſoil, but not ſo as to bury the ſurface-earth; after which the three-feet ridges muſt be formed, and the other particulars carried on as directed above with reſpect to plants that are to be ſet in March.

## CHAP. VI.

### CULTURE OF GRASS.

THE graſſes commonly ſown for paſture, for hay, or to cut green for cattle, are red clover, white clover, yellow clover, ryegraſs, and narrow-leaved plantain, commonly called *ribwort*. Among the great variety of graſſes, there is little doubt, but that ſome new ſorts may be introduced to advantage. But without meaning to ſhut out light, I am certain that the graſſes mentioned anſwer completely all uſeful purpoſes of huſbandry.

Red clover is of all the moſt proper to be cut green for ſummer-food. It is a biennial plant when ſuffered to perfect its ſeed; but when cut green, it will laſt three years, and in a dry ſoil longer. At the ſame time the ſafeſt courſe is to let it ſtand but a ſingle year: if the ſecond year's crop happen to be ſcanty, it proves, like a bad crop of peaſe, a great encourager of weeds by the ſhelter it affords them. Sainfoin and lucern make excellent green food; and, when preſerved clean from weeds, they will ſtand good ten or twelve years, eſpecially in a deep gravel. There they extend their roots very deep, and will grow vigorouſly in a dry ſummer, when other plants of ſhorter roots languiſh by lack of moiſture. But except in ſuch a ſoil, I venture to declare in favour of red clover; and my reaſon is, that the expence of ſowing it yearly is much leſs than that of hand-hoeing ſainfoin and lucern frequently every year. Sainfoin indeed ſeems to be the hardier plant. Farmers about Bath ſow it in their higheſt unſheltered grounds; and it endures froſt better than clover, or any ſort of grain. Like clover it is ſown with barley; and as much ſeed is given as of barley. It is commonly cut but once the firſt year; and the firſt winter, coal-aſhes are ſpread upon it.

Here, as in all other crops, the goodneſs of red-clover ſeed is of importance. Chuſe plump ſeed of a purple colour, becauſe it takes on that colour when ripe. It is red when hurt in the drying, and of a faint colour when unripe.

Red clover is luxuriant upon a rich ſoil, whether clay, loam, or gravel: it will grow even upon a moor when properly cultivated. A wet ſoil is its only bane; for there it does not thrive.

To have red clover in perfection, weeds muſt be extirpated, and ſtones taken off. The mould ought to be made as fine as harrowing can make it, and the ſurface be ſmoothed with a light roller, if not ſufficiently ſmooth without it. This gives opportunity for diſtributing the ſeed evenly; which muſt be covered by a ſmall harrow with teeth no larger than of a garden-rake, three inches long, and ſix inches aſunder; of which there is a draught annexed. In harrowing, the man ſhould walk behind with a rope in his hand fixed to the back part of the harrow, ready to diſentangle it from ſtones, clods, turnip or cabbage roots, which would trail the ſeed, and diſplace it.

Nature has not determined any preciſe depth for the ſeed of red clover more than of other ſeed. It will grow vigorouſly from two inches deep, and it will grow when barely covered. Half an inch I reckon the moſt advantageous poſition in clay ſoil, a whole inch in what is light or looſe. It is a vulgar error, that ſmall ſeed ought to be ſparingly covered. Miſled by that error, farmers commonly cover their clover-ſeed with a buſhy branch of thorn; which not only covers it unequally, but leaves part on the ſurface to wither in the air.

The proper ſeaſon for ſowing red clover, is from the middle of April to the middle of May. It will ſpring from the 1ſt of March to the end of Auguſt; but ſuch liberty ought not to be taken, except from neceſſity.

The ordinary manner of ſowing, is to hold the ſeed between the thumb and the two fore fingers. I prefer another manner; which is, to take into the hollow of the hand as much as will ſerve in walking three or four ſteps; and to join the fingers to the palm ſo looſely, as to make many ſmall holes for throwing out the ſeed. A hand cloſed ſo looſely, reſembles the roſe of a watering pan, which ſcatters the water through a number of ſmall holes.

There cannot be a greater blunder in huſbandry, than to be ſparing of ſeed. Ideal writers talk of ſowing an acre with four pounds. That quantity of ſeed, ſay they, will fill an acre with plants as thick as they ought to ſtand. I admit this rule to be good where grain is the object; but it will not anſwer with reſpect to graſs. Graſs-ſeed cannot be ſown too thick: the plants ſhelter one another: they retain all the dew: and they muſt puſh upward, having no room laterally. Obſerve the place where a ſack of peaſe, or of other grain, has been ſet down for ſowing: the ſeed dropt there accidentally grows more quickly than in the reſt of the field ſown thin out of hand: I have ſeen it ſix inches high, when the reſt of the ſeed ſcarce appeared above ground. A young plant of clover, or of ſainfoin, according to Tull, may be raiſed to a great ſize where it has room; but the field will not produce half the quantity. When red clover is ſown for cutting green, there ought not to be leſs than twenty-four pounds to an acre. A field of clover is ſeldom too thick: the ſmaller a ſtem be, the more acceptable it is to cattle. It is often too thin, and when ſo, the ſtems tend to wood.

Red clover is commonly ſown with grain; and the doubt may be, what grain is the moſt proper. I pronounce in favour of flax; and I pronounce with confidence from multiplied experience. The ſoil muſt be highly cultivated for flax as well as for red clover. The proper ſeaſon of ſowing is the ſame for both: the leaves of flax being very ſmall, admit of free circulation of air; and flax being an early crop, is removed ſo early as to give the clover time for growing. In a rich ſoil it has grown ſo faſt, as to afford a good cutting that very year. Next to flax, barley is the beſt companion to clover. The ſoil muſt be looſe and free for barley; and ſo it ought to be for clover: the ſeaſon of ſowing is the ſame; and the clover is well eſtabliſhed in the ground, before it is overtopped by the barley. At the ſame time, barley commonly is ſooner cut than either oats or wheat. In a word, barley is rather a nurſe than a ſtepmother to clover during its infancy. When clover is ſown in ſpring upon wheat, the ſoil, which has lain five or ſix months without being ſtirred, is an improper bed for it; and the wheat, being in the vigour of growth, overtops it from the beginning. It cannot be ſown along with oats, becauſe of the hazard of froſt; and when ſown as uſual among oats three inches high, it is overtopped, and never enjoys free air till the oats be cut. Add, that where oats are ſown upon the winter-furrow, the ſoil is rendered as hard as when under wheat. Red clover is ſometimes ſown by itſelf, without other grain; but this method, beſide loſing a crop, is not ſalutary; becauſe clover in its infant ſtate requires ſhelter. This very year 1775 has confirmed all my experiments about clover. In part of a field, flax was ſown with it; in another part, barley; and, in the remainder, it was ſown alone. The clover on the firſt was the beſt; on the ſecond, inferior; and, on the third, the worſt. Yet the barley was ſown thin, as it ought to be with graſs-ſeeds, and was but an indifferent crop.

And this leads to the quantity of grain proper to be ſown with clover. In a rich ſoil well pulverized, a peck of barley on an Engliſh acre is all that ought to be ventured; but there is not much ſoil in Scotland ſo rich. Two Linlithgow firlots make the proper quantity for an acre that produces commonly ſix bolls of barley; half a firlot for what produces nine bolls. To thoſe who are governed by cuſtom, ſo ſmall a quantity will be thought ridiculous,

ridiculous. Let them only conſider, that a rich ſoil in perfect good order, will from a ſingle ſeed of barley produce twenty or thirty vigorous ſtems. People may flatter themſelves with the remedy, of cutting barley green for food, if it happen to oppreſs the clover. This is an excellent remedy in a field of an acre or two; but the cutting an extenſive field for food muſt be ſlow; and while one part is cutting, the clover is ſmothered in other parts.

The culture of white clover, of yellow clover, of ribwort, of ryegraſs, is the ſame in general with that of red clover. I proceed to their peculiarities. Yellow clover, ribwort, ryegraſs, are all of them early plants, blooming the end of April or beginning of May. The two latter are evergreens, and therefore excellent for winter-paſture. Ryegraſs is leſs hurt by froſt than any of the clovers, and will thrive in a moiſter ſoil: nor in that ſoil is it much affected by drought. In a rich ſoil, it grows four feet high: even in the dry ſummer 1775, it roſe to three feet eight inches; but it had gained that height before the drought came on. Theſe graſſes are generally ſown with red clover for producing a plentiful crop. The proportion of ſeed is arbitrary; and there is little danger of too much. When ryegraſs is ſown for procuring ſeed, five firlots wheat-meaſure may be ſown on an acre; and for procuring ſeed of ribwort, forty pounds may be ſown. The roots of ryegraſs ſpread horizontally: they bind the ſoil by their number; and though ſmall, are yet ſo vigorous as to thrive in hard ſoil. Red clover has a large tap-root, which cannot penetrate any ſoil but what is open and free; and the bigneſs of the root makes the ſoil ſtill more open and free. Ryegraſs, once a great favourite, appears to be diſcarded in moſt parts of Britain. But were the management of it well underſtood, it would be reſtored to high favour. The common practice has been, to ſow it with red clover, and to cut them promiſcuouſly the beginning of June for green food, and a little later for hay. This indeed is the proper ſeaſon for cutting red clover, becauſe at that time it begins to flower; but as at that time the ſeed of the ryegreſs is approaching to maturity, its growth is ſtopped for that year, as much as of oats or barley cut after the ſeed is ripe. Oats or barley cut green before the ſeed forms, will afford two other cuttings; which is the caſe of ryegraſs, of yellow clover, and of ribwort. By ſuch management, all the profit will be drawn that theſe plants can afford.

When red clover is intended for ſeed, the ground ought to be cleared of weeds, were it for no other purpoſe than that the ſeed cannot otherwiſe be preſerved pure: what weeds eſcape the plough, ought to be taken out by the hand. In England, when a crop of ſeed is intended, the clover is always firſt cut for hay. This I conjecture

ture to be done, as in fruit-trees, to check the growth of the wood, in order to encourage the fruit. This practice will not anſwer with us, as the ſeed would often be too late for ripening. It would do better to eat the clover with ſheep till the middle of May, which would allow the ſeed to ripen. The ſeed is ripe when, upon rubbing it between the hands, it parts readily from the huſk. Then apply the ſythe, ſpread the crop thin, and turn it carefully. When perfectly dry, take the firſt opportunity of a hot day for threſhing it on boards covered with a coarſe ſheet. Another way leſs ſubject to riſk, is to ſtack the dry hay, and to threſh it the end of April. After the firſt threſhing, expoſe the huſks to the ſun, and threſh them over and over till no ſeed remain. Nothing is more efficacious than a hot ſun to make the huſk part with its ſeed; in which view it may be expoſed to the ſun by parcels, an hour or two before the flail is applied.

White clover intended for ſeed, is managed in the ſame manner. No plant ought to be mixed with ryegraſs that is intended for ſeed. In Scotland, much ryegraſs-ſeed is hurt by tranſgreſſing that rule. The ſeed is ripe when it parts eaſily from the huſk. The yellowneſs of the ſtem is another indication of its ripeneſs; in which particular it reſembles oats, barley, and other culmiferous plants. The beſt manner to manage a crop of ryegraſs for ſeed, is to bind it looſely in ſmall ſheaves, widening them at the bottom to make them ſtand erect; as is done with oats in moiſt weather. In that ſtate they may ſtand till ſufficiently dry for threſhing. By this method they dry more quickly, and are leſs hurt by rain, than by cloſe binding and putting the ſheaves in ſhocks like corn. The worſt way of all, is, to ſpread the ryegraſs on the moiſt ground; for it makes the ſeed malten. The ſheaves, when ſufficiently dry, are carried in cloſe carts to where they are to be threſhed on a board, as mentioned above for clover. Put the ſtraw in a rick, when a hundred ſtone or ſo are threſhed. Carry the threſhing-board to the place where another rick is intended; and ſo on till the whole ſeed be threſhed, and the ſtraw ricked. There is neceſſity for cloſe carts to ſave the ſeed, which is apt to drop out in a hot ſun: and, as obſerved above, a hot ſun ought always to be choſen for threſhing. Carry the ſeed in ſacks to the granary or barn, there to be ſeparated from the huſks by a fanner. Spread the ſeed thin upon a timber floor, and turn it once or twice a-day, till perfectly dry. If ſuffered to take a heat, it is uſeleſs for ſeed.

## CHAP. VII.

## ROTATION OF CROPS.

O branch of huſbandry requires more ſkill and ſagacity than a proper rotation of ps, ſo as to keep the ground always in heart, yet to draw out of it the greateſt profit poſ- e. A horſe is purchaſed for labour; and it is purchaſer's intention to make the moſt of him. is well fed, and wrought according to his ngth: to overwork him, is to render him eſs. Preciſely ſimilar is land. Profit is the ner's object; but he knows, that to run out on the ſoil for nouriſhment, and little on the air. During the ripening of the ſeed, they draw probably their whole nouriſhment from the ſoil; as the leaves by this time, being dry and withered, muſt have loſt their power of drawing nouriſhment from the air. Now, as culmiferous plants are chiefly cultivated for their ſeed, and are not cut down till the ſeed be fully ripe, they may be pronounced all of them to be robbers, ſome more ſome leſs. But ſuch plants, while young, are all leaves; and in that ſtate draw moſt of their nouriſhment from the air. Hence it is, that where cut green for food to cattle, a culmiferous crop is far from being a robber. A hay-crop accordingly, even where it conſiſts moſtly of ryegraſs, is not a robber, provided it be cut before the ſeed is formed; which at any rate it ought to be, if one would have hay in perfection. And the foggage, excluding froſt by covering the ground, keeps the roots warm. A leguminous plant, by its broad leaves, draws much of its nouriſhment from the air. A cabbage, which has very broad leaves, and a multitude of them, owes its growth more to the air than to the ſoil. One fact is certain, that a cabbage cut and hung up in a damp place, preſerves its verdure longer than other plants. At the ſame time, a ſeed is that part of a plant which requires the moſt nouriſhment; and for that nouriſhment a culmiferous plant muſt be indebted entirely to the ſoil. A leguminous crop, on the contrary, when cut green for food, muſt be very gentle to the ground. Peaſe and beans are leguminous plants; but being cultivated for ſeed, they ſeem to occupy a middle ſtation; their ſeed makes them more ſevere than other leguminous crops cut green: their leaves, which grow till reaping, make them leſs ſevere than a culmiferous plant left to ripen.

Theſe plants are diſtinguiſhed no leſs remarkably by the following circumſtance. All the ſeeds of a culmiferous plant ripen at the ſame time. As ſoon as they begin to form, the plant becomes ſtationary, the leaves wither, the roots ceaſe to puſh, and the plant, when cut down, is blanched and ſapleſs. The ſeeds of a leguminous plant are formed ſucceſſively: flowers and fruit appear at the ſame time in different parts of the plant. This plant accordingly is continually growing, and puſhing its roots. Hence the value of bean or peaſe ſtraw above that of wheat or oats: the latter is withered and dry when the crop is cut; the former, green and ſucculent. The difference therefore with reſpect to the ſoil between a culmiferous and leguminous crop, is great. The latter, growing till cut down, keeps the ground in conſtant motion, and leaves it to the plough looſe and mellow. The former gives over growing long before reaping, and the ground, by want of motion, turns compact and hard. Nor is this all. Dew falling on a culmiferous crop after the ground begins to harden, reſts on the ſurface, and is ſucked up by the next ſun. Dew that falls on a leguminous crop, is ſhaded from the ſun by the broad leaves, and ſinks at leiſure into the ground. The ground accordingly after a culmiferous crop, is not only hard but dry: after a leguminous crop, it is not only looſe, but ſoft and unctuous.

Of all culmiferous plants, wheat is the moſt ſevere, by the long time it occupies the ground without admitting a plough. And as the grain is heavier than that of barley or oats, it probably requires more nouriſhment than either. Spring-wheat is creeping into uſe: if it ſucceed, it will probably be not much more ſevere than other culmiferous plants. It is obſerved above, that as peaſe and beans draw part of their nouriſhment from the air by their green leaves while allowed to ſtand, they draw the leſs from the ground; and by their conſtant growing they leave it in good condition for ſubſequent crops. In both reſpects they are preferable to any culmiferous crop.

Culmiferous crops, as obſerved above, are not robbers when cut green: the ſoil, far from hardening, is kept in conſtant motion by the puſhing of the roots, and is left more tender than if it had been left at reſt without bearing any crop.

Bulbous-rooted plants are above all ſucceſsful in dividing and pulveriſing the ſoil. Potato-roots grow ſix, eight, or ten, inches under the ſurface; and, by their ſize and number, they divide and pulveriſe the ſoil better than can be done by the plough; conſequently, whatever be the natural colour of the ſoil, it is black when a potato-crop is taken up. The potato, however, with reſpect to its quality of dividing the ſoil, muſt yield to a carrot or parſnip; which are large roots, and pierce often to the depth of eighteen inches. The turnip, by its tap-root, divides the ſoil more than can be done by a fibrous-rooted plant; but as its bulbous root grows moſtly above ground, it divides the ſoil leſs than the potato, the carrot, or the parſnip. Red clover, in that reſpect, may be put in the ſame claſs with turnip.

Whether potatoes or turnip be the more gentle crop, appears a puzzling queſtion. The former bears ſeed, and probably draws more nouriſhment from the ſoil than the latter, when cut green. On the other hand, potatoes divide the ſoil more than turnip, and leave it more looſe and friable. It appears no leſs puzzling, to determine between cabbage and turnip: the former draws more of its nouriſhment from the air, the latter leaves the ſoil more free and open.

Here are a number of facts: What is the reſult of the whole? Clearly what follows. Culmiferous plants are robbers; ſome more, ſome leſs: they at the ſame time bind the ſoil; ſome more, ſome leſs. Leguminous plants in both reſpects are oppoſite; if any of them rob the ſoil, it is in a very ſlight degree; and all of them without exception looſen the ſoil. A culmiferous crop, however, is generally the more profitable: but few ſoils can long bear the burden of ſuch crops, unleſs relieved by interjected leguminous crops. Theſe, on the other hand, without a mixture of culmiferous crops, would ſoon render the ſoil too looſe.

Theſe preliminaries will carry the farmer ſome length in directing a proper rotation of crops. Where dung, lime, or other manure, can be procured in plenty to recruit the ſoil after ſevere cropping, I know no rotation more proper or profitable in a ſtrong ſoil, than wheat, peaſe or beans, barley, oats, fallow. The whole farm may be brought under this rotation, except ſo far as hay is wanted. But as ſuch command of manure is rare, it is of more importance to determine what ſhould be the rotation, where no manure can be procured but the dung collected in the farm. Conſidering that culmiferous crops are the more profitable in rich land, it would be proper to make them more frequent than the other kind. But as there are few ſoils in Scotland that will admit ſuch frequent culmiferous crops without ſuffering, it may be laid down as a general rule, that alternate crops, culmiferous and leguminous, ought to form the rotation. Nor are there many ſoils that will ſtand good, even with this favourable rotation, unleſs relieved from time to time by paſturing a few years. If ſuch extended rotation be artfully carried on, I take it for granted, that crops without end may be obtained in a tolerable good ſoil, without any manure but what is produced in the farm.

Having diſcuſſed the nature of plants, as far as rotation of crops is concerned, the nature of the ſoil comes next under conſideration. It is ſcarce neceſſary to be mentioned, being known to every farmer, that clay anſwers beſt for wheat, moiſt clay for beans, loam for barley and peaſe, light ſoil for turnip, ſandy ſoil for rye and buck wheat; and that oats thrive better in coarſe ſoil than any other grain. Now, in directing a rotation, it is not ſufficient that a culmiferous crop be always ſucceeded by a leguminous: attention muſt be alſo given, that no crop be introduced that is unfit for the ſoil. Wheat, being a great binder, requires more than any other crop a leguminous crop to follow. But every ſuch crop is not proper: potatoes are the greateſt openers of ſoil; but they are improper in a wheat-ſoil. Neither will turnip anſwer, becauſe it requires a light ſoil. A very looſe ſoil, after a crop of rye requires ryegraſs to bind it, or the treading of cattle in paſturing: but to bind the ſoil wheat muſt not be ventured; for it ſucceeds ill in looſe ſoil.

Another conſideration of moment in directing the rotation, is to avoid crops that encourage weeds. Peaſe is the fitteſt of all crops for ſucceeding

ceeding to wheat, becauſe it renders the ground, looſe and mellow, and the ſame ſoil agrees with both. But beware of peaſe, unleſs the ſoil be left by the wheat perfectly free of weeds; becauſe peaſe, if not an extraordinary crop, foſter weeds. Barley may be ventured after wheat, if the farmer be unwilling to loſe a crop. It is indeed a robber; better however any crop than run the hazard of poiſoning the ſoil with weeds. But to prevent the neceſſity of barley after wheat, the land ought to be fallowed before the wheat: it cleans the ground thoroughly, and makes peaſe a ſecure crop after wheat. And after a good crop of peaſe, barley never fails. A horſe-hoed crop of turnip is equal to a fallow for rooting out weeds; but turnip does not ſuit land that is proper for wheat. Cabbage does well in wheat-ſoil; and a horſe-hoed crop of cabbage, which eradicates weeds, is a good preparation for wheat to be ſucceeded by peaſe; and a crop of beans diligently hand-hoed is in that view little inferior. As red clover requires the ground to be perfectly clean, a good crop of it enſures wheat, and next peaſe. In loam, a drilled crop of turnip or potatoes prepares the ground, equal to a fallow, for the ſame ſucceſſion.

Another rule is, to avoid a frequent repetition of the ſame ſpecies; for to produce good crops, change of ſpecies is no leſs neceſſary than change of ſeed. The ſame ſpecies returning every ſecond or third year, will infallibly degenerate, and be a ſcanty crop. This is remarkably the caſe of red clover. Nor will our fields bear pleaſantly perpetual crops of wheat after fallow, which is the practice of ſome Engliſh farmers.

Hitherto of rotation in the ſame field. I add one rule concerning rotation in different fields; which is, to avoid crouding crops one after another in point of time; but to chuſe ſuch as admit intervals ſufficient for leiſurely dreſſing, which gives opportunity to manage all with the ſame hands, and with the ſame cattle; for example, beans in January or February, peaſe and oats in March, barley and potatoes in April, turnip in June or July, wheat and rye in October.

For illuſtrating the foregoing rules, a few inſtances of exceptionable rotations, will not be thought amiſs. The following is an uſual rotation in Norfolk. Firſt, wheat after red clover. Second, barley. Third, turnip. Fourth, barley with red clover. Fifth, clover cut for hay. Sixth, a ſecond year's crop of clover commonly paſtured. Dung is given to the wheat and turnip. Againſt this rotation ſeveral objections lie. Barley after wheat is improper. The two crops of barley are too near together. The ſecond crop of clover muſt be very bad, if paſturing be the beſt way of conſuming it; and if bad, it is a great encourager of weeds. But the ſtrongeſt objection is, that red clover repeated ſo frequently in the ſame field cannot

not fail to degenerate; and of this the Norfolk farmers begin to be ſenſible. Salton in East Lothian is a clay ſoil; and the rotation there is, wheat after fallow and dung. Second, barley after two ploughings; the one before winter, the other immediately before the ſeed is ſown. Third, oats. Fourth, peaſe. Fifth, barley. Sixth, oats: and then fallow. This rotation conſiſts chiefly of robbing crops. Peaſe are the only leguminous crop, which even with the fallow is not ſufficient to looſen a ſtiff ſoil. But the ſoil is good, which in ſome meaſure hides the badneſs of the rotation. About Seaton, and all the way from Preſton to Geiſsford, the ground is ſtill more ſeverely handled: wheat after fallow and dung, barley, oats, peaſe, wheat, barley, oats, and then another fallow. The ſoil is excellent; and it ought indeed to be ſo, to ſupport many rounds of ſuch cropping.

But let not our wonder be confined to this narrow ſpot; for what better do we find in the greateſt part of this county? In the pariſhes of Tranent, Aberlady, Dirleton, Northberwick, and Athelſtonefoord, the following rotations were formerly univerſal, and to this day are much more frequent than any other mode.

1. After fallow with dung, wheat, barley, oats, peaſe and beans, barley, oats, wheat.

2. After fallow and dung, barley, oats, peaſe and beans, wheat, barley, oats, peaſe, wheat.

3. After fallow and dung, wheat, oats, peaſe, barley, oats, wheat.

4. After fallow and dung, barley, oats, beans, wheat, peaſe, barley, oats.

Eaſt Lothian, time out of mind, has been famous for ſuperior ſkill in agriculture; and yet, to ſeek for inſtruction there, one would be greatly miſled. That county, for the richneſs of its crops, is more indebted to the fertility of its ſoil, than to the ſkill of its farmers. What pity it is, that ſo fine a county ſhould be poſſeſſed by men ſo little grateful to nature for her bounties! But their ingratitude is not ſuffered to paſs with impunity. Every farmer complains that his crops are not ſuch as they have been: the decay is viſible; but the cauſe, however obvious, is not manifeſt to every one. Some few who juſtly aſcribe the decay to ſeverity of cropping, have ventured upon ſome alterations; but ſo imperfectly, from the prepoſſeſſion of former practice, as to have made no conſiderable progreſs. The following rotations, held to be improvements upon the former practice, will juſtify this obſervation.

1. After fallow without dung, barley, clover. Dung laid on the clover-ſtuble, and after a ſingle ploughing, wheat, barley, oats.

2. After fallow with dung, wheat, barley, peaſe, wheat.

3. After fallow with dung, wheat, beans hand-

hoed, wheat, peaſe and beans drilled, wheat with dung, barley, clover. Dung laid on the clover-ſtubble. Spring-wheat, one furrow before winter, and one before ſowing. Turnip broadcaſt, barley and graſs-ſeeds for paſture.

4. After fallow with dung, wheat, barley with clover-ſeed. Clover made hay two years. After the ſecond year's crop, fallow and dung for wheat, barley, oats, peaſe, oats or wheat, turnip with dung, barley, peaſe, barley, oats.

5. Potatoes dunged, wheat, peaſe, barley and graſs-ſeeds.

6. After fallow with dung, wheat, oats, peaſe or clover, wheat, oats, clover. The clover-ſtubble dunged for barley, oats, peaſe after two furrows, wheat after one furrow.

7. Lincoln barley upon ground opened from paſture-graſs, peaſe, wheat, turnip, barley, clover. The ſtubble dunged for wheat, beans, barley, oats.

8. After fallow and dung, barley, clover red and white for hay, paſture ſeven years, oats, peaſe, wheat, barley, oats.

9. Turnip after lime and dung. Barley, with which white clover, yellow clover, ryegraſs, and ribwort, are ſown. Paſtured with ſheep ſeven years, broken up for oats, drilled beans, barley, oats.

Theſe rotations are far from being orthodox; but it is good to be convinced of an error: and when once a reformation is fairly begun, it is to be hoped, that the farmers in the beſt county of Scotland, will at laſt ſettle in ſuch a rotation of crops, as will prove no leſs beneficial to themſelves than to their landlords.

After ſuch ſevere cenſure I would gladly make ſome apology for the Eaſt-Lothian farmers. In the ſeveral Tours of Young the itinerant farmer, are found, in the beſt counties of England, examples without end, of rotations no leſs exceptionable than many of thoſe mentioned.

Where a field is laid down for paſture in order to be recruited, it is commonly left in that ſtate many years; for it is the univerſal opinion, that the longer it lies, the richer it becomes for bearing corn. This I believe to be true; but in order to determine the mode of cropping, the important point is, what upon the whole is the moſt profitable rotation; not what may produce luxuriant crops at a diſtant period. Upon that point, I have no heſitation to affirm, that the farmer who keeps a field in paſture beyond a certain time, loſes every year conſiderably; and that a few luxuriant crops of corn, after twenty years of paſture, and ſtill more after thirty, will not make up the loſs. The novelty of this propoſition will diſcredit it with the generality; but as the ſubject is of capital importance in the management of a farm, I muſt notwithſtanding hope for a patient hearing. Graſs-ſeeds intended for hay, produce the weightieſt crop at firſt: were hay to be taken many years ſucceſſively without manure, the crops would turn exceeding ſcanty. To prevent loſs, the farmer confines himſelf to two or three crops, and then ſurrenders the field to paſture. The ſame happens where a field is laid down with paſture-graſſes: the firſt year's paſture is more plentiful than any of the ſucceeding. For a proof of which, a field newly laid down for paſture will draw a greater rent, than after being paſtured ſeven or eight years; if I ſhould ſay double, it would not be far from truth. Nor is it difficult to aſſign a cauſe for the degeneracy. A tree deprived of its top, ſpreads into a buſh, and never again takes to a head. Graſs plants are ſimilar: the beſt crops are always at firſt; and they leſſen gradually, becauſe the plants dwarf gradually. Theſe plants have certainly not better *ſtamina vitæ* than an oak: if the latter turn dwarfiſh by having its head lopped off, what can be expected from humble vegetables that are cropped every day and every hour? The dwarfing of plants however is confined within a certain limit; otherwiſe they would in time diſappear altogether. But as they never after increaſe in ſize, they cannot give much food. The food they give, improves indeed in quality, and turns richer the older it is; which is viſible by the effects of old graſs upon milk, butter, beef, and mutton. Old graſs is valuable in point of luxury, but far from valuable in point of profit. The preciſe time when graſs ought to yield to corn, depends greatly on the nature of the ſoil. Our beſt director is practice. I will only venture to ſuggeſt, that clay ſoil may, without loſs, be kept in paſture much longer than gravelly or light ſoil. The former being retentive of moiſture, preſerves graſs in vigour, even during the heat of ſummer: graſs in the latter ſoon withers by lack of moiſture. This is providential: a light or gravelly ſoil can be cultivated almoſt in any ſeaſon: clay is extremely tickliſh; and where ſucceſsfully laid down for paſture, one would not be in a hurry to take it up again; eſpecially as it maintains more cattle, and conſequently receives more dung, than the other kind. It is extremely true, that a greater number of corn-crops may be ſucceſsfully taken upon a field that has been long in paſture, than when paſtured but a few years. But will the additional crops of corn overbalance the mean returns from old graſs? Far from it. Why not then reſtore a field to corn as ſoon as the paſture begins to fail? The corn will quadruple the value of the paſture: the labour indeed and expence is greater; but they will be amply recompenſed by the profit.

Though there can lie no objection againſt this mode of cropping with reſpect to profit, a ſpecious objection may occur with reſpect to the effect it has upon the ſoil. It may be ſuſpected with ſome ſhew of reaſon, that plentiful crops without

reſt,

crops must in time exhauſt the ſoil, unleſs prevented by extraordinary manure. Experience is our only means for clearing that doubt; but till the truth be aſcertained by experience, one would not heſitate to venture a mode of cropping that is clearly ſo profitable; conſidering, that, at the worſt, the ſoil can be reſtored by diligent culture, and extraordinary manure. But I ſay more. It will be made evident in the ſecond part, that a ſoil well pulverized, and yet not too looſe, is what affords the greateſt quantity of food to plants. Now the mode of cropping above recommended is intended to preſerve the ſoil in that ſtate, and muſt infallibly anſwer the purpoſe. However plentiful therefore the crops may be, this mode of cropping cannot exhauſt the ſoil.

To be obliged to ſtand ſingle againſt all the world, would make me tremble like an aſpin leaf, were it not impreſſed upon me, that the difference is greater in appearance than in reality. What I have all along had in view, is a field ſown with graſs-ſeeds; not for hay, but for paſture, ſuch as white clover, yellow clover, ribwort, rye-graſs. The firſt crop of ſuch graſſes is undoubtedly the weightieſt; and there is a diminution in quantity annually, till after ſeven or eight years there is not half of the food for cattle that was at firſt. The plan recommended above, is to take up the field at that period; and after a few corn-crops, to lay it down again for paſture. The opition, I am opposing, is certainly right according to the common method of laying down ground for graſs. This method is, to ſow the field with ryegraſs and red clover; and, after taking hay two years, to ſurrender it for paſture. By this method, the paſture muſt undoubtedly be worſt at firſt: at the end of the two years the red clover is gone, leaving nothing but the ryegraſs, which does not occupy the fifth part of the ground. The field accordingly is exceedingly bare for three or four years; and is not covered till natural graſſes ſpring up to fill the place of thoſe that are gone, which, in clay ſoil eſpecially, will be very late. From this time, the paſture mends as the natural graſſes thicken; and after a certain period, if they do not improve in quantity, they certainly improve in quality. But not to mention, that graſſes which thus occaſionally occupy a field, are not equal to ſown graſſes for feeding; what I affirm is, that the farmer pays dear for them, when he muſt ſubmit in the interim to very ſcanty crops.

If the leſſon here inculcated be ſolidly founded, it muſt produce a great change in the management of a farm. Paſture-graſs, while young, maintains many animals; and the field is greatly recruited by what they drop: it is even recruited by hay-crops, provided the graſs be cut before feeding. But as old graſs yields little profit, the field ought to be taken up for corn when the paſture fruit begins to fail; and after a few crops, it ought to be laid down again with graſs-ſeeds. Seduced by a chimerical notion, that a field, by frequent corn-crops, is fatigued and requires reſt, like a labouring man or animal, careful farmers give long reſt to their fields by paſture, never adverting that it affords little profit. Pity it is, that by a chimerical notion they ſhould be tantalized, to neglect good crops within their reach. It ought to be their ſtudy, to improve their ſoil, by making it free and alſo retentive of moiſture. If they accompliſh theſe ends, they need not be afraid of exhauſting the ſoil by cropping *.

Where a farmer has acceſs to no manure but what is his own production, the caſe under conſideration, there are various rotations of crops, all of them good, though perhaps not equally ſo. I ſhall begin with two examples, one in clay, and one in free ſoil, each of the farms ninety acres. Six acres are to be incloſed for a kitchen-garden, in which there muſt be annually a crop of red clover, for ſummer-food to the working cattle. As there are annually twelve acres in hay, and twelve in paſture, a ſingle plough with good cattle will be ſufficient to command the remaining ſixty acres.

---

* As vegetable and animal food are equally natural to man, it is admirable in Providence, to adjuſt the ſoil he treads on ſo happily to his nature, as to yield him more food by a rotation of corn and graſs crops, than if it were confined to either.

Rotation

### *Rotation in a clay ſoil.*

| | 1775. | 1776. | 1777. | 1778. | 1779. | 1780. |
|---|---|---|---|---|---|---|
| 1. | Fallow. | Wheat. | Peaſe. | Barley. | Hay. | Oats. |
| 2. | Wheat. | Peaſe. | Barley. | Hay. | Oats. | Fallow. |
| 3. | Peaſe. | Barley. | Hay. | Oats. | Fallow. | Wheat. |
| 4. | Barley. | Hay. | Oats. | Fallow. | Wheat. | Peaſe. |
| 5. | Hay. | Oats. | Fallow. | Wheat. | Peaſe. | Barley. |
| 6. | Oats. | Fallow. | Wheat. | Peaſe. | Barley. | Hay. |
| 7. | Paſture. | Paſture. | Paſture. | Paſture. | Paſture. | Paſture. |

When the rotation is completed, the ſeventh incloſure having been ſix years in paſture, is ready to be taken up for a rotation of crops, which begins with oats in the year 1781, and proceeds as in the ſixth incloſure. In the ſame year 1781, the fifth incloſure is made paſture; for which it is prepared, by ſowing paſture graſs-ſeeds with the barley of the year 1780. And in this manner may the rotation be carried on without end. Here the labour is equally diſtributed; and there is no hurry nor confuſion. But the chief property of this rotation is, that two culmiferous or white-corn crops, are never found together: by a due mixture of crops, the ſoil is preſerved in good heart without any adventitious manure. At the ſame time, the land is always producing plentiful crops: neither hay nor paſture get time to degenerate. The whole dung is laid upon the fallow.

Every farm that takes a graſs-crop into the rotation muſt be incloſed, which is peculiarly neceſſary in a clay ſoil, as nothing is more hurtful to clay than poaching.

### *Rotation in a free ſoil.*

| Incloſ. | 1775. | 1776. | 1777. | 1778. | 1779. | 1780. |
|---|---|---|---|---|---|---|
| 1. | Turnip. | Barley. | Hay. | Oats. | Fallow. | Wheat. |
| 2. | Barley. | Hay. | Oats. | Fallow. | Wheat. | Turnip. |
| 3. | Hay. | Oats. | Fallow. | Wheat. | Turnip. | Barley. |
| 4. | Oats. | Fallow. | Wheat. | Turnip. | Barley. | Hay. |
| 5. | Fallow. | Wheat. | Turnip. | Barley. | Hay. | Oats. |
| 6. | Wheat. | Turnip. | Barley. | Hay. | Oats. | Fallow. |
| 7. | Paſture. | Paſture. | Paſture. | Paſture. | Paſture. | Paſture. |

For the next rotation, the ſeventh incloſure is taken up for corn, beginning with an oat-crop, and proceeding in the order of the fourth incloſure, in place of which, the third incloſure is laid down for paſture, by ſowing paſture-graſſes with the laſt crop in that incloſure, being barley. This rotation has all the advantages of the former. Here the dung is employed on the turnip-crop.

We proceed to conſider what rotation is proper
r carſe clay. The farm I propoſe conſiſts of
venty-three acres. Nine are to be incloſed for
kitchen-garden, affording plenty of red clover
be cut green for the farm-cattle. The remain-
g ſixty-four acres are divided into four inclo-
res, ſixteen acres each, to be cropped as in the
llowing table.

| Inclof. | 1775. | 1776. | 1777. | 1778. |
|---|---|---|---|---|
| 1. | Beans. | Barley. | Hay. | Oats. |
| 2. | Barley. | Hay. | Oats. | Beans. |
| 3. | Hay. | Oats. | Beans. | Barley. |

proved ſucceſsful in a ſoil proper for wheat. 1. Oats with red clover, after fallow, without dung. 2. Hay. The clover-ſtubble dunged, and wheat ſown end of October with a ſingle furrow. 3. Wheat. 4. Peaſe. 5. Barley. Fallow again. Oats are taken the firſt crop to ſave the dung for the wheat. Oats always thrive on a fallow, though without dung; which is not the caſe of barley. But barley ſeldom fails after peaſe. In ſtrong clay ſoil, the following rotation anſwers. 1. Wheat after fallow and dung. 2. Beans ſown under furrow as early as poſſible. Above the beans, ſow peaſe end of March, half a boll per acre, and harrow them in. The two grains will ripen at the ſame time. 3. Oats or barley on a winter-furrow with graſs-ſeeds. 4. Hay for one year or two; the ſecond growth paſtured. Lay what dung can be ſpared on the hay-ſtubble, and ſow wheat with a ſingle furrow. 5. Wheat. 6. Beans or peaſe. 7. Oats. Fallow again.

## CHAP. VIII.

## REAPING CORN AND HAY CROPS, AND STORING THEM UP FOR USE.

CULMIFEROUS plants are ripe when the ſtem is totally white: they are not fully ripe if any green ſtreaks remain. Some farmers are of opinion, that wheat ought to be cut before it is fully ripe. Their reaſons are, firſt, that ripe wheat is apt to ſhake, and, next, that the flour is not ſo good. With reſpect to the laſt, it is contrary to nature, that any ſeed can be better in an unripe ſtate, than when brought to perfection: nor will it be found ſo upon trial. With reſpect to the firſt, wheat, at the point of perfection, is not more apt to ſhake than for ſome days before: the huſk begins not to open till after the ſeed is fully ripe; and then the ſuffering the crop to ſtand becomes tickliſh: after the minute of ripening, it ſhould be cut down in an inſtant, if poſſible.

This leads to the hands that are commonly engaged to cut down corn. In this country, the univerſal practice was, to provide a number of hands, in proportion to the extent of the crop, without regard to the time of ripening. By this method, the reapers were often idle for want of work; and what is much worſe, they had often more work than they could overtake, and ripe fields were laid open to ſhaking winds. The Lothians have long enjoyed weekly markets for reapers, where a farmer can provide himſelf with the number he wants; and this practice is creeping into neighbouring ſhires. Where there is no opportunity of ſuch markets, ought not neighbouring farmers to agree in borrowing and lending their reapers? The advantage is obvious; and yet I believe it is ſeldom practiſed.

One ſhould imagine, that a caveat againſt cutting corn when wet, is unneceſſary; yet from the impatience of farmers to prevent ſhaking, no caveat is more ſo. Why do they not conſider, that corn ſtanding, dries in half a day, when in a cloſe ſheaf, the weather muſt be favourable if it dry in a month? in moiſt weather it will never dry.

With reſpect to the manner of cutting, I muſt premiſe, that barley is of all the moſt difficult grain to be dried for keeping. Having no huſk, rain has eaſy acceſs; and it has a tendency to malten when wet. Where the ground is properly ſmoothed by rolling, I am clear for cutting it down with the ſythe. This manner being more expeditious than the ſickle, removes it ſooner from the danger of wind; and gives a third more ſtraw, which is a capital article for dung, where a farm is at a diſtance from other manure. I except only corn that has lodged; for there the ſickle is more convenient than the ſythe. As it ought to be dry when cut, bind it up directly: if allowed to lie any time in the ſwath, it is apt to be diſcoloured.

Barley ſown with graſs-ſeeds, red clover eſpecially, requires a different management. Where the graſs is cut along with it, the difficulty is great of getting it ſo dry as to be ventured in a ſtack. The cunning way is, to cut the barley with a ſickle above the clover, ſo as that nothing but clean barley is bound up. Cut with a ſythe the ſtubble and graſs: they make excellent winter-food. The ſame method is applicable to oats; with this only difference, that when the field is expoſed to the ſouth-weſt wind, it is leſs neceſſary to bind immediately after mowing. As wheat commonly grows higher than any other grain, it is difficult to manage it with the ſythe; for which reaſon the ſickle is preferred in England. Peaſe and beans grow ſo irregularly, as to make the ſickle neceſſary.

The beſt way for drying peaſe, is to keep ſeparate the handfuls that are cut: though in this way they wet eaſily, they dry as ſoon. In the common way of heaping peaſe together for compoſing a ſheaf, they wet as eaſily, and dry not near ſo ſoon. With reſpect to beans, the top of the handful laſt cut, ought to be laid on the bottom of the former; which gives ready acceſs to the wind. By this method peaſe and beans are ready for the ſtack in half the ordinary time.

The ſize of the ſheaves ought to be regarded. A ſheaf commonly is made as large as can be contained in two lengths of the corn made into a rope. To ſave frequent tying, the binder preſſes it down with his knee, and binds it ſo hard as totally to exclude the air. If there be any moiſture in the crop, which ſeldom fails, a proceſs of fermentation and putrefaction commences in the ſheaf; which is perfected in the ſtack, to the deſtruction both of corn and ſtraw. How barba-

rous

lous and ſtupid is it, to make the ſize of a ſheaf depend on the height of the plants! By that rule, a wheat-ſheaf is commonly ſo weighty, as to be unmanageable by ordinary arms: it requires an effort to move it, that frequently burſts the knot, and occaſions loſs of grain, beſide the trouble of a ſecond tying. I have long practiſed the following method with ſucceſs. My ſheaves are never larger than to be contained in one length of the plant, cut cloſe to the ground: I admit no exception if the plants be above eighteen inches high. The binder's arm compreſſes the ſheaf ſufficiently, without need of his knee. The additional hands that this way of binding may require, are not to be regarded, compared with the advantage of drying ſoon. Corn thus managed may be ready for the ſtack in a week: it ſeldom in the ordinary way requires leſs than a fortnight, and frequently longer. Of a ſmall ſheaf compreſſed by the arm only, the air pervades every part; nor is it ſo apt to be unlooſed as a large ſheaf, however firmly bound. I omit the gathering of ſheaves into ſhocks, becauſe the common method is orthodox, which is to place the ſhocks directed to the ſouth-weſt, in order to reſiſt the force of that wind. Five ſheaves on each ſide make a ſufficient ſtay; and a greater number cannot be covered with two head-ſheaves.

Every article is of importance that haſtens the operation, in a country like Scotland, ſubjected to unequal harveſt-weather; for which reaſon, the moſt expeditious method ſhould be choſen for carrying corn from the field to the ſtack-yard. Our carriages are generally too ſmall or too large. A ſledge is a very aukward machine: many hands are required, and little progreſs made. Waggons and large carts are little leſs dilatory, as they muſt ſtand in the yard till unloaded ſheaf by ſheaf. My way is, to uſe long carts moveable upon the axle, ſo as at once to throw the whole load on the ground; which is forked up to the ſtack by a hand appointed for that purpoſe. By this method, two carts will do the work of four or five.

It will not be eaſy to convince me, that building round ſtacks in the yard is not preferable to houſing the corn. There it is ſhut up from the air; and it muſt be exceedingly dry, if it contract not a muſtineſs, which is the firſt ſtep to putrefaction. Let me add another circumſtance, which would make a figure were it detached from that now mentioned. In the yard, a ſtack is preſerved from rats and mice by being ſet on a pedeſtal: no method has hitherto been invented, for preſerving corn in a houſe from ſuch deſtructive vermin. The proper manner of building, is to make every ſheaf incline downward from its top to its bottom. Where the ſheaves are laid horizontally, the ſtack will take in rain both above and below. The beſt form of a ſtack is that of a cone placed on a cylinder; and the top of the cone ſhould be formed with three ſheaves drawn to a point. If the upper part of the cylinder be a little wider than the under, ſo much the better.

The delaying to cover a ſtack for two or three weeks, though common, is however wonderfully abſurd; for if much rain fall in the interim, it is beyond the power of wind to dry the ſtack. Vegetation begun in the external parts, ſhuts out the air from the internal; and to prevent a total putrefaction, the ſtack muſt be thrown down, and expoſed to the air, every ſheaf. In order to have a ſtack covered the moment it is finiſhed, ſtraw and ropes ought to be ready; and the covering ought to be ſo thick as to be proof againſt rain.

Scotland is ſubject not only to floods of rain, but to high winds. Good covering guards againſt the former, and ropes artfully applied guards againſt the latter. I will anſwer for the following mode. Take a hay-rope well twiſted, and ſurround the ſtack with it, two feet or ſo below the top. Surround the ſtack with another ſuch rope immediately below the eaſing. Connect theſe two with ropes in an up and down poſition, diſtant from each other at the eaſing about five or ſix feet. Then ſurround the ſtack with other circular ropes parallel to the two firſt mentioned, giving them a twiſt round every one of thoſe that lie up and down, by which the whole will be connected together in a ſort of network. What remains is, to finiſh the two feet at the top of the ſtack. Let it be covered with bunches of ſtraw laid regularly up and down; the under part to be put under the circular rope firſt mentioned, which will keep it faſt, and the upper part be bound by a ſmall rope artfully twiſted, commonly called *the crown of the ſtack*. This method is preferable to the common way of laying long ropes over the top of the ſtack, and tying them to the belting-rope; which flattens the top, and makes it take in rain. A ſtack covered in the way here deſcribed, will ſtand two years ſecure both againſt wind and rain; a notable advantage in this variable climate. So much for corn. Now for hay.

The great aim in making hay is, to preſerve as much of the ſap as poſſible. All agree in this; and yet differ widely in the means of making that aim effectual. To deſcribe all the different means might be profitable to the bookſeller; but the reader would loſe patience, and gather no inſtruction. I ſhall therefore confine myſelf to what I think the beſt. A crop of ryegraſs and yellow clover ought to be ſpread as cut. A day or two after, when the dew is evaporated, rake it into a number of parallel rows along the field, termed *wind-rows*, for the convenience of putting it up into ſmall cocks. After turning the rows once and again, make ſmall cocks weighing a ſtone or two. At the diſtance of two days or ſo, put two cocks into one, obſerving always to mix the tops and bottoms together, and to take a new place for each cock, that the leaſt damage poſſible may be done to the graſs. Proceed in putting two cocks into one, till ſufficiently dry for tramp-ricks of 100 ſtone each. The eaſieſt way of erecting tramp-ricks, is to found a rick in the middle of the row of cocks that are to compoſe it. The cocks may be carried to the rick by two perſons joining arms together. When all the cocks are thus carried to the rick within the diſtance of forty yards or ſo, the reſt of the cocks will be more expeditiouſly carried to the rick, by a rope wound about them and dragged by a horſe. Two ropes are ſufficient to ſecure the ricks from wind, the ſhort time they are to ſtand in the field. This very year, 1775, ten thouſand ſtone were put into tramp-ricks the fourth day after cutting. In a country ſo wet as many parts of Scotland are, expedition is of mighty conſequence in the drying both of hay and corn. With reſpect to hay intended for horned cattle, it is by the generality held an improvement, that it be heated a little in the ſtack. But I violently ſuſpect this doctrine to have been invented for excuſing indolent management. An ox, it is true, will eat ſuch hay; but I have always found that he prefers ſweet hay; and it cannot well be doubted, but that ſuch hay is the moſt ſalutary and the moſt nouriſhing.

The making hay conſiſting chiefly of red clover, requires more care. The ſeaſon of cutting is the laſt week of June, when it is in full bloom:

earlier it may be cut; but never later. To cut it later, would indeed produce a weightier crop; but a late firſt cutting makes the ſecond alſo late, perhaps too late for drying. At the ſame time, the want of weight in an early firſt cutting, is amply compenſated by the weight of the ſecond.

The additional labour required to make hay of red clover, ariſes from the largeneſs of the ſtem, and the hazard of the leaves dropping off in moiſt weather. I have tried two methods. One is, to let it lie in the ſwath two days, and longer if the weather be unfavourable. The ſwaths muſt be turned over and over two or three times every day, but not unleſs the weather be dry. It will then be ready to be put into cocks, containing each about two ſtone. After two, three, or four days, according to the weather, let two cocks be put into one; and ſo on at proper intervals till ready for the tramp-rick. The other way, more expeditious, may be ventured on where ryegraſs is mixed with the clover. Stir it not the day it is cut. Turn it in the ſwath the forenoon of the next day; and in the afternoon put it up in ſmall cocks. The third day, put two cocks into one, enlarging every day the cocks till they be ready for the tramp-rick.

When the ſeaſon is too variable for making hay of the ſecond growth, mix ſtraw with that growth, which will be a ſubſtantial food for cattle during winter. This is commonly done by laying ſtrata of the ſtraw and clover alternately in the ſtack. But this method I cannot approve: if the ſtratum of clover take heat, they turn mouldy at leaſt, and unpalatable. The better way is, to mix them carefully with the hand before they be put into the ſtack. The dry ſtraw imbibes moiſture from the clover, and prevents heating.

I muſt add in general with reſpect to hay of whatever kind, that if the weather be ſo wet as to prevent cocking in the ordinary time, there ought to be no intermiſſion in turning the ſwaths; which will help to evaporate the moiſture, if there be any motion in the air; and at the ſame time, prevent the ſwaths from ſinking into the ground among the uncut graſs, which never fails to blanch it.

The expence of making an acre of hay, compoſed of ryegraſs and yellow clover, is, in a tolerable ſeaſon, from four to ſix ſhillings; and from ſix to eight if compoſed of red clover. This however is an uncertain computation, the expence differing greatly in a good or bad ſeaſon.

I will not ſtop to give any rule for making hay of natural graſs, termed *meadow-hay*; becauſe in a well-conducted farm there ought to be no meadow-hay. This is made evident in the chapter *Rotation of Crops*.

In the yard, a ſtack of hay ought to be an oblong ſquare, if the quantity be greater than to be eaſily ſtowed in a round ſtack; becauſe a ſmaller ſurface is expoſed to the air, than in a number of round ſtacks. For the ſame reaſon, ſtacks of peaſe ought to have the ſame form, the fodder being more valuable than that of oats, wheat, or barley. The moment a ſtack is finiſhed, it ought to be covered; becauſe the ſurface-hay is much damaged by withering in dry weather, and moiſtening in wet weather. Let it have a pavilion-roof; for more of it can be covered with ſtraw in that ſhape, than when built perpendicular at the ends. Let it be roped as directed above for corn-ſtacks; with this difference only, that in an oblong ſquare the ropes muſt be thrown over the top, and tied to the belt-rope below. This belt-rope ought to be fixed with pins to the ſtack; the reaſon is, that the ropes thrown over the ſtack will bag by the ſinking of the ſtack, and may be drawn tight by lowering the belt-rope, and fixing it in its new poſition with the ſame pins.

The ſtems of hops, being long and tough, make excellent ropes; and it will be a ſaving article, to propagate a few plants of that kind for that very end.

A ſtack of ryegraſs-hay, a year old, and of a moderate ſize, will weigh, each cubic yard, eleven Dutch ſtone. A ſtack of clover-hay in the ſame circumſtances weighs ſomewhat leſs.

I conclude this article with obſerving, that till lately the making hay was little underſtood in

Scotland; nor to this day is it generally altered. The method was, to expoſe it as much as poſſible to the ſun and wind, and never to give it reſt till it was ſo dry as to be grindable in a mill, and rendered a *caput mortuum*. The poor animals reduced to ſuch food, were truly to be pitied; was it wonderful that they were too feeble for work? But this made no impreſſion; as the feebleneſs of the cattle was but in proportion to the lazineſs of the men. They had no check of conſcience for being idle, becauſe they were educated in that way, and knew no better.

## C H A P. IX.

### Feeding Farm-Cattle.

Having diſcuſſed the management of corn and hay, what naturally follows is, to apply them to the maintenance of farm-cattle: for to conſider them as the food of human beings, falls not properly under any branch of agriculture.

As in this chapter are contained many different matters upon which the profit of a farm greatly depends, I wiſh to inculcate what I have to ſay with perſpicuity. In that view the chapter is divided into five ſections. Green food is the ſubject of the firſt; dry food, of the ſecond; feeding for the butcher, of the third: the fourth con-

ns rules for the wintering of cattle that are not
ended for immediate ſale ; and the fifth, rules
buying and ſelling cattle and corn.

## 1. GREEN FOOD.

I begin this ſection with the ſummer-food of
m-horſes. The manner of feeding them du-
g ſummer, is and has been various through
otland : none of them good. Some time ago,
rſes were fed in balks between ridges of corn,
ich required the attendance of men, and wa-
d much time. In many parts, horſes are re-
ced to thiſtles ; the time of the men being conſu-
d in pulling, and of the horſes in eating. In

forced in hot weather with flies, and cannot feed with eaſe. In the next place, they have no time for reſting; and much time is loſt in laying hold of them for the yoke. Laſtly, few incloſures in the hands of a tenant, are in ſo good order as to keep in horſes when they ſee corn; and if they once break out, it is in vain to think of impriſoning them after. The approved method to prevent every inconvenience, is to feed the horſes with cut graſs, under cover. In the interval between the work of the forenoon and afternoon, they can fill the belly in an hour, and have time to reſt another hour: nor is a moment loſt in yoking.

Several plants ſerve this purpoſe, ſainfoin, lucern, red clover, white clover, ryegraſs. Red clover is the beſt. Sainfoin and lucern early cut are excellent food; but when they turn ſtrong and reedy, horſes are not fond of them. The diſadvantage of white clover and ryegraſs, is, that, being ſmall plants, they are difficult to be collected in heaps for food. Red clover is extremely luxuriant: it is eaſily collected; and it ought to be eaſily collected; for to feed properly a horſe of a middle ſize, requires ten ſtone a-day. It flowers the firſt week of June; but in rich ſoil it will riſe to eighteen inches before flowering. So rapid is its growth, that in good ſoil it may be cut thrice in a year, and afford over and above ſome paſture. It ſhould be cut in the morning when moiſt with dew: it is leſs palatable when cut dry. The cutting ought to begin long before flowering, that all may be cut before it is too old, and thus it may grow the faſter for a ſecond cutting. Theſe conſiderations are not ſufficiently attended to: people are loath to cut till the clover is fully grown; tho' early cutting will upon the whole afford more food, as well as more palatable food, to horſes eſpecially, which diſlike old clover. I deſpair not to ſee all the corn-farmers in Scotland, depending on red clover for the ſummer-food of their cattle; and then we ſhall no longer be ſtunned with loud complaints commonly thrown out as excuſes for idleneſs: "How can I improve, having no food "for my horſes but bare lea or thiſtles? they "cannot work on ſuch food; I cannot ſtir a "foot." A horſe works as he is fed: it is ſurpriſing what work he will perform upon cut clover, without loſing fleſh. Many a ſummer, for ſeven or eight weeks running, have my horſes been daily employed in bringing lime from a quarry fifteen Engliſh miles diſtant, fed on red clover only; and at the end of the ſeaſon, as plump and hearty as at the beginning. Let another article be conſidered. In every farm, a great proportion is left out for paſture, if that can be called paſture which affords little or no food. A ſingle acre of good red clover, will give more food than fifteen or twenty ſuch acres. How much better might theſe acres be employed in bearing profitable crops of corn. But a ſkilful farmer will not confine himſelf to red clover for ſummer-food. There are other graſſes that ſpring more early, and grow later than red clover. Ryegraſs, ribwort, and yellow clover, flower a month before red clover, are fully ready for cutting green the middle of May, and if cut at that time continue growing, and may be cut a fortnight after red clover is gone. To enlarge the period of green food for cattle, is a deſirable object in huſbandry. It affords plenty of food both early and late; it ſaves paſture-fields in ſpring till the graſs cover the ground, which retains the dew, and ſhelters the graſs-roots from withering winds; and it enables the farmer to leave his fields rough at the end of the ſeaſon to keep out the froſt during winter, inſtead of eating them bare, which is the ordinary practice. Now theſe ſalutary effects, all of them, may be procured by a very ſimple operation; which is, to ſow part of the field with ryegraſs, ribwort, and yellow clover mixed. Theſe plants are ready for being cut the middle of May; and if the ſeaſon prove favourable, they may be cut again as late as even the middle of November. Cut graſs is of all the cheapeſt food, and the moſt agreeable to horſes; and therefore to add a month of this food, is a valuable improvement; eſpecially during ſpring; for however nouriſhing dry food may be, yet a horſe put upon green food turns remarkably more agile and plump *.

I proceed to the ſummer-food of horned cattle. A beaſt that chews the cud, takes in at once a

* It may be agreeable to bring under one view the graſſes mentioned above, with reſpect to the ſeaſon of their ſhooting and ripening.

Ryegraſs ſown in ſpring with corn, ſhoots the year following, from the 20th to the 30th of April, according to the ſoil and ſeaſon. It flowers from the 1ſt to the 10th of June. The flower continues about eight days, falls off, and the ſeed at that time begins to form. The ſeed is ripe between 1ſt and 10th July. When it is fully formed, the ſtalk begins to turn brown; and more and more ſo till the ſeed fall, which is about the end of July.

Ribwort ſhoots the laſt week of April. The head in a thriving plant is three inches long, full of ſeed, which is completely ripe about the 19th of July. Upon the head are found at the ſame time ſeed formed, flowers, and part that has not yet flowered.

Red clover ſhoots from the 1ſt to the 10th of June; and in eight days after begins to flower. It continues in flower twenty days; and about the end of July the ſeed is ripe. The progreſs of white clover is preciſely the ſame.

Yellow clover ſhoots the laſt week of April, and flowers till Auguſt. On a ſtalk is found at the ſame time, ſeed ripe, ſeed half ripe, flowers, and ſhoots juſt beginning. It accordingly reſembles peaſe, and grows a long time. Its continual growing keeps the ſtem full of ſap. The time of cutting plants for hay is in the middle of their flowering; but as yellow clover flowers much longer than the others mentioned, it affords a greater latitude for cutting without injuring the hay.

large quantity of green food, eſpecially of red clover, which is extremely palatable when young. So large a quantity is apt to ferment with the heat of the ſtomach, ſo as ſometimes to make the creature burſt. This is conſidered as a formidable objection to the feeding horned cattle on red clover. But it is eaſily obviated, by feeding them in the houſe; ſervants will not readily give more than ſufficient, when cutting and carrying is a work of labour. And red clover ſhould always be cut for food; for where cattle have liberty to paſture, more is trampled down than is eaten. At any rate, burſting may be prevented even when cattle are allowed to paſture. Indulge them but half an hour or ſo, for two or three days when the clover is dry; after which there is no hazard. If yellow clover and ribwort be ſown with red clover, there is little or no hazard of fermenting to ſuch a degree as to be hurtful. White clover is no remedy: it ferments in the ſtomach as much as red clover.

Red clover cut green, is preferable to all other food for milk-cows. Being ſoon filled, they have much time to reſt, which increaſes the quantity of milk. The milk at the ſame time is richer and higher coloured, than from any other food.

Red clover is good food for ſheep; but the cutting it for them would be too expenſive. White clover at the ſame time is their favourite, which is never wanting in good ſoil, growing naturally.

ne ſignal advantage of feeding horſes and
ed cattle in the houſe during ſummer, is their
g protected from heat and inſects. And it is
ll more ſignal advantage, that the dung turns
uch better account, than when ſcattered du-
ſummer in a paſture-field. Horſe-dung in a
ure-field is totally loſt : it dries, and withers a-
, not to mention that its heat burns the graſs
lls on. Dung is an article of great import-
, eſpecially in a farm diſtant from other ma-
e. And a dunghill, procured by feeding on
graſs, may be conſiderably increaſed by feed-
the cattle with ſtraw; and by adding to the heap
y weed that grows in the farm, which at any
ought to be cut, to prevent ſeeding.

conſiderable, as to make it of importance to leſſen it. In that view, I recommend the following plan, the purpoſe of which is, to carry cattle to their food, inſtead of carrying food to the cattle. Erect a moveable ſhed in the field, all of wood, the back conſiderably higher than the front, in order to have a ſloping roof againſt rain. Sixteen feet in wideneſs is ſufficient for a beaſt of any ſize; the length correſponding to the number of cattle that are to be fed. On the back at the heads of the cattle, a deal is hung with hinges, to be lifted up for throwing food to them. Upon the ground along the length of the houſe, three beams are laid, croſſed with ſpars an inch diſtant from each other. The channel or gutter behind the cattle, is lined with a deal in the bottom, and one on each ſide, to convey the piſs from the cattle to a pit filled with rich earth; which I hold to be preferable even to dung itſelf. The three beams covered with ſpars make a vacuity below, which receives the piſs at the firſt inſtance, and preſerves the cattle dry. This is an important article in feeding cattle, which every animal at liberty is fond to procure to itſelf. There is no neceſſity for hecks in this ſhed; on the contrary, horſes eat more conveniently in the natural way, by bending down the neck to food. The only thing neceſſary is a board between their fore feet and the clover, to ſave it from being trampled under foot. It is proper that in a corner a bed be erected for a ſervant, to attend the cattle during night. The deals of this ſhade muſt be held together with wooden nails, ſo as eaſily to be taken down, and ſet up again where it may be wanted. It ſhould be placed at the loweſt part of the field, becauſe the clover is more weighty, than the dung it produces. It is poſſible to ſet a little ſhed on wheels to be carried from place to place, without being taken down; but that will never anſwer for a ſhed of thirty or forty yards long. Such a ſhed is proper in every farm, where red clover is annually raiſed in the courſe of cropping; and the expence will be the leſs grudged, conſidering that it alſo anſwers for conſuming turnip and cabbage in winter. Let the expence be computed of carrying theſe to an immoveable ſhed; and in a farm of any extent, it will be found, that the expence thus ſaved, even in a ſingle year, will equal the coſt of the propoſed ſhed. In a ſmall farm, where red clover enters not into the rotation of crops, and yet is neceſſary for ſummer-feeding; the moſt convenient way is, to incloſe ſix or ſeven acres as near as may be to the farm-offices, upon a part of which there always may be a crop of red clover in rotation. In that caſe the carriage is a trifle. I have only to add, that room ſhould not be ſpared; for horſes are hurt as much as horned cattle by being crowded.

The proper ſeaſons for diſpoſing of cattle fatted on graſs, are the June markets, and thoſe of December and January. With a view to the firſt, early graſs ought to be provided; and late graſs with a view to the others. In an open winter, there is no difficulty to preſerve graſs-cattle far through December and January: in a hard winter, the addition of a little hay will do.

Next in order is the feeding cattle in a paſture-field. White clover is for paſture the beſt graſs known in Britain, being extremely palatable to cattle of every kind. Being a native of Britain, it propagates itſelf by ſpreading along the ſurface, and taking root at every joint. But as this is a work of time, it is more profitable to ſtock the field with it at once: thirty pounds of ſeed are no more than ſufficient for an acre. Good ſeed is weighty, and full, without dimples: it is red when hurt in drying. A field intended for paſture, requires a mixture of graſſes: every ſpecies has its favourite graſs; and when animals of different kinds feed together, not a ſingle ſtump is left. Different graſſes alſo, having different times of flowering, keep the chain of food more complete during the ſeaſon. Ryegraſs for example anſwers for ſpring food better than any other plant, and continues longer after autumn. But white clover during ſummer holds out better than ryegraſs. Different graſſes at the ſame time excite the appetite: an ox will leave turnip for cabbage; and after feeding plentifully on both, will take kindly to hay or ſtraw. The proper quantity of ſeed to an acre intended for immediate paſture, is ten pounds white clover, five pounds yellow clover, as much ribbed graſs, and two wheat-firlots of ryegraſs.

A field proper for paſture, ought to have the following properties. It ought to be well aired. Second, well watered. Third, well ſheltered. Fourth, the larger the better. And, laſtly, the graſs ought to be ſo rank as to afford a full bite. With reſpect to the firſt, a field well aired makes cattle feed kindly; in a hot day, they go to the higheſt part for freſh air: if they have neither freſh air nor water to reſort to, they fret, and loſe fleſh. The want however may be ſupplied artificially, by clumps of trees ſcattered through the field, to ſhelter them from the ſun. With reſpect to the ſecond, plenty of water for drinking is not alone ſufficient: there ought to be plenty for bathing in a hot day: cattle are never more at eaſe in ſuch a day, than when they are plunged in water. With reſpect to the third, it is not ſufficient that cattle be ſheltered againſt heat: ſhelter againſt cold is ſtill more neceſſary. By proper management, the chain of graſs may be carried on in tolerable weather till the end of the year; but unleſs the cattle be protected from cold blaſts, graſs will do them little good. The clumps mentioned planted in the form of a croſs, will afford ſhelter from whatever quarter the ſtorm comes. With regard to the fourth, the field ought to be ſo large as to give cattle their natural range. Every ſpecies of animals that feed on graſs have a natural range in feeding; and to confine them within narrower bounds, is to them a ſort of impriſonment. Sheep have a wide range; and ought to have, becauſe they delight in ſhort graſs: give them eighty or ninety acres, and any fence will keep them in: confine them to a field of ſeven or eight acres, and it muſt be a very ſtrong fence that keeps them in. A range of fifty or ſixty acres is ſufficient for horſes; and a ſtill narrower range for horned cattle. In oppoſition to the field deſcribed, advert to cattle cooped up in a ſmall incloſure of eight or nine acres, ſurrounded with high hedges. In ſummer they are ſtifled for want of air, are peſtered with inſects, and loſe fat inſtead of gaining. To examine the progreſs of fattening, I weighed twenty ſtots the firſt day of May and the firſt day of the five ſucceeding months. Their quickeſt advance was in May and September, being at an average two pounds daily each. I could not attribute this to any other cauſe, but to leſs heat and fewer inſects than in the three intermediate months. With reſpect to the property laſt in order, the benefit of a full bite is too obvious to need explanation.

A paſture-field bare of graſs in ſpring, having no protection againſt withering winds, turns hard and unfit for vegetation, eſpecially after wet weather. But where a field ſprings early, and is covered with graſs before drought ſets in, it continues moiſt and tender, by retaining dews and keeping out drought. To encourage early graſs in ſpring, the field ought to be left rough in winter; which alſo keeps the ground warm, and protects the roots from froſt.

Ragwort is a troubleſome gueſt, as it never fails to infeſt rich paſture-fields; it is not only a robber, but overſhadows the graſs, and renders it unwholeſome. I am at a loſs however whether to call it a weed or an uſeful plant. As it bears no ſeed till the third year of its growth, it cannot propagate in land under tillage: in paſture-land, it dies indeed after dropping its ſeed, but new plants ſpring from that ſeed, and have a ſucceſſion without end. Many things in appearance noxious, have been found uſeful; of which this plant is an inſtance. The ſame means will prevent its noxious effects, and make it profitable. Ragwort in flower was never ſeen in a field paſtured with ſheep. Why? becauſe that animal is exceſſively fond of it. Therefore, in every paſture-field, for ſome years after it is laid down, there ought to be a proportion of ſheep. They prefer ragwort before any other vegetable; and experience pronounces, that every food is wholeſome which an animal is fond of. Lincolnſhire ſheep do beſt; becauſe a fence ſufficient for horned cattle, is more than ſufficient for them. Sheep are ſingular with reſpect alſo to other food. They are fond of the tender ſhoots of broom and whins; and no leſs ſo of the fruit of the horſe-cheſnut.

The ruſh may be compared to ragwort: it is a troubleſome weed; and yet may be made in ſome degree profitable. Whether it ſhould be claſſed among the evergreens, appears doubtful from the following account of it. It ſprings ſix or ſeven inches high in April, grows on till Auguſt, when the ſeed appears at the ſide of the ſtem, five or ſix inches below the top. While the ſeed is drawing toward maturity, the part above withers gradually; and when the ſeed ripens and falls, the part below withers down till within a foot or ſo of the ground. That part continues green all winter; but dies away before next ſummer. In place of the ſtems that thus die, freſh ſtems ariſe, which, as obſerved above, make a figure in April. Whether theſe ſtems ariſe from ſeed, or from the bulky root, or from both, I cannot at preſent determine.

As the ruſh is an aquatic, and grows ſo vigorouſly as to deſtroy all other plants, it ought to be rooted out if poſſible; not only becauſe it is a bad paſture-graſs, but becauſe the infallible way of rooting it out is, to lay the ground dry; which makes a double improvement. But if this cannot be got done at a moderate expence, the reſource is, to make all the profit of it that is poſſible. If cut in June while young and tender, and dried into hay, ruſhes make tolerable winter-food: a freſh growth enſues which is proof againſt froſt, and is not unſavoury to cattle that run out all winter.

In the month of April, while graſs is ſtill ſo ſhort as not to afford a bite to horned cattle, I have ſeen fourteen cows living on ruſhes. At that ſeaſon, they are to horned cattle almoſt as palatable as red clover. They are rejected when old; and ſo is even red clover.

A ſprat is not an evergreen, for it dies away in winter. It is an aquatic, like a ruſh, but thrives with a leſs degree of moiſture. It may be of ſome uſe for hay when cut in June; and the after growth is not unpalatable when eat young. But after feeding no beaſt will touch it.

### 2. DRY FOOD.

I proceed now to dry food. As hay is of uſe to cattle of every kind, it is a capital object in huſbandry; and not the leſs capital, that in my thought it may be carried to greater perfection than is commonly done. To give ſatisfaction, we muſt enter into an examination of the different graſſes that are uſed for making hay. Red clover is a ſucculent plant, of the leguminous tribe, that flowers about the beginning of June, and riſes to the height of between three and four feet. Rye-graſs is a culmiferous plant, dry and ſolid, like other plants of that tribe; riſing commonly in good ſoil to four feet, or nearly ſo. It ſhoots the end

April or beginning of May; and above all other plants haſtens to perfect its ſeed. Yellow clover and ribwort, both of them leguminous plants, are more tender and ſucculent than ryegraſs, but leſs ſo than red clover: they riſe commonly to between three and four feet. They ſhoot at the ſame time with ryegraſs, but perfect their ſeed not altogether ſo ſoon. Ryegraſs, becauſe of its ſolidity, is of all the beſt food for horſes; and next to it, yellow clover and ribwort. Horned cattle delight in leguminous plants, red clover eſpecially: it is probable that tender graſſes are fitteſt for animals that chew the cud. White clover blooms and perfects its ſeed at the ſame time with red clover: it makes excellent dry food for ſheep; but as it ſeldom riſes above eighteen inches, it is leſs proper for hay than any of the others mentioned; and upon that account, is often left out in the mixture of graſſes for hay.

With reſpect to the time of endurance, red clover cannot be depended on for hay longer than two years: the third year, it makes at beſt a ſcanty crop, and frequently vaniſhes altogether. Ryegraſs, ribwort, and yellow clover, ſtand good three years. From that time, the product leſſens gradually; and after the ſeventh or eighth year they afford little paſture.

The general practice of Britain has been, to mix for hay, ryegraſs and red clover with a ſmall proportion of white clover; which I believe continues to be the practice in many places.

I

I cannot help condemning it, as the child of ignorance or inattention. Two weighty objections occur. The firſt is, that when the red clover is fit to be cut for hay, which is about the beginning of July, the ryegraſs-ſeed is ripe. And what follows? the ryegraſs that year grows no more than barley or wheat cut when the ſeed is ripe; whereas if ryegraſs be cut before the ſeed is formed, it grows all ſummer, and even all winter, till it makes way for new ſhoots in ſpring. It may poſſibly be thought, that the ſeed, like that of other culmiferous plants, is more than ſufficient to make up the ſcantineſs of ſubſequent cuttings; but in drying for hay, moſt of it is loſt, ſome in the field, ſome in the ſtack, and ſome in the hayloft; little being left but the dry ſtraw, which cattle do not willingly eat. The other objection is of ſtill greater weight. After a crop or two of hay, the field is ſurrendered to paſture. The red clover wears out the ſecond year, leaving nothing but the ryegraſs, which continues but another year in perfection: and the ſmall proportion of white clover has not yet got time to ſpread over the field. Thus, after the ſecond year, the paſture is but indifferent; and turns worſe and worſe unleſs the field happen to ſtock itſelf with natural graſſes. Nor is that all: while the field is but half-ſtocked with ſown graſſes, weeds take poſſeſſion of the vacuities, and accelerate the dwarfing of the ryegraſs and white clover. And if the red clover happen to be a ſcanty crop the ſecond year, it encourages weeds no leſs than a ſcanty crop of plaſter.

I venture to ſuggeſt a better plan for hay than any I have read of. I pronounce the beſt hay for horſes to be a mixture of ryegraſs and yellow clover, which flower together, and are fit to be cut for hay the beginning of June, when ſtill in flower and the ſeed not formed: at that time, being full of ſap, they are in perfection for hay. When cut ſo early, they grow again vigorouſly, and afford a ſecond crop end of September; or excellent paſture, if the ſeaſon be unfavourable for hay. When the firſt cutting is later than beginning of June, the ſtem turns dry and woody; and much of it is rejected, if a horſe be not extremely hungry. But I recommend this to gentlemen only and farmers, for feeding their own horſes. In the view to ſell hay, their profit I acknowledge will be greater in cutting when the ſeed is ripe, becauſe the ſeed is a profitable article. The hay, it is true, ſeparate from the ſeed, is no better than ſtraw: but that is no objection to a ſtabler; for the leſs hay a travelling horſe conſumes, his profit is the greater. My reaſon for chuſing theſe two plants for hay to horſes is, that, of all leguminous plants, yellow clover approaches the neareſt in ſolidity to ryegraſs, and that they dry well together. Ribwort is left out, as being leſs fit for horſes; and where plenty of ſeed is given, the two plants choſen will make a weighty crop as the ground can bear. Three firlots of ryegraſs, and ten pounds of yellow clover, make a ſufficient doze for an acre. And when cut early, as it ought to be, the crop muſt be very weighty if the cutting coſt more than eighteen pence per acre.

For hay to horned cattle, the mixture ought to be red clover, yellow clover, and ribwort. Red clover, it is true, falls properly to be cut a little later than the other two; but as it is choice food for horned cattle, it is better to ſubmit to a ſmaller quantity, than to loſe the foggage of the other plants by cutting them too late. Ten pounds red clover, as much ribwort, and four pounds yellow clover, are ſufficient for an acre.

A farm-horſe during winter requires at leaſt two lippies of oats daily: in ſpring, which affords more working-hours, they are encreaſed to three. The reſt of his food is hay or ſtraw; bean-ſtraw is the beſt, peaſe-ſtraw next; and after it good oat-ſtraw. Upon that food, a pair of good horſes will labour ten hours a-day, and plough an acre of cultivated land; or draw on a ſmooth road a hundred ſtone in a cart, ſixteen Engliſh miles. Such work they can perform daily without loſing fleſh.

When too much hay or corn is given to a horſe at once, he eats greedily, and is apt to ſurfeit on it. On this account, as well as to ſave food, better ten to give it in ſmall parcels at intervals, in which caſe every particle will be eat up clean. Were it not for the expence, the beſt way of feeding a horſe with hay would be, to give it out of the hand. As for corn, a horſe, when hungry, is apt to ſwallow it without chewing; in which caſe it paſſes entire without affording nouriſhment. Therefore with oats mix chaff or cut ſtraw, which require chewing. If that labour be grudged, there is an inſtrument contrived for bruiſing oats, which has a promiſing appearance. I will not, however, venture to recommend it, becauſe I have not experienced it.

A dairy may be turned to great account. A good cow, during the ſix ſummer-months, will give at a medium twelve Scotch pints of milk daily; the butter of which, with the ſkimmed milk, may amount to eighteen pence per day, and thirteen pounds ten ſhillings in the ſix months. The graſing of ſuch a cow for that time will not coſt above forty ſhillings, which makes eleven pounds ten ſhillings of profit.

## 3. FEEDING FOR THE BUTCHER.

HORNED cattle continue to grow till they are full ſix years old; during which time they do not readily take on fat, nor carry much tallow. The proper time to enter them upon fattening food, is at the age of ſeven. There is an additional reaſon, that three years work can be got from them; which in all events will do more than balance the expence of their food.

As the demand for butcher-meat in Scotland increaſes rapidly, the feeding cattle for the ſhambles has become an intereſting article to the farmer. Thirty years ago, he had no temptation to keep fat on his cattle during winter, becauſe there was nothing but ſalt meat during winter and ſpring. We have now freſh meat in plenty, all the year round; only a little dearer in ſpring; and of that circumſtance a provident farmer will avail himſelf. The difference of a month, will ſometimes add a halfpenny to every pound of beef; which, upon an ox of ſixty ſtone, makes forty ſhillings for that month's feeding.

A field ſown with the graſſes above mentioned, may be depended on for fattening from the middle of April, in a warm ſoil, till the middle of November: nor will they fall off till the middle of December, if froſt and ſnow keep away. Hay, though greatly preferable to ſtraw of any kind, yet will not fatten horned cattle for the market without green food. It indeed keeps the fat upon them; but adds little or none. It is however profitable to feed a fat ox with hay during winter; becauſe the additional price got in the ſpring, will defray the expence of the hay. Some years ago, I fed twelve oxen with hay through winter; and though they were not a pound heavier in April,

pril, I ſold them at that time for double the ſum I paid for them. An ox of a middling ſize, eats thirty pounds of hay, Dutch weight, in twenty-four hours, and drinks forty-eight Scotch pints of water. An ox of a large ſize will eat forty pounds, and will drink in proportion.

Of all the beaſts I know, a ſpayed quey is the moſt profitable both for labour and for the butcher. She is little inferior to an ox in ſtrength; but much more agile, and conſequently better fitted for travel. She will work even till eight years old, and ſtill be fit for feeding fat. People of delicate taſte prefer that ſort of beef.

It is a great loſs to have a cow to maintain that has miſſed calf. The only profit is to feed her for the butcher. She feeds the faſter after having received the bull. But care muſt be taken not to admit the bull, but ſo as that ſhe may be ſold fat three months before the time of calving; for during theſe three months ſhe commonly loſes fat.

Conſiderable profit may be made by feeding ſmall cattle bred in the Highlands, purchaſed when four years old at a ſmall price, becauſe they are unfit for work. This branch of commerce is accordingly well underſtood.

A ſow is a profitable animal: it feeds greedily on cut clover; which, with the offals of the kitchen, dairy, and barn, prepare it finely for being fatted in a ſhort time with more nouriſhing food.

The feeding of calves for veal is alſo profitable. e calf even of a middle-ſized cow, after ſucking for ſix weeks, will ſell at a guinea. The e cow will in ſix months feed four calves for butcher, ſometimes more; and after all, will e milk two months longer. For making fine l, the calf ought to be blooded frequently, ot from light, laid clean and dry, and get chalk lick.

For ſome years paſt, a ſhed erected upon pillars, h intervals of eight or ten feet, has been uſed ſtall-feeding. Such a ſhed I pronounce to be cold for our climate. A houſe ſo conſtructed, to avoid the extremities of heat and cold, an- rs much better. Upon a feed of turnip in

For feeding in perfection, all of them ought to be provided; for which there is more than one reaſon. In the firſt place, variety excites the appetite: next, ſome of theſe vegetables endure the winter better than others: turnip, for example, does not anſwer for ſpring-food, ſo well as cabbage and colewort. Therefore, as far as is conſiſtent with variety, I would be ſparing of the vegetables that are the leaſt hurt by winter. Potatoes anſwer beſt for the concluding food. If ſufficient ſtore be provided, and well preſerved, which is an eaſy matter, all complaints of wanting green food in ſpring muſt be at an end. Every animal is fond of potatoes, not even excepting a horſe. They are a choice food for milk-cows, and produce plenty of milk; which has no rank taſte more than where fed on hay or graſs. And yet after all, how many indolent farmers ſtill remain, who for want of ſpring-food are forced to turn their cattle out to graſs, before it is ready for paſture; which not only ſtarves the cattle, but lays the graſs-roots open to be parched by ſun and wind. One precaution, however, is neceſſary with reſpect to graſs in proper condition for paſture: ſurrender it not to the cattle at once, which would give a looſeneſs, but for a few days let them feed an hour or two only.

Preparatory to the feeding cattle in the houſe with cabbage and turnip, they ought to be made acquainted with that food in the field, by getting now and then ſmall feeds of it; beginning with cabbage, which they ſoon take to as being ſoft; and then proceeding to turnip. Without being thus prepared, ſome beaſts have been known to faſt obſtinately for days, before they would touch them. In the houſe, it is common to fill the ſtalls at once for ſaving trouble. This is wrong: cattle are ſo fond of cabbage and turnip after acquaintance, as to be apt to ſurfeit upon them. A hungry horſe, by eating too much corn at a time, takes a loathing of that food; and his loathing continues for days. Begin with giving a bullock one turnip after another, and he will not readily ſurfeit. One bullock of ninety ſtone Dutch thus fed, ate up thirteen Dutch ſtone before he ſtopped; and in twenty-four hours he devoured thirty ſtone. This was the third part of his own weight; and every bullock in health will do the ſame, when thus fed. Therefore, after cleaning the turnip, let the feeder begin in the morning with throwing a turnip or two to every bullock, one after another: let him repeat the doſe till they turn ſhy: let him then give them cabbage in the ſame manner; and conclude with handfuls of hay. When they are thus ſatisfied, prepare them a ſoft bed as an invitation to lie down. Leave them to chew the cud and ſleep, till they riſe of their own accord. Repeat the doſe as before. As they grow fat, they will reject the coarſer parts of the food; which may be given to winterers,

terers, or to ſwine. If the turnip be large, there is no danger of giving them whole. But they are apt to choke upon ſmall turnip; which therefore muſt be cut into ſmall bits that can be eaſily ſwallowed. A machine to bruiſe turnip for eating would be a uſeful invention.

Theſe inſtructions are calculated to make cattle eat the greateſt quantity poſſible; it being certain, that the more a bullock eats with an appetite, the ſooner he grows fat. It is bad œconomy to ſpare food in this caſe: a certain quantity daily is requiſite to preſerve a beaſt from falling away; and an addition is neceſſary to put fat on him. Therefore the ſooner he is fatted, the greater proportion of what is neceſſary for bare maintenance, is ſaved.

To keep cattle clean, and well littered, is to them half food; and this may be eaſily done in a ſhed conſtructed as deſcribed above. Let them be combed every day, waſhed with water every week, and bled every month; for theſe all contribute to fattening.

Moſt of the cattle in this country ſold to the butcher, are fed upon graſs, and ſold in November at two pence per pound, or two pence halfpenny. But as the profit here is very ſmall, a farmer who is ſtudious of his intereſt, will have a proviſion of cabbage and turnip for winter, in order to ſell his cattle at double price in ſpring.

It has become a pretty general practice, to feed cattle in the field with turnip, cabbage, and other annual greens. There is not another way of fattening cattle ſo cheap; nor another way by which ſo much dung can be raiſed in a farm. Theſe are important objects. But what I chiefly inſiſt on is, that there is not within the invention of man, a more effectual method for improving a gravelly or ſandy ſoil. Nothing indeed is more hurtful to clay or rank loam than poaching; but the poaching a light ſoil takes away the pores, makes the earth more compact, and more retentive of moiſture. A crop of turnip or cabbage on ſtiff land, ought not to be fed in the field; but in a ſhed, ſuch as above deſcribed, or in an adjacent dry field.

To be ſucceſsful in this article, let cattle be choſen that have been accuſtomed to run out in winter. Cattle that have been always houſed in winter, are too tender for field-feeding; they will never turn fat.

There requires more management in feeding cattle with cabbage and turnip, in the field, than is commonly practiſed. What muſt one think of the ſlovenly method of turning cattle into a turnip-field, to feed at random? I hope this is rare; but another method is not rare, which is, to incloſe with flakes a portion of the field, and within that ſmall ſpace to confine the cattle. Is it not obvious, that by dunging, piſſing, trampling, a great part of the turnip muſt be loſt, or become nauſeous? To prevent that loſs, I have always practiſed the following method. Suppoſing the incloſure to be an oblong ſquare, which is the moſt convenient for flakes, begin at one of the ſhort ſides, and from the fence throw the turnip towards the middle of the field, clearing as much ground as can be done at one throw, which may be thirteen or fourteen feet. Separate this vacant ſpace from the turnip by flakes. Let the flakes incline inward to the field, which will prevent the cattle from rubbing them down. Introduce the cattle into this void ſpace, and begin with throwing over to them, from time to time, the turnip that were taken up, ſo ſparingly that they may eat without trampling them under foot. After theſe are clean eat up, clear another ſtrip of the ſame breadth with the former, by throwing over to the cattle the turnip that grow there. Remove the flakes to the ſide of the growing turnip, and go on till the field be eat up. In this manner the whole field will be knead and poached, ſo as totally to alter the texture of the ſoil. But becauſe to give the cattle no other bed, would greatly retard the progreſs of fattening; an adjacent graſs-field is neceſſary, in which they ſhould be put every night for a dry bed. In this graſs-field place hecks, for feeding the cattle with hay or ſtraw; as nothing contributes more to expeditious fatning, than alternate green and dry food.

Froſt is the only enemy to this manner of feeding. In froſt, the digging up the turnip is expenſive; and they give the cattle a looſeneſs, which makes them lean inſtead of fat. Hard froſt deſtroys the turnip altogether. I have tried ſeveral preventives. At the corner of a field, I built in a ſtack all the turnip that grew on four acres. They remained entire ſix weeks; but after that time, they began to ſprout, eſpecially about the centre, which exhauſted the turnip, and rendered them leſs palatable. I tried another method; which was, to fill a large houſe with turnip, on the firſt appearance of froſt. The warmth of the houſe made them ſprout ſooner than in the former way. I made a third experiment; which was, to dig a pit in the field ſix or ſeven feet deep, where I ſtowed the turnip and covered them with three feet of earth, reckoning that this would prevent vegetation. But they ſprouted as ſoon as in the houſe. A fourth experiment was, to build in the field what would fill two large carts, covering the heap with ferns or ſtraw. In this ſituation, they were longer of ſprouting; but they were more expoſed to froſt. Upon the whole, the beſt method, as appears to me, is to ſtore up in a houſe as many turnip as will ſerve the cattle a fortnight. Becauſe after that time they begin to wither, give them to the cattle though the weather be freſh; and then fill the houſe again. This is a reſource againſt a fortnight's froſt; and as a farther reſource, a few heaps may be collected in the field, ready at hand if froſt ſet in. The ſame method may be taken with cabbage. Carrots are preſerved by taking them up, and burying them in ſand. Potatoes being more hurt by froſt than any other root, they ought to be ſtored up in a houſe, and covered with dry ſtraw preſſed down with litter. But here a precaution is neceſſary. If allowed to lie too long in their winter-quarters, they will ſprout, and be uſeleſs. Therefore, as ſoon as the froſt is over in ſpring, they muſt be expoſed to the ſun and air till perfectly dry; and then laid up where there is a free circulation of air.

Cabbage and turnip give a ſtrong taſte to butcher-meat, eſpecially when not intermixed with dry food. But the remedy is eaſy: give nothing but dry food for a few days before they are delivered to the butcher. The intermixing dry food with turnip and cabbage in feeding milk-cows, ought never to be omitted; becauſe theſe plants alone give a nauſeous taſte to the milk, cream, and butter.

The feeding cattle with turnip and cabbage in the field, is an intereſting article. There are few farms but what are fit for raiſing green food of one kind or other; and by far the greater part are fit for every kind. Light ſoil is fit for turnip, both light and loamy ſoil for potatoes, deep ſoil for carrots, and ſtrong ſoil for cabbage. For a dozen of years back, the ordinary profit of ſuch feeding from the end of November to the end of March, has been to double the price of the cattle; which affords a very handſome rent for the land. Nor do I reckon this the capital part: the gain is ſtill greater by the improvement of the ſoil. No other method is ſo effectual to convert a light porous ſoil into what is firm and heavy, than the poaching of cattle during winter. To compare it with a manure that is exhauſted by cropping, would not do it juſtice. It alters and improves the ſoil like clay-marl; and theſe two are the only means I am acquainted with, to produce a new ſoil equal to one originally rich. There are few ſoils indeed but what may be hurt by cropping; but a ſoil ſo improved, can never be hurt ſo much by cropping, as to be reduced to its original poor ſtate. After ſuch a winter-feeding, it would ſurpriſe one, to find ground formerly ſo looſe as not to hold together, become now ſo ſolid as to be raiſed by the plough in ſolid maſſes. This way of feeding cattle, is at the ſame time a good dunging to the field, equal at leaſt to an ordinary dunging from a dunghill. The cattle evacuate abundantly, and what drops from them mixes intimately with the ſoil: not a particle is loſt.

The feeding ſheep on turnip and cabbage ought to be delayed as long as poſſible, for the reaſon given above with reſpect to horned cattle. But as ſheep are better protected againſt cold, there is the leſs neceſſity of providing a ſhed for them. To ſave the turnip, flakes ought to be uſed; and a dry bed is ſtill more neceſſary to them than to horned cattle. Their dry food ought to be white-clover hay, or unthreſhed fitches; both of which they delight in. White-clover hay, however, without corn or green food, will not fatten ſheep for the butcher. In froſt and ſnow, ſheep ſhould always be ſupplied with hay or other dry food; which prepares them for green food the end of March; at which time a few weeks of ryegraſs will make them ready for the market, at the deareſt time of the year.

Where ſheep are fed in the houſe, which is ſeldom done except for the uſe of a family, they ought to be ſeparated by rails from each other; otherwiſe the ſtrongeſt wedder will oppreſs the reſt. They muſt be ſhorn when put up to feed, and be always kept clean. There muſt be a heck for holding hay, a place for the turnip or cabbage, and a rip of oats be hung up within their reach. A ſheep, like an ox, eats of turnip the third of its own weight in twenty-four hours. The beſt age for feeding weathers is four or five: ſhort of that age they feed not ſo kindly, nor tallow ſo well.

Some land is fitted for feeding; ſome for breeding only. A farmer who poſſeſſes rich land, buys lean cattle from the breeder, and fattens them for the butcher.

4. The

## 4. THE WINTERING OF CATTLE NOT INTENDED FOR IMMEDIATE SALE.

THE food proper for ſuch cattle is, firſt, coarſe graſs that they refuſe to eat during ſummer, when they have better food. Second, ſtraw or coarſe hay; and, laſt, what is left by milk-cows, by beaſts ſtall-fed, or by working oxen and horſes. With reſpect to the firſt, the common but very improper method is, to let them go at large in the field; and in froſt and ſnow to give them food in hecks. By this method, the dung is almoſt entirely loſt; and unleſs the field happen to be well ſheltered, which ſeldom is the caſe, Scotland is a climate too cold for ſuch management. This is verified in our highland cattle, which never arrive at half their ſize; not ſo much from want of food, as from piercing cold in a mountainous country. To remedy both theſe evils, an open ſhed ſhould be erected in the field, for ſhelter to the cattle in a ſtorm; and this ſhed ſhould be in the moſt ſheltered ſpot, fronting the ſouth. To preſerve the food given them during froſt and ſnow, a heck ſhould be put up in the ſhed; and the dung be carefully collected from time to time. It is evident from what is ſaid, that no cattle are fit to be managed in this manner, but what have been accuſtomed to lie out all winter.

Where there is no coarſe graſs for winter-feeding,

ing, the ordinary method to feed winterers is in a dung-yard with ſtraw, the half of which, trodden down with the foot, turns to no account. The more provident farmers ſet up a heck in the yard, which ſaves ſome of the ſtraw that is loſt the other way.

This method, though common, lies open to many objections: firſt, it is ſtill too cold for winter; next, much good food is deſtroyed by it; and, third, the dung, by trampling of the cattle, is kept from rotting. This matter is intereſting, and I beg the reader's attention, while I endeavour to verify theſe propoſitions. With reſpect to the firſt, the ſhelter of a yard is far from being ſufficient to preſerve cattle in a kindly heat, during froſty weather. Such an incloſure is ſubject to whirling winds, which pinch the cattle even in freſh weather. Obſerve, that when cattle are brought from a warmer climate to mend the breed, every one is ſenſible, that during winter a warm houſe, and plenty of food, ſhould be provided for them. A cow when thus treated gives more milk, and a beaſt intended for the butcher goes ſooner to fat. To anſwer theſe purpoſes, I believe it will be found, that the nearer the air approaches to the heat of the blood, the cattle will thrive the better. That cattle fed in a yard deſtroy much ſtraw, is obvious to ocular inſpection. Even when ſtraw is put into a heck, one beaſt no ſooner draws out a mouthful, than he is puſhed away by another, and loſes in his hurry part of what he draws from the heck: none of them are ſuffered to feed peaceably or quietly. The third propoſition is the moſt important of all. Half-rotten dung trodden under foot, and kneaded together by the cattle, excludes the air totally from the inner parts of the heap; and it is a truth indiſputable, that there never can be any putrefaction where there is no air. Putrefaction cannot go on without moiſture, and as little without air. Put a ſpoonful of cream in an exhauſted receiver; and after a year it will come out as ſweet as when put in. When a dunghill, after heating, turns cool again, turn it over and admit freſh air, it heats a ſecond time: a ſtake driven into an open gravelly ſoil, which admits air into every pore, rots ſooner than even in a wet clay-ſoil that excludes air.

From theſe premiſſes I conclude with firmneſs, that the beſt way of feeding winterers is in a houſe where there is free ventilation; indulging them only an hour or two in the field when let out to water, more or leſs according to the weather. I know many judicious farmers, who prefer the feeding on a dunghill, with an open ſhed to retire to in a ſtorm; and they even hold, that the treading of cattle on a dunghill contributes to its putrefaction. I flatter myſelf that I have diſcovered the reaſon of this opinion. The practice is, to throw quantities of dry ſtraw from time to time on the dunghill, part of which is eaten by the cattle, and the reſt trodden under foot. Straw is elaſtic, and when laid on a dunghill dry, it admits too much air; in which caſe the dunghill gains by being trodden on. But where all the ſtraw is uſed, either in food or in litter, and none of it carried to the dunghill till it be half putrefied; it claps cloſe enough of itſelf; it becomes too compact by being trodden upon; and the air is excluded altogether, which obſtructs putrefaction no leſs than too much air. A provident farmer will never waſte his ſtraw, by throwing it on a dunghill: he will provide as many winterers, as to conſume all the ſtraw that is to ſpare from his working cattle. I add, that ſuppoſing winterers to be as comfortably put up in a farm-yard as in a houſe, the latter however ought to be preferred; firſt, becauſe it ſaves ſtraw, and the beaſts are more regularly fed; next, that it is a better way of having a dunghill well putrefied; and, laſtly, that the piſs of the cattle can be wholly preſerved; whereas in a farm-yard all is loſt but what happens to fall on the dunghill.

### 5. RULES FOR BUYING AND SELLING CATTLE AND CORN.

THE common and conſtant way is, to ſell cattle by the eye; which is far from being equal between the farmer and the butcher. The former has but a very uncertain gueſs of the weight; the latter, who is dealing the year round, can gueſs very near. Fair commerce is in general the moſt beneficial; and every thing that approaches to chance or gaming is hurtful. To bring on a perfect equality between the ſeller and buyer, I propoſe, that every beaſt ſhould be ſold by weight, and that the weight ſhould be aſcertained by a balance. The moſt convenient one I know is a ſteel-yard, being the fitteſt for weighing heavy goods; and a ſteel-yard I have uſed with eaſe and ſucceſs many years.

But it is not ſufficient to have the weight of a living beaſt aſcertained. Different parts are very different in their value; and there is a rule for aſcertaining the proportion of theſe different parts, by which their weight may be known, almoſt with equal certainty as the weight of the whole beaſt. My experience goes no farther than to Scotch cattle ſold fat, to which the following proportions will nearly anſwer. The four quarters make the half of the weight of the bullock. The ſkin is the eighteenth part. The tallow the twelfth part. Theſe make twenty-three thirty-ſixths of the whole; and the head, feet, tripe, blood, &c. make the remainder, being a third part and a little more. Theſe offals never ſell by weight, but at a certain proportion of the weight of the beaſt. They commonly draw ten ſhillings and ſixpence when the bullock weighs a hundred ſtone Dutch; and ſo in proportion.

These particulars adjuſted, the next thing the ſeller is to inform himſelf of, is the price of butcher-meat in the market, of tallow, and of hides. Suppoſing the bullock I have to ſell is ſeventy-two ſtone living weight, the four quarters make thirty-ſix ſtone, which at 4 s. per ſtone, or 3 d. per pound, amount to L. 7, 4 s. The hide is worth 16 s. at 4 s. per ſtone; and the tallow, being 5 s. 4 d. the ſtone, is worth L. 1, 12 s. Sterling. The offals, according to the proportion above mentioned, will give 7 s. 6 d.; and by that computation the value of the bullock is L. 9, 19 s. 6 d. This anſwers to 2 s. 9$\frac{9}{12}$ d. per ſtone, living weight. And therefore, if the butcher agree to give me that ſum per ſtone, no more is neceſſary to aſcertain the price of the whole cargo, than to weigh the beaſts by threes or fours as the ſcale can hold them. Out of this ſum however muſt be deducted the butcher's profit, which cannot be much leſs than 5 per cent.

The weighing cattle alive anſwers another important purpoſe; which is, to diſcover whether the feeder gets the value of the food by the additional weight of the beaſt. For example, the food of a bullock coſts 9 d. per day, or 5 s. 3 d. per week. If the bullock do not take on two ſtone per week, the keeper is a loſer; and there

is

io excuſe for keeping the beaſt on hand, un-
perhaps in expectation of a riſing market.

There is another advantage of regulating the
ce of cattle by living weight. Where a but-
r buys by the lump, and bargains that he is to
e away the beaſt at a day certain, the vender
empted to be ſparing of food. But ſuppoſing
beaſt to be ſold by living weight, it is the in-
eſt of the ſeller to make it as fat as poſſible.

The ſame rule in ſelling is applicable to ſheep.
e four quarters make half of the living weight,
ſkin the eleventh part, the tallow the tenth
t, the offals ſomewhat leſs than the third
t. But computing the prices that theſe parti-
ars ſell for in the market, the amount will not
the value of the ſheep, becauſe the wool alſo

of wedders to ſell at the end of December, each of which weighs ſix ſtone fourteen pounds Dutch weight, I want to know what they are worth per head.

| | | | | |
|---|---|---|---|---|
| 1. The four quarters weighing 55 pounds, is, at 3 d. per pound, | L. | 0 | 13 | 9 |
| 2. The value of the wool as above 11$\frac{2}{11}$d. to which muſt be added 10 d. as the value of the ſkin, *inde*, | | 0 | 1 | 9$\frac{2}{11}$ |
| 3. The tallow being the tenth part of the weight, makes 11 pounds, which, at 4 d. per pound, is | | 0 | 3 | 8 |
| 4. The offals are not ſold by weight, but are commonly valued at - | | 0 | 1 | 0 |
| The ſum, | L. | 1 | 0 | 2$\frac{2}{11}$ |

This price anſwers to 2 s. 11$\frac{6}{11}$ d. Sterling per

ſtone

---

therwiſe. Some miles round Cheviot hills, none but ſheep of a year old are ſmeared: elder ſheep are reckoned ſufficiently ſtrong to endure the cold without it. But there black ſheep of all ages are ſmeared, becauſe black wool is not diſcoloured by ſmearing. In the north of Scotland ſmearing is not known.

Wool ſhorn immediately after a ſheep is waſhed, never turns white. A kind of oil, termed *gleet*, perſpires from the animal, and contributes to whiten the wool in ſcouring. Therefore, where waſhing is neceſſary, delay ſhearing for a fortnight, that the wool may again be covered with gleet.

ſtone living weight. And if the butcher agree to give that price, the value of any particular beaſt may be determined by weighing him as above.

From this muſt be deducted the butcher's profit at 5 per cent. or under, as can be agreed.

*N. B.* An animal weighs more or leſs as his belly is more or leſs full. The above proportions were made out when the ſheep and horned cattle were weighed at eleven o'clock forenoon.

Having diſcuſſed cattle, I proceed to corn. The variety of meaſures in ſelling and buying corn, has been time out of mind a juſt cauſe of complaint in Scotland, as well as other countries; and it is indeed an inlet to many frauds. And yet, were all the meaſures uſed in Scotland reduced to the Linlithgow ſtandard, there would however remain a great inconvenience in ſelling grain by meaſure; for of all commodities, it is the leaſt proper to be ſold in that manner. The quality of grain differs widely in different ſoils, and even in the ſame ſoil by good or bad culture. One boll of barley weighs twenty-one Dutch ſtone, another only fifteen. One boll of oats weighs fifteen ſtone, another, only eleven. The ſame difference is obſervable in other grain.

There is another objection againſt ſelling by meaſure. The ſlovenly farmer is ſatisfied with bulk, without any regard to the quality of his grain:

grain; whereas, were it the rule to ſell by weight, it would make the farmer doubly attentive to the dreſſing of his land, in order to produce the weightieſt grain.

Beſide weight, another circumſtance enters into conſideration for aſcertaining the value of grain; which is, the proportion of the huſk to the kernel.

Middling wheat weighs per boll fourteen Dutch ſtone; of which the huſk makes the ſeventh part, or two Dutch ſtone *.

Middling barley weighs per boll eighteen Dutch ſtone; of which the huſk weighs one ſtone four pounds.

Middling oats weigh per boll fourteen Dutch ſtone, of which the huſk weighs ſix ſtone.

Middling beans weigh per boll fifteen ſtone eight pounds Dutch weight, of which the huſk weighs but eight pounds,

And the ſame proportion holds as to peaſe.

---

* *N. B.* Four firlots of barley is nearly equal to ſix firlots of wheat, both Linlithgow meaſure. The meaſure of oats, beans, and peaſe, is the ſame with that of barley.

## CHAP. X.

## CULTURE OF OTHER PLANTS PROPER FOR A FARM.

THERE are many uſeful plants propagated by curious farmers that do not anſwer for food. I confine myſelf to three, the moſt common, and at the ſame time the moſt uſeful; foreſt-trees, flax, hops. I begin with foreſt-trees, as the moſt complex.

### SECT. I.

### FOREST-TREES.

CONSIDERING the great quantity of waſte land in Scotland, fit only for bearing trees, and the eaſineſs of tranſporting them by navigable arms of the ſea, one cannot but regret the indolence of our forefathers, who neglected that profitable branch of commerce, and left us to the neceſſity of purchaſing foreign timber for every uſe in life. The Commiſſioners of the annexed eſtates, deeply ſenſible of this neglect, have beſtowed liberally to raiſe plantations every where in the King's eſtates. Their laudable example has animated many land-proprietors, to benefit themſelves and their country by the ſame means. The ſpirit of planting is rouſed; and there ſeems little doubt of its ſpreading wider and wider, till this country be provided with timber for its own conſumpt at leaſt, if not for exportation. As an author, I am fond to do all in my power to keep up that ſpirit: and in that view, the preſent chapter on the culture of foreſt-trees, will, I hope, be well received. A regular treatiſe upon the ſubject would require a volume: but as I muſt contract what I have to ſay within the nutſhell of a chapter, I ſhall ſtudy brevity, and mention nothing but what appears material.

Trees are propagated by ſeed, by cuttings, by layers, and by ſuckers.

### 1. Raiſing Trees by Seed.

The propagating trees by ſeed is nature's method. One inconvenience it has, that the trees thus raiſed are not always the ſame with the parent plant: though they are of the ſame ſpecies, they copy not always its varieties.

What follows will enable us to judge of the maturity of ſeed. Seed incloſed in a *capſula*, in a pod, or in a cone, is ripe when the covering opens by the heat of the ſun. The ſeed of a fruit-tree is ripe when it no longer adheres to the fruit; and where unripe fruit is pulled, the ſeed ripens with it. In general, ſeed is ripe when it ſinks in water to the bottom.

The ſeed of the Scotch elm ripens before the middle of June. The beſt way of gathering it is, to ſhake the tree gently: the ripeſt ſeed falls firſt, which may be gathered in a ſheet laid at the root of the tree.

The ſeed of the aſh and of the maple may be put into the ground without being taken out of its *capſula*.

The beſt way of opening the cones of pine, fir, &c. is to expoſe them in boxes to ſun and dew. The drying them in a kiln is apt to deſtroy the germ. The cones of the larix are at their full ſize in autumn; but the ſeed is not ſo early ripe. Delay gathering them till March or April, when they begin to drop from the tree. Cut off a part of the cone next the ſtalk, which will render it eaſy to ſeparate the quarters: the ripeſt ſeed falls out upon ſhaking the cone with the hand.

The ſeed of the birch, the willow, the poplar, the aller, being very ſmall, is not eaſily gathered: ſtir the ground about theſe trees, and it will ſoon be filled with young plants. With reſpect to the ſeed of the birch and aſh, it is ſingular, that when dropt from the tree, no ſeed takes root ſo readily; yet when gathered, and ſcattered with the hand, it ſeldom grows.

As for a choice of ſeed, ſmall acorns gathered from large and lofty trees, are preferable before the largeſt acorns of ſmaller trees. In general, the ſeed is always the beſt that is procured from the moſt vigorous trees. But as in extenſive plantations much preciſion cannot be expected, it ought to be the chief care that the ſeed be perfectly ſound.

Next, as to preparing ſeed for ſowing. Trees propagated from ſeed have all of them a tap-root, which puſhes perpendicularly downward. The purpoſe of nature in this root is, to fit trees for growing in the ſtiffeſt ſoil, and to ſecure them againſt wind; but it proves hurtful to trees intended for tranſplantation. A young oak five or ſix years old, when taken up for tranſplanting, has, like a turnip, but this ſingle root, which will be four or five feet long when the ſtem is within one foot. Planted in this manner, it ſeldom lives. This evil is prevented by making the ſeed germinate in moiſt earth, and ſowing it in the ſeed-bed after the radicle is cut off. The radicle never puſhes more; and inſtead of it the tree puſhes out many roots, which ſpread horizontally. Walnuts, almonds, and other ſhell-fruit, being long of germinating, ought to be put in moiſt ſand, in order that the radicle may puſh before the end of April, to be cut off as aforeſaid. Acorns, Cheſnuts, and beech-maſt, will germinate timeouſly in dry ſand. In wet ſand or moiſt earth, they would, before the time of ſowing, not only germinate, but puſh out long roots, which would ruin all. As this method is too troubleſome for ſmall ſeeds, ſow them in beds as gathered: pull them up the ſecond year: cut off the tap-root: and plant them again at the diſtance from each other of three or four inches. Two years after, they may again be tranſplanted wider; there to remain till they be fit for the field. Some imagine, that to deprive a tree of the tap-root prevents its growth. But experience vouches the contrary; and ſo does reaſon. It is obſervable, that the roots next the ſurface, being acceſſible to ſun and moiſture, are always the moſt vigorous, and are farther ſpread than thoſe below. A tap-root is deprived of ſun and air, and even of water, unleſs where it happens to glide below the ſurface: how then can it equal a horizontal root in nouriſhing the tree.

The ſeeds of the white thorn ſown without preparation, riſe not till the ſecond year. If buried under ground in a heap till the pulp be rotted off, and ſown in the ſpring following, they will germinate that very year. Inſtead of burying them under ground, a more approved method is, to lay them in a heap at the end of a barn, mixed with earth. By that method, a greater number will germinate than in the ordinary way. I made an experiment. One bed was ſown with haws prepared in the ordinary way; and one with haws prepared in the other way. Upon the latter bed ſprung a double quantity of thorns, and more vigorous. I made another experiment upon elm-ſeed. Of a quantity gathered when ripe, the half was immediately ly ſown; the other half was carefully dried in the ſhade, and ſown a fortnight after. The latter produced a greater number of plants, and more vigorous. Thorns are propagated ſtill more expeditiouſly by cuttings from the root. When thorns are taken from the nurſery to be planted in a hedge, the roots that are either wounded by the ſpade, or too long, muſt be cut off. Let theſe be ſhred into ſmall parts, and ſown in a bed prepared for them: they will produce thorns that very year. The ſeed of the aſh ſeldom germinates till the ſecond year. When gathered in the month of October, let it be put in pots with earth, and ſown in the ſpring: it will germinate immediately. The ordinary way of raiſing hollies, is to ſow the berries entire; which is wrong: every berry contains four ſeeds; and the plants that ſpring from them are ſo interwoven, as not to be ſeparable without injury. A better way is, to gather the berries in December, the later the better if they can be ſaved from birds. Throw them into a tub with water, and between the hands rub them carefully in the water till all the pulp fall off. The good ſeed will ſink to the bottom, which, after the water is poured off, muſt be laid upon a cloth to dry. Mix them with dry ſand, which will preſerve them all winter. Sow them in March or April, and cover them with earth about three quarters of an inch thick.

With reſpect to the time of ſowing, the beſt rule is, to imitate nature, by ſowing when the ſeed is ripe; provided the tree be of a hardy kind to endure the froſt of winter. By this rule, the ſeed of Scotch elm ought to be ſown in June; the ſeed of pine and fir in April, at which time their cones open. Acorns, cheſnuts, and beech-maſt, ripen in autumn, which is the time of ſowing them. If they ripen later, it is more ſafe to ſow them in the ſpring following; becauſe the young plants cannot reſiſt froſt, if before winter they have not acquired ſome degree of vigour. There is another reaſon for ſtoring up theſe ſeeds till ſpring; which is, that the longer they lie in the ground, the greater riſk they run of being deſtroyed by vermin. As the white thorn vegetates early, the haws ought to be ſown the firſt dry weather in February, after being ſeparated by a wire-ſieve from the mould with which they were mixed. Avoid freſh dung, which is injurious to them. Sow the ſeed of the larix when taken out of the cone in March or April; for though in the cone it will ſtand good for years, yet it does not long retain its vegetative quality when ſeparated from the cone.

Next as to the manner of ſowing ſeed. Nature drops ſeed upon the ſurface of the ground. We muſt depart from nature in this inſtance, upon the following account, that after much expence and trouble in procuring ſeed, the far greater part would periſh, partly by vermin, and partly by an inclement air. This is not regarded by nature, which is profuſe in the production of ſeeds. All ſeeds therefore ought to be covered with earth, birch-ſeed alone excepted, which ought to be preſſed down with the back of the ſpade, but left open to the air without covering. Small ſeeds muſt be ſlightly covered, as having leſs vigour to puſh upward. In ſtrong ſoil, the covering ought in every caſe to be ſlight. The depth is pretty much arbitrary, becauſe the ſame ſeed will thrive at different depths. But it muſt be attended to, that a ſlight covering expoſes the ſeed to drought; and therefore the ground ought to be watered if the ſeaſon be dry. Where the ground ſown is too extenſive for watering, a crop of barley will preſerve the tree-ſeed from the ſun, and alſo prevent weeds. The tree-ſeed and the barley may be ſown alternately in lines. If trees are intended to remain where their ſeed is ſown, it is proper to ſow thick, partly for ſhelter, partly to keep down weeds. M. Buffon declares againſt weeding the ground upon which the ſeed is ſown: "For," ſays he, "weeds ſhelter the young plants from "the ſun, keep in the dew, and preſerve the "plants warm in winter." In Scotland nothing is more hurtful to plants than weeds, which choke them, and exclude the air. A better way, even in France, is to ſow barley with the ſeed, which will protect the young plants from the ſun, and admit the air.

The beſt way of preſerving ſeed is in dry ſand, which ſucks in the moiſture from the ſeed, and prevents muſtineſs. It withal retains ſo much moiſture as to prevent the ſeed from withering. This method is chiefly uſeful in preſerving during winter ſeeds that require ſpring-ſowing, and in the conveyance of ſeeds to a diſtance. The efficacy of dry ſand appears in preſerving oranges and citrons, which in the air dry and wither: if to prevent withering they be laid in a moiſt place, they never fail to turn muſty. There is one exception, that ſeed which lies long in the ground before it germinates, ought to be preſerved in moiſt earth. The ſeed of the ſenſitive plant will keep entire for twenty years; of a melon for nine or ten. There are many ſeeds that will not keep entire longer than two or three years; which is the caſe of flax-ſeed, though remarkably oily: ſome ſeeds require to be put in the ground as ſoon as ripe.

To prevent young plants in the ſeed-bed from being ſpewed out by froſt, cover the beds with leaves of trees, to be removed when the ſevere froſts are over.

We proceed from the ſeed-bed to the nurſery. Plants form very different roots, according to the ſoil they grow in. In ſtiff ſoil, the roots are commonly few, but ſtrong and vigorous, for overcoming the reſiſtance of ſuch a ſoil. Roots multiply in proportion to the richneſs and mellowneſs of a ſoil. An oak, for example, has a ſtrong tap-root, which fits it, more than any other tree, for growing in a ſtiff ſoil. This root diminiſhes in ſtrength and ſize in a loam, and ſtill more in a ſandy ſoil. When it grows in water, it has a multitude of roots, but not the leaſt appearance of a tap-root. Hence it follows, that the ſoil of a nurſery ought always to be light and free: ſuch a ſoil produces a multitude of roots; and the vigour of growth is always in proportion to the number of roots, the ſmaller the better. But it alſo follows, that in tranſplanting trees from ſuch a nurſery, the ſoil about them ought to be made as mellow and free as poſſible, in order to encourage the ſmall roots. When theſe are enlarged in ſo fine a ſoil, they will be able to overcome the ſtiffneſs of the natural ſoil of the field. Avoid dung in a nurſery. If any be admitted, it ought to be thoroughly putrefied, and digeſted into a ſort of rich mould. Green dung makes the roots ill conditioned, and encourages a large white worm, which lives on the bark of the roots. Neither the walnut nor horſe-cheſnut ſucceed in a nurſery: the plants require to be placed at a diſtance from each other; and the earth about them muſt be ſtirred ſeveral years. Aquatics that are intended to be propagated by large cuttings, ought firſt to have the benefit of a nurſery; becauſe they thrive beſt when planted out with roots. Avoid a mixture of different trees in the ſame bed, for the ſlow growers will be oppreſſed.

The true ſeaſon for tranſplanting from the ſeed-bed to the nurſery is about the fall of the leaf. Catch the time when the earth is ſo moiſt as to ſuffer the plants to be drawn without tearing the roots. All evergreens ought to be tranſplanted in ſpring; and alſo all other trees that ſuffer by froſt.

Where trees are ſo young as that an interval of five or ſix inches along the rows is ſufficient, there muſt be an interval of a foot at leaſt between the rows, in order to give acceſs to clean the ground of weeds; and this interval is ſufficient, even when the plants are ſo large as to make an interval of a foot along the rows neceſſary. Where the diſtance along the rows is made eighteen inches, or two feet, the intervals between the rows ought to be no leſs, for the ſake of the trees, though unneceſſary for the ſake of weeding. Yet ſuch is the influence of cuſtom, contrary to common ſenſe, that from the original poſition of young plants in a nurſery, the interval between rows is always made double of the interval along the rows. Thus if the latter be eighteen inches, the former is always made three feet; and four feet where the ſize of the trees requires an interval of two feet along the rows. The ſame influence of cuſtom occaſions trees to be planted in rows in the field, where they are to ſtand; and yet they make a much better figure when, in imitation of nature, they are ſcattered as at random.

## 2. CUTTINGS, LAYERS, SUCKERS.

SEED is not the only means that nature has provided for propagating trees. They can be propagated by cuttings, by layers, and by ſuckers. They have one advantage, that whereas ſeed propagates the kind only, theſe carry on any variety that is in the tree from whence they are taken. Grafting has the ſame effect.

The willow, the oſier, the vine, the elder, the poplar both black and white, the platanus, the yew, the box, may all be propagated by cuttings. The black poplar is ſingular: a branch will not anſwer for a cutting, unleſs the top be left entire. A cutting of willow eight or ten feet long, and ſeven or eight inches thick, planted in the following manner, will ſoon become a tree. Let the great end be immerſed in water a foot deep as ſoon as cut, which ought to be the end of March; and remain in that ſtate till planted, which ought to be the beginning of May. Immediately before planting, cut the great end ſloping to a point; and on the ſide that is not cut, keep the bark entire down to the point. Make a hole in the earth a foot and a half deep, ſufficiently large to admit the cutting without ruffling the bark, which would prove deſtructive. Any vacuity left in the hole muſt be filled up with freſh earth, and preſſed down cloſe to the cutting. A ſafer way, and little leſs expeditious, is to make the hole with the ſpade, to return the earth to the hole round the cutting, and to preſs down all firm and cloſe. After ſtanding a year, throw ſome freſh earth upon the roots. It is ſtill better, to make a ditch two feet from the row of the trees thus planted, and to lay upon the roots the earth of the ditch. Several trees that can be propagated by cuttings, require more precaution than the willow or poplar. The branches intended for cuttings muſt be young; and a part of the greater branch from whence they are taken muſt be cut with them, to ſerve as a ſort of root. With all theſe precautions, it muſt not be expected, that every cutting from the platanus, the white poplar, the poplars of Virginia and of Lombardy, the aſpin, the maple with aſh leaves, will take root. Cuttings from the yew, the alaternus, the box, require the utmoſt care. They ought to be planted in beds ſheltered from the ſun, and watered in dry weather.

All trees do by layers; and the method is eaſy in ſhrubs which have branches near the ground: but to propagate by layers from large trees, that have no branches near the ground, ſuch as the lime, the mulberry, the aller, more art is neceſſary. One method is, to cut the tree by the ground before the ſap begins to riſe; which will produce many ſhoots the firſt year. The next ground at the ſame time, heap earth upon the root till it riſe a foot upon the ſhoots. After two or three years, remove the earth, and cut off the ſtems, which will be full of roots as far as they were covered with earth. Theſe will make good plants. Spare the ſmaller ſtems, and cover them with earth as before: they will in time produce new plants. Another method is, to chuſe a young tree eight or nine inches in circumference; and cut it over two feet from the ground. In every part, the ſtump puſhes many ſhoots. The ſecond or third year, take all out of the ground: lay the ſtump with its roots and ſhoots in a trench; and cover them with earth, ſo as to leave nothing open to the air but the extremities of the ſhoots. Theſe will thruſt out roots under the ſurface, which will afford young plants in abundance. When a pine or a fir is cut down, the root dies without producing any ſhoot. Nor can theſe trees be propagated either by cuttings or by layers; if a ſpruce fir be excepted, which it is ſaid can be propagated by cuttings.

To have ſtraight trees, cuttings and layers ought to be of perpendicular branches, eſpecially where the wood is hard. How long layers ſhould continue in the ground to have good roots, depends much upon the ſeaſon, and ſtill more on the nature of the tree. A bramble will take root on the ſurface of the ground, without the leaſt covering of earth. Layers of lime and of platanus have commonly good roots in three years, and ſometimes in two. Many trees require longer time.

To propagate by ſuckers, part of the root of the parent plant muſt be cut along with the ſucker. It muſt be immediately planted in a nurſery, in order to acquire roots. When planted out to ſtand, the old root ſhould be cut away all but what is cloſe to the ſucker; for it is apt to ſwell under ground, and to obſtruct the growth of the plant. To have a quantity of ſuckers, which riſe not plentifully from old trees, cut the old tree over, and the ground will be filled with them. Some writers ſay, that trees propagated by layers take on a better ſhape, and grow faſter, than thoſe propagated by ſuckers.

### 3. SOIL PROPER FOR TREES.

THE ſoil proper for trees comes next in order. Fat ſand, that is, clay mixed with a large proportion of ſand, agrees with almoſt every ſort of tree, eſpecially if the ſoil be deep. Evergreens do well in ſuch a ſoil. And even aquatics, ſuch as aſh, poplar, willow, aller, thrive in it, though more ſlowly than in moiſt ground: theſe aquatics make a ſhift even in ground too dry for the oak, the beech, the cheſnut. A pine grows well in ſand. The juniper will grow in a very thin ſoil where ſcarce any other tree will thrive. An aſpin does well in a pure clay: a cheſnut does not. Dry earth of a good quality, though but eighteen inches above a tough till, will bear the elm, the maple, the hornbeam, the walnut, the aſh, the birch, the mulberry, the white poplar, and almoſt every kind of ſhrub. If but ten or twelve inches deep, it is only fit for ſhrubs; excepting the birch, which will grow if the till be covered with but five or ſix inches of black and light earth. The lime and the horſe-cheſnut love a tender and deep ſoil. Marſhy ſoil is proper for the willow, the aſh, the aller, the occidental platanus, and for moſt ſorts of the poplar. An elder, though it makes a ſhift in the drieſt ſoil, yet loves moiſture; and therefore is proper for a fence on the ſides of ditches, for cattle do not touch it. Ground elevated two or three feet above a running water, being moiſt without being marſhy, is fit for trees of every ſort, particularly for the occidental and oriental platanus, the tulip-tree, and the lime. Young trees ſhould be planted differently, according to the nature of the ſoil: in a ſoil retentive of moiſture, the tree ſhould be bulked above the ſurface; in a very dry ſoil, the earth round the tree ſhould ſlope down to the root, in order to collect the rain. In general, though corn proſpers in clay, ſandy or gravelly ſoil is fitteſt for trees. The culture of corn, renewed annually, renders clay open and free; but when left untilled, it turns too hard even for the roots of trees.

4. CLI-

## 4. CLIMATE.

WITH reſpect to climate, an oak is an inhabitant of the temperate zone: none are found between the tropics, and none farther north than Stockholm. Fir and birch bear much cold, the latter eſpecially. Plants, like animals, after ſeveral generations, come to thrive in a climate very different from their own. It requires peculiar ſkill and attention to habituate to a new climate ſuch as grow on the top of the Alps, and on the top of high mountains farther north. Their nature fits them for a very cold ſummer; and for a temperate winter, being always covered with ſnow during that ſeaſon. In a low country the want of ſnow can be tolerably well ſupplied by ſome ſmall degree of artificial heat; but in our ſummers it is not eaſy to give them the cold of their native place.

The advantages and diſadvantages of different expoſures come under the preſent article. In ſpring, even a ſtrong froſt hurts not plants, provided the ice be melted before they are expoſed to the ſun: but even a moderate froſt commits great waſte, if the ice continue till it be melted by the ſun; for the ice acts as a burning-glaſs. By that means, delicate plants, expoſed to the riſing ſun, are often deſtroyed in ſpring; while ſuch plants, expoſed to the north, are ſafe: which is

the

the fate even of young ſhoots of the oak. An eaſtern expoſition has, on the other hand, its advantages. Plants are ſooner relieved from the morning cold by the heat of the ſun: they are protected from the ſun's meridian heat: and as the eaſt wind is generally dry, ſpring-froſt makes leſs impreſſion than where there is more moiſture.

In a ſouthern expoſition, plants, being covered from the north, are the leſs ſubject to froſt. As the ſun reaches them not till about ten in the morning, the ſpring ice is commonly melted before that time; and if the climate be rainy to temper the meridian heat, trees in that expoſure grow faſt. The diſadvantage is, at firſt, that young plants are apt to be ſcorched by the ſun, eſpecially in a light ſoil and dry ſummer; and next, that ice being frequently melted in that expoſure, even by winter-heat; if the moiſture be not ſucked up by heat or diſſipated by wind, it is congealed in the evening, and does much hurt.

A weſtern expoſition is free from the burning ſun in a dry ſeaſon; but is expoſed to ſpring ſnow and hail, which come moſtly from the weſt. We often feel a weſt expoſition inſupportably cold, when the air is tolerably ſoft in other expoſitions. Hardy trees can bear this cold; but tender trees are often deſtroyed by it.

In a northern expoſition, ſnow never melts; and the wind from that quarter is the coldeſt and drieſt of all. By that means however perſpiration is ſo faint, that little moiſture is required. Here deciduous foreſt-trees grow ſlowly; but the pine, the fir, the yew, the evergreen oak, the box, and other evergreens, thrive well. This fact appears ſingular: evergreens perſpire little; and one would think that they ſhould, more than other trees, need the action of the ſun to keep their ſap in motion. The birch alſo thrives well in a northern aſpect. In a dry and light ſoil, trees thrive better expoſed to the north, than to the ſouth; in the former, the dew continues on the trees, till nine or ten in the morning; and the ſun ſtrikes not ſo violently as to wither the ground, or to occaſion great perſpiration. But a ſouthern aſpect merits the preference in a clay ſoil, and in a cold climate.

## 5. TIME OF PLANTING TREES IN THE FIELD.

WITH reſpect to the time of planting trees where they are to ſtand, it runs from autumn, when they drop the leaf, till ſpring, when the buds begin to ſwell, provided it be freſh weather, and the ground be tolerably dry. But becauſe in the dead of winter froſt prevails, or too much moiſture, two ſeaſons chiefly are recommended, viz. autumn before ſtrong froſt ſets in, and ſpring after it is paſt. In this ſeaſon, planting may be continued till the buds begin to open; which in ſome trees is early, in others late. The opening the buds depends alſo on the ſeaſon, late or early. Whether autumn or ſpring be the beſt for planting, is not agreed. As the weather is commonly moiſt in autumn, trees brought from a diſtance ſuffer leſs in that ſeaſon by being long kept out of the ground; and if the winter happen to be mild, new roots are produced, which are a fine preparation for a more vigorous vegetation in ſpring. Millar holds October to be the beſt ſeaſon for planting trees that loſe the leaf in winter, provided the ſoil be dry. In a moiſt ſoil, it is better, ſays he, to defer planting till the latter end of February or beginning of March. But though this may hold in general, there are ſeveral exceptions. Tender plants that are hurt by froſt, ought to be delayed till ſpring. Trees that retain the leaf during winter, ought to be tranſplanted in ſpring; for, having a ſlow circulation of ſap, they perſpire little, and run leſs riſk of being hurt by drought. Another reaſon concurs with reſpect to the oak, the beech, and the hornbeam, which hold the leaf all winter; which is, that they are late in puſhing: when planted in February or March, they have time to prepare new roots before the buds begin to ſwell *. April is undoubtedly the beſt

---

* It is maintained by ſome writers, that the beſt ſeaſon for planting oak and larche, is immediately before the buds begin to puſh. I have not diſcovered any good reaſon for making theſe trees an exception from the general rule.

ſeaſon

ſon for evergreens; though they may be ſafe-
removed at Midſummer, if near the place where
y are to ſtand. During winter, evergreens
in a ſtate approaching to reſt. If removed at
t ſeaſon, they do not take root till the ſpring
s the ſap in motion; and in a hard winter they
mmonly die. Light land ſhould infallibly be
nted in autumn; for ſpring-planting in ſuch
d is ſubject to great diſtreſs from the ſummer-
1.

## 6. MANNER OF PLANTING.

As to the manner of planting trees in a field,
ſafeſt way to draw trees out of a nurſery for
nting, is to remove the earth from the firſt

too thick, provided attention be given to thin them timeouſly. Thick planting ſhelters them from wind and from cold. When they riſe to ſeven or eight feet hight, ſo as to wave with the wind, they ought to be weeded, to prevent their rubbing upon one another, which is apt to create a ſort of gangrene. But let them be weeded cautiouſly: fix on the weakeſt tree, the branches of which may be ſhortened, for giving room to the trees that are to ſtand; and let the tree be cut down a year or two after. This is a better method than to cut down the tree at firſt; for young trees that have too much room, are apt to branch out inſtead of puſhing up. This method does finely in a plantation of firs and pines. When the trees riſe to eighteen or twenty feet, and by good roots are proof againſt wind, they ought to be much thinned, ſo as not to leave one nearer another than its own length. Where trees of that height ſtand cloſe together, they occaſion a ſtagnation of air: the air they ſuck in is unwholeſome, and makes them languiſh. Young trees five or ſix feet high only, occaſion very little ſtagnation of air: the free air above mixing with that below, preſerves all ſweet and wholeſome.

One method of making a plantation turn to profit in a ſhort time, is to begin with planting birch in rows with intervals of ſix feet, ſtirring the ground about them two years. In the intervals ſow acorns, cheſnuts, or beech-maſt. The birch, a faſt grower, will in a few years form a thick wood, deſtroy the weeds, and ſhade the young plants below them. The birch cut out when they begin to oppreſs the trees under them, will afford ſome profit, and leave the ground plentifully ſtored with better trees.

The beſt way to encourage trees planted in a row, is to draw a trench at the ſide of the row, at ſuch a diſtance as not to wound the roots. The earth thrown upon the roots will ſave weeding, and ſecure the trees againſt wind. The water in that trench will be an additional nouriſhment to the trees.

Evergreens, perſpiring leſs than other plants, require leſs nouriſhment, and for that reaſon continue green all winter. They reſemble the exanguous tribe of animals, the frog, the toad, the tortoiſe, the ſerpent, which, perſpiring little, make a ſhift to paſs the winter without food. Evergreens, by perſpiring little, have a thick, viſcid, oily, ſap, which enables them to endure the winter's cold. They ſeem many of them to thrive beſt in the temperate ſeaſons of the year; not ſo well in the heat of ſummer, their perſpiration being then too great for the ſlow aſcent of the ſap. Evergreens, when tranſplanted, do not ſo readily ſtrike root as other trees: for which reaſon they ought to be taken up with a bulk of earth about their roots. Gardeners commonly place ſhrubs of this kind in an oſier-baſket, which ſoon rots after it is put into the ground with a tree. A holly thus tranſplanted ought to be watered in the month of May, if the ſeaſon be dry.

In order to tranſplant a tree with a bulk of earth about the roots, cut a trench round it at the diſtance of ten or twelve inches, as deep as the roots go, cutting over with a ſharp knife all the roots that appear. Return the earth into the trench. Repeat the operation next year, but a little farther from the tree. When the tree is tranſplanted the year after, the roots will be ſo interlaced in the bulk, that none of the earth will fall away in carrying. The hole where the tree is to ſtand, ſhould be conſiderably larger than the bulk, and made ſome months before planting, to receive the influence of ſun, rain, and froſt. Fill up the hole with freſh good earth, fit to encourage the young roots. The harder the ſoil is, the hole ought to be the larger, to receive the greater quantity of the nouriſhing earth. In making the hole, lay the upper *ſtratum* on the one ſide, and what is below on the other: lay the former about the roots, being the beſt ſoil, and cover it with the latter. Preſerve as many roots as poſſible, ſhortening thoſe only that are too long, and what are torn in taking up. If the tree have too much head, ſhorten the largeſt branches, leaving the ſmall branches for carrying leaves: it is by theſe that the ſap is drawn up;

and it is by theſe that perſpiration is performed. But preſerve carefully the leading ſhoot or ſhoots; for many experiments have made it evident, that theſe have the greateſt power to draw up the ſap. If the lime be not an exception, a tree, after its head is lopped off, ſpreads into a buſh, but never riſes in height. Conclude all, by preſſing down the earth vigorouſly with the foot. A tree planted deep in the ground, ſtands the firmer againſt wind: its roots are better protected againſt ſun and froſt, and leſs apt to throw up ſuckers. Theſe conſiderations notwithſtanding, trees ought not to be planted deep; for they languiſh till they acquire roots near the ſurface. Theſe, ſpreading themſelves in the beſt ſoil, and being acceſſible to ſun and rain, convey much more nouriſhment to the tree than thoſe below. Nothing however is meant againſt planting large trees deeper than what are ſmall. At the ſame time, if the under ſoil be bad, or very moiſt, even large trees ought to be planted near the ſurface, with a bulk of earth about them. Becauſe in a porous ſoil the ſun penetrates deeper than in clay, and withers the roots near the ſurface; for that reaſon a tree ought to be planted deeper in the former than in the latter. Many think, that a fir does beſt where fir-trees have been recently cut: a fir being the native of a cold country, ſtands much in need of a ſhade in ſummer; and therefore ſucceeds the beſt when protected from the ſun by ſurrounding firs. So far the obſervation holds, and I believe no farther.

It ought to be an indiſpenſable duty, to viſit young plantations after every high wind, and to ſet upright thoſe that are ſhaken, preſſing the earth cloſe about the roots. Support a tree much ſhaken with a forked ſtick. I know no general rule more important than this. It is my opinion, that more trees are loſt by neglect of this operation, than any other way. The operation ought to be renewed after every high wind, till trees have acquired ſuch roots as to ſtand firm againſt wind.

Some are careful, to give a tranſplanted tree the ſame poſition with reſpect to the ſun, that it had in the nurſery. But experience has proved this precaution to be uſeleſs.

As the expence and riſk of filling up a vacant ſpot with a full-grown tree is great, a nurſery may be ſet apart for rearing young trees till they be from fifteen to eighteen feet high. Theſe trees may be tranſplanted twice or thrice in the nurſery for multiplying their roots; and they ought to be planted where they are to ſtand, with as much as poſſible of the nurſery-ſoil about the roots. In that view, froſt is the proper time for the operation. Such trees will not at firſt make ſo great a figure as full-grown trees; but there will be leſs hazard of miſcarrying.

Where trees of unequal growth are planted together, thoſe of the quickeſt growth will overtop the reſt, and deſtroy them. Therefore let trees of the ſame kind be planted in clumps; or let none be mixed but what grow equally faſt. I imagine there is a beauty in ſmall clumps, as it makes different ſhades the more conſpicuous. Colours, even the fineſt, make but a faint impreſſion in a confuſed mixture.

## 7. PRUNING.

AND now of pruning. By multiplied experiments it is aſcertained, that the cutting off young branches, hurts not any ſort of tree, not even the walnut, nor the reſinous kind. The loweſt branches, which in time would wither, and drop off, ought firſt to be cut; but gradually, that the tree may not be bared of leaves. Severe pruning makes trees grow tall, but withal ſo ſlender as not to reſiſt wind. Every tree ſuffers by having its large branches cut off, but in different degrees. The wound of an elm is ſoon healed: not of a walnut, an oak, or a pine; if the tree be not vigorous, the wound is apt to rot into the body. When a large branch is cut off, though the place of its inſertion is ſoon covered with wood and bark; yet the new wood doth not unite with the old, and there always remains a defect within. When an overgrown branch is cut cloſe to the trunk, which ought to be at the end of the year, the young ſhoots muſt the next June or July be pulled off with the hand. If cut off with a knife, ſhoots will grow without end, and create a disfiguring bunch in the tree. A writer whoſe integrity equals his experience, affirms, that a branch cut ſome inches from the trunk will make no blemiſh in the tree *. The greateſt attention ought to be given to the head: if forked, one of the rival branches muſt be cut off ſix inches high; and to the remaining ſtump ought to be tied the other branch, in order to give it an upright direction. If a young tree become ſtationary, as it is apt to do in ſtiff ſoil, cut it over by the ground in September, or rather below the ground. Next June or July tear off with the hand all the ſhoots but the ſtrongeſt, and lay earth round the ſtump. If this be delayed till the ſap fall, there is danger of tearing the bark of the ſtump, which would hurt it. Avoid a knife; for at every amputation ſhoots will puſh, which muſt again be cut, and a bunch will grow.

Pruning may go on from the beginning of July to the middle of September: trees later pruned ſuffer by cold. A holly is an exception: it has a large heart, and is hurt by froſt if clipped or pruned after the month of July. A holly-hedge, that was not clipped after the month of June,

---

* Kennedy.

endured without hurt the hard froſt of the year 1740.

The Scotch fir, which is not a fir but a pine, deſerves to be cultivated for beauty as well as for uſe. In a natural wood, the timber is always better, and freer of knots, than in a plantation. Trees are always planted at the ſame time; but in a natural wood are of different ages, the elder bearing down the younger, but not without loſing all their under branches. This in effect proves a benefit; for as the under branches do not ſpring again, there happens to be much timber without knots. In a planted field, on the contrary, the trees grow all equally; and if weeding be neglected, they grow up like ſpindles without a lateral branch: if duly weeded, ſo as to give room for lateral branches, the lower branches die by degrees, and leave knots in the trees. Therefore to train a fir-plantation, the trees ought to be thinned as ſoon as they begin to wind-wave; and the loweſt tire of branches ſhould be cut off from every tree that is intended to ſtand. Another tire ſhould be cut off the next year; and ſo on, leaving five or ſix feet of the trunk without a branch. All the wood that is added to the tree after, will be ſolid without a knot. A better way is, to tear off with the hand the under branches, which bring their roots with them: the hollow is ſoon filled up with regular fibres, and the wood is all equally good. A branch cut away with a knife, though cloſe to the ſtem, leaves its root, which becomes a knot when ſurrounded with new wood. If a Scotch fir be intended for beauty, let all other trees be kept at a diſtance, and it will ſtand forty or fifty years without loſing a branch. When a larche is fifteen or ſixteen feet high, cut off the loweſt tire of branches in October cloſe to the ſtem, and the next two tire ſucceſſively, year after year. The rays of the ſun will be admitted to the root of the tree; and the air will have a free circulation, neceſſary to all plants. It will not be neceſſary afterward to uſe a knife to a larche, unleſs it be to lop off a broken branch *.

Sheep and goats are more deſtructive to young trees than horned cattle; and theſe, more than horſes. Sheep are fond of the leaves of the white thorn, above all other food: it is folly to think of white-thorn hedges, without baniſhing them. The depredations of theſe creatures upon my plantations, have often ſwelled my heart againſt Providence. Why has it made young trees ſo palatable to them: what woods might not be raiſed, were it not for the expence of fencing! Such thoughts were apt to ſteal in upon me,

---

* In Mr Duff's garden, town of Air, there was an old ſtump of a thorn three or four feet high, that appeared to have very little life in it. It was pierced in ſeveral places with an iron nail: buds came out at every hole; and now it is a flouriſhing tree about fifteen feet high.

But in nothing are we more wrong than in murmuring againſt Providence. It is to us a ſignal bleſſing that domeſticated animals feed on young trees: otherwiſe, the utmoſt induſtry of man would be inſufficient to prevent trees from occupying the whole ground, and putting an end to agriculture; he would be reduced to his original ſavage ſtate.

### 8. WOOD PROPER FOR INSTRUMENTS OF HUSBANDRY.

AMONG the moſt expenſive articles of a farm, are carts, ploughs, brakes, harrows, rollers, &c.: and it is of importance with reſpect to economy, that theſe ſhould be conſtructed of proper wood. To that end the following hints may be of uſe.

I begin with examining, at what age a tree is in perfection for the purpoſes of a farm. At the age of ſixty, it is ſufficiently large for every farm-purpoſe; being, when cut to the ſquare, from twelve to fifteen inches each ſide. I muſt except the oak, which, even for the purpoſes of farming, improves till it be a hundred years old. Every oak conſiſts of red and white wood; the former the firmeſt of all wood, the latter good for nothing. Aſh, after the growth of ſixty years, turns ſhort and brittle.

The proper ſeaſon for cutting a tree is, when it has leaſt ſap; which is preciſely in the middle between the time of ſhedding the leaf and that of budding: in that interval it is tough, and fitteſt for every farm-purpoſe. When cut in the ſap, the wood is ſhort, and apt to ſplit with drought.

For preſerving wood after being cut, there are three methods. One is, to dry it in the air; another, to immerſe it in water; and a third, to cover it up with horſe-dung. Aſh, when ſawed green, never fails to ſplit. Before applying an inſtrument, it ought to be expoſed eighteen months in a dry ſituation, that all the ſap may evaporate. During that time, both ends ought to be covered from the air: the bark prevents the body from ſplitting; but when the ends are expoſed, they will ſplit into the body five or ſix inches. When aſh is deſigned for uſes that require it to be ſplit, let it be ſplit immediately after cutting, and the parts laid up where the air has not free acceſs, in order that they may dry by ſlow degrees; for ſudden drought makes them warp. Oak and elm require the ſame treatment. The Huntington willow, and other willows that riſe to a large ſize, turn extremely tough when dry; and therefore, if intended for planks or boards, they ought to be ſawed directly after being cut. But as in this caſe they are apt to ſplit, great care ought to be taken to dry them ſlowly. Alder and birch ought to be managed in the ſame manner.

The immerſing in water, and covering with horſe-dung, are far from being the beſt methods of drying wood. It is always harder and tougher when dried ſlowly in the air. Therefore theſe methods are only for expedition, in order to extract the ſap the more quickly, when the wood is wanted for immediate uſe.

There is not an inſtrument of huſbandry that conſiſts of different parts, but requires wood of different kinds. Of all wood, oak is that which reſiſts moiſture the beſt, and can the beſt endure the being totally deprived of air. For theſe reaſons, oak is the only wood fit for being mortiſed into other wood. From the part that is mortiſed, air is totally excluded; and yet ſome moiſture finds acceſs, being more penetrating than air. Therefore, the ſpokes of a wheel, which are mortiſed both into the nave and fillies, ought indiſpenſably to be of oak; the ſheths of harrows, which bind the parts together, ought to be of the ſame wood; as alſo the head of the chain-plough, becauſe it is mortiſed into the beam. As aſh is leſs apt to ſplit than oak, it is the more proper wood of the two for naves and fillies. As it is the tougheſt of all wood, and the moſt elaſtic, it is fitteſt for the trams of a cart. The beſt wood for the body of a cart or waggon, is the Huntington willow. It is both lighter and tougher than even the beſt red fir. The head of the Scotch plough may be of alder, becauſe it is not mortiſed into any other part. Whatever the plough be, the mouldboard may be of willow, or alder, or plane; becauſe they are lighter, and not apt to ſplit. The bulls of brakes and harrows ſhould be of birch or alder. A roller ſhould be made of beech wood, being heavy, the ſheths and pins of oak, and the ſhafts of aſh. Foreign fir is the beſt and cheapeſt for couples. Beech-wood is firmer and tougher. It is indeed apt to take the worm: but in a farm-houſe that is not lofted, will not the japanning with ſmoke prevent that evil? The handles of ſpades, ſhovels, picks, &c. ought undoubtedly to be of aſh: beſide its toughneſs, it is leſs apt to turn warm in handling, than any other wood. For gates, fir is undoubtedly the beſt: It is light; it reſiſts moiſture and is not apt to warp.

One general rule I give, of more importance than at firſt view may be thought, which is, that the angle made by mortiſing, or otherwiſe, being always the weakeſt part of the inſtrument, ought to be fortified with a plate of iron fitting accurately the angle of the wood.

## SECT. II.

### FLAX.

HAVING finiſhed what I had to ſay on foreſt-trees, flax comes next in order, according to the diſtribution made above. The regulations publiſhed by the truſtees for manufactures, have left me little to obſerve upon that article. I ſhall

venture

venture a few particulars only, more immediately connected with huſbandry. Annual weeds abound ſo much in this country by careleſs management, that the weeding of flax is the greateſt incumbrance on its culture. After horſe-hoed turnip, cabbage, or potatoes, flax ſucceeds well; and I know no other crops that extirpate weeds ſo effectually. A potato-crop being removed in October, the ground during winter gets a froſt-preparation; which cannot be obtained after cabbage or turnip, becauſe theſe keep the ground all winter. Therefore, above all, I recommend a potato-crop as a preparation for flax. Next to it, if at all inferior, is paſture-ground three or four years old, left rough in foggage, and in that ſtate trench-ploughed before winter. It gets the froſt-preparation, is clean of weeds; and the rough foggage, turned to the bottom of the furrow, retains moiſture like a ſpunge, which it yields plentifully to the roots of the flax. Flax is a thirſty plant; and a better ſituation it cannot have for procuring nouriſhment.

In pulling flax, the fully ripe ought to be ſeparated from what is leſs ſo, and the tall from the ſhort: when mixed, they neither water well, nor dreſs well. Let the ſeed, when ſeparated from the plant, be beat lightly and paſſed through a ſieve. The beſt and plumpeſt will come out firſt; and this ought to be reſerved for ſowing again. Beat what remains with a heavier hand: the ſeed thus got will be fit for the oil-mill.

Lint pulled green requires more watering than when fully ripe.

## SECT. III.

### HOPS.

THE laſt article of this kind I undertook, is the hop. A regular hop-yard is an undertaking too great for an ordinary farmer; but every farmer, by the following plan, may have hops of his own growing ſufficient for his own uſe, and perhaps for his neighbours. If I can reduce the expence within moderate bounds, I am not afraid of the climate of Scotland: many judicious trials made here, have produced good hops.

Dr Woodward has obſerved, that the fruit which grows neareſt the ground, is always the beſt. This has ſuggeſted to me a thought, that hops may be propagated in the eſpalier way like apples or pears. Fix in the ground, at an interval of three feet, a number of poles eight or nine feet high, in a line from weſt to eaſt. Beginning at the weſt end, plant a hop-vine at the foot of every pole, the laſt ſix or ſeven excepted. Inſtead of allowing them to aſcend the poles, train them from weſt to eaſt in an angle with the horizon of nine or ten degrees, and directing them from pole to pole by ſmall twigs between the poles. In this manner, each vine may extend itſelf twenty or thirty feet, without riſing at its extremity more than ten feet above the ground. If a hop reſemble other fruit-trees, it will carry more fruit by having the growth of the wood checked. And if this method ſucceed, a ſmall hop-plantation may be within the reach of every farmer, requiring ſome attention, but little expence. Poles above twenty feet long, renewed every two or three years, is a moſt expenſive article in an Engliſh hop-yard; and the places in Scotland are few where they can be procured at any rate: but poles of nine or ten feet may be procured every where. There is another ſignal advantage of this method: Wind is a great enemy to a hop-yard; but a row of humble poles bound together by hop-vines will be ſufficiently ſecure againſt wind, eſpecially in a line from weſt to eaſt.

Taking it for granted, that the fruit next the ground is the beſt, I am in the courſe of an experiment with a young apple-tree having two branches, one trained to the weſt, the other to the eaſt, upon ſmall pegs of wood about ſix inches high. Under theſe branches the earth is covered with ſharp ſand, in order that the fruit may be benefited both by the direct and reflected rays of the ſun. It deſerves an experiment, whether hops may not be trained ſucceſsfully the ſame way, without the expence of any poles. It will coſt very little expence to fill a whole acre in that manner, making an interval of a foot or eighteen inches, in order that the ſun may have acceſs to all of them equally.

CHAP.

## CHAP. XI.

## MANURES.

THE manures commonly uſed in Scotland are dung, lime, ſhell-marl, clay-marl, and ſtone-marl. Many other ſubſtances are uſed; ſhavings of horn, for example, refuſe of malt, and even old rags: but as the quantity that can be procured is inconſiderable, and as their application is ſimple, I ſhall conſume no time upon them.

Dung is the chief of all manures; becauſe a quantity of it may be collected in every farm, and becauſe it makes the quickeſt return. A field ſufficiently dunged, will produce good crops four or five years.

Dung of animals that chew the cud, being more thoroughly putrefied than that of others, is fit to be mixed with the ſoil without needing to be collected into a dunghill. A horſe does not chew the cud; and in horſe-dung may be perceived ſtraw or ryegraſs broken into ſmall parts, but not diſſolved: it is proper therefore that the putrefaction be completed in a dunghill. It ought to be mixed there with cool materials: ſo hot it is, that in a dunghill by itſelf, it ſinges and burns inſtead of putrefying. The difference between the dung of a horſe and of a horned animal, is viſible in a paſture-field: the graſs round the former is withered; round the latter, it is ranker and more verdant than in the reſt of the field. A mixture of dry and moiſt ſtuff, ought to be ſtudied: the former attracting moiſture from the latter, they become equally moiſt.

To prevent ſap from running out of a dunghill, its ſituation ſhould be a little below the ſurface; and to prevent rain from running into it, it ſhould be ſurrounded with a ring of ſod. If the ſoil on which the dunghill ſtands be porous, let it be paved, to prevent the ſap from ſinking into the ground. If moiſture happen to ſuperabound, it may be led off by a ſmall gutter to impregnate a quantity of rich mould laid down to receive it, which will make it equal to good dung.

Straw ſhould be prepared for the dunghill, by being laid under cattle, and ſufficiently moiſtened. When laid dry into a dunghill, it keeps it open, admits too much air, and prevents putrefaction.

Dung from the ſtable ought to be carefully ſpread on the dunghill, and mixed with the former dung. When left in heaps upon the dunghill, fermentation and putrefaction go on unequally.

Complete putrefaction is of importance with regard to the ſeed of weeds that are in the dunghill: if they remain ſound, they are carried out with the dung, and infeſt the ground. Complete putrefaction is of ſtill greater importance by pulveriſing the dung; in which condition it mixes intimately with the ſoil, and operates the moſt powerfully. In land intended for barley, undigeſted dung has an unhappy effect: it keeps the ground open, admits drought, and prevents the ſeed from ſpringing. On the other hand, when thoroughly rotted, it mixes with the ſoil, and enables it to retain moiſture. It follows, that the propereſt time for dunging a field, is in its higheſt pulveration; at which time the earth mixes intimately with the dung. Immediately before ſetting cabbage, ſowing turnip, or wheat, is a good time. Dung divides and ſpreads the moſt accurately when moiſt. Its intimate mixture with the ſoil is of ſuch importance, that hands ſhould be employed to divide and ſpread any lumps that may be in it.

Dung ſhould be ſpread, and ploughed into the ground, without delay. When a heap lies two or three weeks, ſome of the moiſture is embibed into the ground, which will produce tufts of corn more vigorous than in the reſt of the field. There cannot be a worſe practice than to lead out dung before winter, leaving it expoſed to froſt and ſnow. The whole ſprit of the dung is extracted by rain, and carried off with it. The dung diveſted of its ſap becomes dry in ſpring, and incapable of being mixed with the mould. It is turned over whole by the plough, and buried in the furrow.

I approve not of ploughing down buck-wheat, red clover, or any other crop, for manure. The beſt way of converting a crop into manure is, to paſs it through the body of an animal. The dung and piſs, not to mention the profit of feeding, will enrich the ground more than to plough down the crop.

As dung is an article of the utmoſt importance in huſbandry, one ſhould imagine, that the collecting it would be a capital article with an induſtrious farmer. Yet an ingenious writer, obſerving that the Jamaicans are in this particular much more induſtrious than the Britiſh, aſcribes the difference to the difficulty of procuring dung in Jamaica. "In England, where the long winter "enables a farmer to raiſe what quantity he "pleaſes, it is not collected with any degree of "induſtry. But in Jamaica, where there is no "winter, and where the heat of the ſun is a "great obſtruction, the farmer muſt be indefatigable, or he will never raiſe any dung."[a] Cool intereſt is not alone a ſufficient motive with the indolent, to be active. As dung is of great importance in huſbandry, a farmer cannot be too aſſiduous, in collecting animal and vegetable ſubſtances that will rot. One article of that kind there is, to collect which there is a double motive, and yet is neglected almoſt every where. A farm full of weeds is a nuiſance to the neighbourhood: it poiſons the fields around; and the poſſeſſor ought to be diſgraced as a peſt to ſociety. Now the cutting down every weed before the ſeed is formed, anſwers two excellent purpoſes. Firſt, it encourages good crops by keeping the ground clean. Next, theſe weeds mixed with other materials in a dunghill, may add conſiderably to the quantity of dung.

Next of lime, which is a profitable manure, and greatly profitable when it can be got in plenty within a moderate diſtance. Philoſophers differ widely about its nature, and the cauſe of its effects; and they talk ſo looſely, as to convince a plain farmer that the matter is very little underſtood. But practice is our preſent theme; and the benefit of lime is ſo viſible, that the uſe of it has become general, where the price and carriage are in any degree moderate.

However people may differ in other particulars, all agree, that the operation of lime depends on its intimate mixture with the ſoil; and therefore that the proper time of applying it, is when it is perfectly powdered and the ſoil at the ſame time in the higheſt degree of pulveration. This opinion appears to have a ſolid foundation. Lime of itſelf is abſolutely barren; and yet it enriches a barren ſoil. Neither of the two produces any good effect without the other: therefore the effect muſt depend on the mixture; and conſequently the more intimately they are mixed the effect muſt be the greater *.

Hence it follows, that lime ought always to be ſlaked with a proper quantity of water, becauſe by that means it is reduced the moſt effectually into powder. Lime left to be ſlaked by a moiſt air, or accidental rain, is ſeldom or never thoroughly reduced into powder; and therefore can never be intimately mixed with the ſoil. Some-

---

[*] Mr Buchanan of Achleſhy, in Perthſhire, prepared a quantity of lime for manuring a moor ploughed before winter. Lime was immediately ſpread upon a part of it; but the work was ſtopped by bad weather. The remaining lime was indeed covered with ſod, but ſo ſlightly as not to throw off the rain. When laid on the reſt of the field in March, it was ſo clotted as to be but very imperfectly mixed with the ſoil. The crop of oats on the part firſt limed was good; that on the part laſt limed was good for nothing. The ſubſequent crops however on this part proved tolerable, the lime by repeated ploughings being better mixed with the ſoil.——In ſeveral parts of Scotland are found limeſtone of two different ſorts. The operation of the one is quick when ſpread upon a field after calcination; but its prolific effects are ſoon over. The other operates more ſlowly; but its prolific effects continue longer. The former upon being ſlaked falls readily into a very fine powder: the latter falls more ſlowly into a powder that is not ſo fine. This accounts for the difference. The fine powder mixes more intimately with the ſoil, and more quickly, than the coarſe powder. For the ſame reaſon, the fine powder makes the beſt cement, by mixing eaſily and perfectly with the ſand and water.

times an opportunity offers to bring home ſhell-lime before the ground is ready for it; and it is commonly thrown into a heap without cover, truſting to rain for ſlaking. The proper way is, to lay the ſhell-lime in different heaps on the ground where it is to be ſpread, to reduce theſe heaps into powder by ſlaking with water, and to cover the ſlaked lime with ſod ſo as to defend it from rain. One however would avoid as much as poſſible the bringing home lime before the ground be ready for it. Where allowed to lie long in a heap, there are two bad conſequences: firſt, lime attracts moiſture, even though well covered, and runs into clots, which prevents an intimate mixture; and, next, we learn from Dr Black, that burnt limeſtone, whether in ſhells or in powder, returns gradually into its original ſtate of limeſtone; and upon that account alſo, is leſs capable of being mixt with the ſoil. And this is verified by a fact, that after lying long, it is ſo hard bound together as to require a pick to ſeparate the parts.

For the ſame reaſon, it is a bad practice, tho' common, to let ſpread lime lie on the ſurface all winter. The bad effects above mentioned take place here in part: and there is another; that rain waſhes the lime down to the furrows, and in a hanging field carries the whole away.

As the particles of powdered lime are both ſmall and heavy, they quickly ſink to the bottom

the furrow, if care be not taken to prevent it.
that view, it is a rule, that lime be ſpread, and
xed with the ſoil, immediately before ſowing,
along with the ſeed. In this manner of appli-
tion, there being no occaſion to move it till the
ound be ſtirred for a new crop, it has time to
corporate with the ſoil, and does not readily
parate from it. Thus, if turnip-ſeed is to be
wn broadcaſt, the lime ought to be laid on im-
ediately before ſowing, and harrowed in with
e ſeed. If a crop of drilled turnip or cabbage
intended, the lime ought to be ſpread imme-
ately before forming the drills. With reſpect
wheat, the lime ought to be ſpread imme-
ately before ſeed-furrowing. If ſpread more ear-
before the ground be ſufficiently broken, it

cient, reckoning four ſmall firlots to the boll, termed wheat-meaſure; nor will it be an over-doze to lay on a hundred bolls. Between fifty and ſixty may ſuffice upon medium ſoils; and upon the thin or gravelly, between thirty and forty. It is not ſafe to lay a much greater quantity on ſuch ſoils.

It is common to lime a paſture-field immediately before ploughing. This is an unſafe practice: it is thrown to the bottom of the furrow, from which it is never fully gathered up. The proper time for liming a paſture-field, intended to be taken up for corn, is a year at leaſt, or two, before ploughing. It is waſhed in by rain among the roots of the plants; and has time to incorporate with the ſoil.

With regard to the expence of carriage, to have the lime-kiln ſo near as to go twice a-day, is a great ſaving. But if there can be but one carriage in a day, there is little difference as to expence, whether the diſtance be ſeven or eleven miles. A little more food to the cattle makes all equal.

Limeſtone beat ſmall makes an excellent manure, and ſupplies the want of powdered lime, where there is no feuel to burn the limeſtone. Limeſtone beat ſmall has not hitherto been much uſed as a manure; and the proportion between it and powdered lime has not been aſcertained. What follows may give ſome light. Three pounds of raw lime is by burning reduced to two pounds of ſhell-lime. Yet nothing is expelled by the fire but the air that was in the limeſtone; the calcarious earth remains entire. *Ergo*, two pounds of ſhell-lime contains as much calcarious earth as three pounds of raw limeſtone. Shell-lime of the beſt quality, when ſlaked with water, will meaſure out to thrice the quantity. But as limeſtone loſes none of its bulk by being burnt into ſhells, it follows, that three buſhels of raw limeſtone contains as much calcarious earth as ſix buſhels of powdered lime. And conſequently, if powdered lime poſſeſs not ſome virtue above raw limeſtone, three buſhels of the latter beat ſmall ſhould equal as a manure ſix buſhels of the former.

Shell-marl, as a manure, is managed in every reſpect like powdered lime, with this only difference, that a fifth or a fourth part more in meaſure ought to be given. The reaſon is, that ſhell-marl is leſs weighty than lime, and that a boll of it contains leſs calcarious earth, which is the fructifying part of both.

I ſhall conclude with clay and ſtone marls, which, with reſpect to huſbandry, are the ſame, though in appearance different. The manures hitherto mentioned are reſtoratives only: they recruit land when worn out by cropping, and enable it to bear more crops. The marl now under conſideration is not only a reſtorative, but has an effect ſtill more deſirable, that of altering the nature of the ſoil, and improving its texture, ſo as to convert it from light to heavy, and from weak to ſtrong. I know nothing comparable to it in that reſpect, but the poaching light land by cattle fed with turnip, mentioned in a foregoing chapter. It has another effect, in appearance oppoſite; which is, to looſen a clay ſoil, and to make it more free.

The goodneſs of this marl depends on the quantity of calcarious earth in it; which I have known to amount to a half or more. It is too expenſive if the quantity be leſs than a third or a fourth part. Good marl is the moſt ſubſtantial of all manures; becauſe it improves the weakeſt ground to equal the beſt borough-acres. One inſtance I know, of two ridges marled a hundred and twenty years ago, that at this day make a figure both in graſs and corn far above the reſt of the field. The low part of Berwickſhire, termed *the Merſe*, abounds every where with this marl; and is the only country in Scotland where it is in plenty.

As none of the manures I am acquainted with make any diſtinction between weeds and corn, the land ought to be cleared of weeds before marling; and it ought to be ſmoothed with the brake and harrow, in order that the marl may be equally ſpread. Marl is a foſſil on which no vegetable will grow: its efficacy depends, like that of lime, ne, on its pulveration, and intimate mixture th the ſoil. Toward the former, alternate ought and moiſture contribute greatly, as alſo oſt. Therefore after being evenly ſpread, it ght to lie on the ſurface all winter. In the onth of October, it may be rouſed with a brake, hich will bring to the ſurface, and expoſe to the and froſt, all the hard parts, and mix with the l all that is powdered. In that reſpect it differs dely from dung and lime, which ought to be oughed into the ground without delay. Oats a hardy grain, which will anſwer for being the ſt crop after marling, better than any other; d it will ſucceed though the marl be not thoughly mixed with the ſoil. In that caſe, the rl ought to be ploughed in with an ebb furrow fore the firſt crop ſhould always have an ebb furrow. During the growing of that crop, the marl has time to incorporate with the ſoil, and to become a part of it; after which it does not readily ſeparate.

Stone marl is ſo hard by a conſiderable mixture of ſand, that it will continue without diſſolving for years. In that caſe, the expence of breaking the larger lumps with hammers would not be loſt: ſuch lumps have no effect to promote vegetation; and they are beſide an obſtruction to ploughing and harrowing.

About twenty years ago, many Merſe tenants applied their whole ſtrength to marling, with very great ſucceſs: and yet of late they ſeem more intent on liming; which may appear ſingular in a country where huſbandry goes on with alacrity. But leaſes in that country are commonly limited to nineteen years, which, it is thought, affords too little time for drawing all the profit from this expenſive manure, that the tenant is intitled to. To marl to perfection, requires four hundred cartloads on an acre, as much as can be drawn by two ſturdy horſes; which, at a moderate computation, coſts about L. 4 per acre. But a field can be ſufficiently limed from the diſtance of fifteen Engliſh miles, for little above the half of that ſum; with this additional convenience, that a farmer can hire carts for liming, inſtead of being confined to his own horſes, as he muſt be in marl-

; by which means, liming can be carried on
h much more expedition than marling. Not-
hſtanding theſe differences, it is eaſy to evince,
t even on a leaſe of nineteen years, marl will
ord a greater profit than lime. Limed ground
nnot bear without injury above three or four
ops; after which it ought to be laid down in
aſs. A field well marled, will produce rich
ops of corn, in the ſimpleſt manner of culture,
long as the leaſe endures. Now, though graſs
more profitable than corn in a poor ſoil, the
ofit bears no proportion in a rich ſoil, which
oduces excellent crops, with no greater labour
r expence than is neceſſarily beſtowed on poor
l.

derable. A ſquare field of ten acres incloſed with a wall ſix feet high, will coſt L. 50, 15 s.; and L. 42 : 5 : 10, if the wall be five feet high. And it will require two and one half per cent. to keep them in order. To build with lime, as many do, inflames the coſt; and yet upon the whole is a ſaving where lime is at hand.

To reduce both the expence of building dry-ſtone walls, and of upholding them, I warmly recommend the following mode. Raiſe the wall to the height only of two feet and a half, and cope it with ſod in the following manner. Firſt, lay on the wall with the graſſy ſide undermoſt, ſod cut with the ſpade four or five inches deep, and of a length to equal the thickneſs of the wall. Next, cover this ſod with looſe earth rounded like a ridge. Third, prepare thin ſod, caſt with the paring ſpade, ſufficiently long for the thickneſs of the wall, and two inches more on each ſide. With theſe cover the looſe earth, keeping the graſſy ſide uppermoſt: place them ſo much on edge, as that each ſod ſhall cover part of another, leaving only free two inches above. Fourth, when twenty or thirty yards are thus finiſhed, let the ſod be beat with mells by two men, one on each ſide of the wall, ſtriking both at the ſame time. By this operation, the ſod becomes a compact body, that keeps in the moiſture, and encourages the graſs to grow. Laſtly, cut off the ragged ends of the ſod on each ſide of the wall,

make the covering neat and regular. The
onth of October is the proper ſeaſon for this o-
ration, becauſe the ſun and wind, during ſum-
er, dries the ſod, and hinders the graſs from ve-
tating. Moiſt ſoil affords the beſt ſod. Wet
il is commonly too fat for binding ; and at any
te, the watery plants it produces will not thrive
a dry ſituation. Dry ſoil, on the other hand,
ing commonly ill bound with roots, ſhakes to
eces in handling. The ordinary way of coping
th ſod, which is to lay them flat and ſingle,
oks as if intended to dry the coping, and to kill
e graſs ; not to mention, that the ſod is liable
be blown off the wall by every high wind.

Having finiſhed the wall, caſt a ditch on each
le, beginning a foot from the root of the wall,

That this is far from being the caſe of a dry-ſtone wall ſix feet or even five feet high, all the world know.

Next of thorn-hedges. The advantage of the white thorn for a fence above every other plant, is well underſtood. It is a quick grower when planted in proper ſoil, ſhooting up ſix or ſeven feet in a ſeaſon. Though tender when young and hurt by weeds, it turns ſtrong, and may be cut into any ſhape. Even when old, it is more diſpoſed than other trees to lateral ſhoots. And, laſtly, its prickles make it the moſt proper of all for a fence.

The method of ſowing the ſeed in beds, is ſet forth in the chapter of Foreſt-Trees. After the plants have ſtood a full year in the ſeed-bed, tranſplant the largeſt into a nurſery, which will leave ſufficient room for the remainder, to ſtand where they are another year. In the nurſery they ought to ſtand at the diſtance of ſeven, eight, or nine inches from each other; and there they may remain till fit to be planted in a hedge, which is no ſooner than at the age of five. Room in a nurſery is of great importance: when ſtraitened for room, the plants ſhoot up faſt, are weakly, and unfit to bear the hardſhips of an open field. The diſtance ought to be proportioned to the ſoil; the greateſt in a rich ſoil, becauſe they grow faſt; the leaſt in a poor ſoil, where they grow ſlow. The beſt ſoil for a nurſery is between rich and

poor,

r. In the latter, the plants are dwarfiſh : in
former they are luxuriant and tender, and apt
be hurt in the ſeverity of weather : and theſe
erfections are incapable of any remedy. An
ntial requiſite in a nurſery is free ventilation.
w common is it to find nurſeries in hollow-
ltered places, ſurrounded with walls and high
ntations, more fit for pine-apples than for bar-
trees. The plants thruſt out long ſhoots, but
ble and tender : when expoſed to a cold ſitua-
n, they decay, and ſometimes die. But there
reaſon for every thing : the nuſeryman's view
to make profit by ſaving ground, and by im-
ing on the purchaſer tall plants, for which he
tends to demand double price. It is ſo diffi-
to purchaſe wholeſome and well-nurſed plants,

all the additional ſum that can be demanded for them. Young and feeble plants in a hedge, are of ſlow growth; and beſide loſs of time, the paling, neceſſary to ſecure them from cattle, muſt be renewed more than once before they become a fence.

A thorn-hedge may be planted in every month of winter and ſpring, unleſs it be froſt. But I have always obſerved, that thorns planted in October are more healthy, puſh more vigorouſly, and fewer decay, than at any other time. In preparing the thorns for planting, the roots ought to be left as entire as poſſible, and nothing cut away but the ragged parts.

As a thorn-hedge ſuffers greatly by weeds, the ground where they are to be planted ought to be made perfectly clean. The common method of planting is, to leave eight or nine inches along a ſide of the intended ditch for a ſcarſement; and behind the ſcarſement to lay the ſurface-ſoil of the intended ditch, cut into ſquare ſods two or three inches deep, its graſſy ſurface undermoſt. Upon that ſod, whether clean or dirty, the thorns are laid, and the earth of the ditch above them. According to that method, the graſs in the ſcarſement, with what weeds are in the moved earth, ſoon grow up, and require double diligence to prevent the young thorns from being choked. The following method, which is creeping into practice, deſerves all the additional trouble it requires.

quires. Leaving a ſcarſement as above of ten inches, and alſo a border for the thorns, broad or narrow according to their ſize, lay behind the border all the ſurface of the intended ditch, champed ſmall with the ſpade, and upon it lay the mouldery earth that fell from the ſpade in cutting the ſaid ſurface. Cover the ſcarſement and border with the under earth, three inches thick at leaſt; laying a little more on the border to raiſe it higher than the ſcarſement, in order to give room for weeding. After the thorns are prepared, by ſmoothing their ragged roots with a knife, and lopping off their heads in order to make them grow buſhy, they are laid fronting the ditch, with their roots on the border, the head a little higher than the root. Special care muſt be taken to ſpread the roots among the ſurface-earth taken out of the ditch, and to cover them with the mouldery earth that lay immediately below. This article is of importance, becauſe the mouldery earth is the fineſt of all. Cover the ſtems of the thorns with the next *ſtratum* of the ditch, leaving always an inch at the top free. It is no matter how poor this *ſtratum* be, as the plants draw no nouriſhment from it. Go on to finiſh the ditch, preſſing down carefully every row of earth thrown up behind the hedge, which makes a ſolid mound impervious to rain. It is a ſafeguard to the young hedge to raiſe this mound as perpendicular as poſſible; and for that end it may be

proper,

proper in looſe ſoil, when the mound is raiſed a foot or ſo, to bind it with a row of the tough ſod, which will ſupport the earth above, till it become ſolid by lying.

This is ſufficient in rich ſoil; but where the ſoil is not rich, greater care is neceſſary. Behind the line of the ditch, the ground intended for the ſcarcement and border ſhould be ſummer-fallowed, manured, and cleared of all graſs-roots; and this culture will make up for the inferiority of ſoil. In very poor ſoil it is vain to think of planting a thorn-hedge; for it will give no ſatisfaction, becauſe it never will become a fence. In ſuch ground there is a neceſſity for a ſtone fence.

The only reaſon that can be given for laying thorns as above deſcribed, is to give the roots ſpace to puſh in all directions, even upward into the mound of earth. There may be ſome advantage in this; but, in my apprehenſion, the diſadvantage is much greater of heaping ſo much earth on the roots, as to exclude not only the ſun and air, but even rain, which runs down the ſloping bank, and has no acceſs to the roots. Inſtead of laying the thorns fronting the ditch, would it not do better to lay them parallel to the ditch; covering the roots with three or four inches of the beſt earth, which would make a hollow between the plants and the ſloping bank? This hollow would intercept every drop of rain that falls on the bank, to ſink gradually among the roots. If this be not a better poſition for a thorn, it muſt be of a ſingular conſtitution. I venture one ſtep farther out of the common path. Why at any rate ſhould a thorn be put in the ground ſloping? This is not the practice with reſpect to any other tree; and I have heard of no experiment to perſuade me that a thorn thrives better ſloping than erect. But as in natural hiſtory experiment is always our laſt reſource, I am at preſent following out a comparative trial. I have many young hedges in the way firſt deſcribed: ſome I have laid parallel to the ditch in the way now deſcribed, and ſome I have planted erect with their tops entire. The trials are fairly made; and time will determine the beſt method.

In a rich ſoil the thorns may be planted ten inches aſunder; and from that to ſix inches in inferior ſoils. To preſerve them from cattle, the ditch ought to be ſix feet wide, three feet deep, and as narrow at bottom as the breadth of the ſpade will allow. But when the thorns are ſufficiently covered, the prudent way is to delay finiſhing the ditch till the froſt be over. Spring is the proper time for completing the work, while there is ſufficient ſap in the ſoil, to bind the mound of earth that is raiſed behind the thorns. If delayed till the earth be dry, it never binds: if completed the beginning of winter, froſt ſwells the earth, looſens it, and makes it crumble down.

The hedge is fenced from cattle on the one ſide by the ditch; but it is neceſſary that it be fenced on both ſides. The ordinary method of a paleing is no ſufficient fence againſt cattle: the moſt gentle make it a rubbing-poſt; and the vitious break it down wantonly with their horns. The only effectual remedy is expenſive; but better no fence than one that is imperfect. The remedy is, two ditches and two hedges, with a high mound of earth between them. Survey Scotland, and you will not find any fences otherwiſe conſtructed without many breaches; the repairing of which gives much trouble and little ſatisfaction. If this remedy however be not palatable, the paleing ought at leaſt to be of the ſtrongeſt kind. Many different kinds have been put in practice, that are extremely frail. I recommend the following, as the beſt I am acquainted with. Drive into the ground ſtrong ſtakes three feet and a half long, with intervals from eight to twelve inches, according to the ſize of the cattle that are to be encloſed; and all preciſely of the ſame height. Prepare plates of wood ſawed out of logs, every plate three inches broad and half an inch thick. Fix them on the head of the ſtakes, with a nail driven down into each ſtake. The ſtakes will be united ſo firmly, that one cannot be moved without the whole; and will be proof accordingly againſt the rubbing of cattle. But, after all, it is no fence againſt vitious cattle. The only proper

ace for it is the ſide of a high-road, or to fence
plantation of trees. It will indeed be a ſufficient
nce againſt ſheep, and endure till the hedge it-
f be a fence. A fence thus completed, inclu-
ng thorns, ditching, wood, nails, &c. will not
uch exceed two ſhillings every ſix yards.

We are now arrived at the moſt important ar-
le of all, that of training up a thorn-hedge after
is planted. The ordinary method is, to cut off
e top, and ſhorten the lateral branches, in or-
r to make it thick and buſhy. To the ſame
d, the young thorns, after ſtanding ſix or ſeven
ars, are ſometimes cut over within two or three
ches of the ground, which multiplies the ſtems,
d makes the hedge ſtill thicker. This form of

which have been deſtroyed by the overſhadowing of thoſe above, depriving them both of rain and air. That the ſecond is the beſt method, is aſcertained by experience. And that it ought to be ſo, will be evident if we can truſt to analogy. In the natural growth of a tree, its trunk is proportioned to its height: lop off the head, it ſpreads laterally and becomes a buſh, without riſing in height, or ſwelling in the trunk. The lime-tree is the only exception I know: the white thorn I am certain is not an exception. Hence the following method of training up a hedge, which is to allow the thorns to grow without applying a knife to their tops, till their ſtems be five or ſix inches in circumference. In good ſoil, with careful weeding, they will be of that bulk in ten or twelve years, and be fifteen feet high or upward. The lateral branches only muſt be attended to. Thoſe next the ground muſt be pruned within two feet of the ſtem: thoſe above muſt be made ſhorter and ſhorter, in proportion to their diſtance from the ground; and at five feet high they muſt be cut cloſe to the ſtem, leaving all above full freedom of growth. By this dreſſing, the hedge takes on the appearance of a very ſteep roof; and it ought to be kept in that form by pruning. This form gives free acceſs to rain, ſun, and air: every twig has its ſhare, and the whole is preſerved in vigour. When the ſtems have arrived at their proper bulk, cut over them at five feet from the ground, where the lateral branches end. This anſwers two excellent purpoſes; the firſt is, to ſtrengthen the hedge, the ſap that formerly aſcended to the top being now diſtributed among the branches. The next is, that a tall hedge ſtagnates the air, and poiſons both corn and graſs near it. A hedge trained up in this manner, is impenetrable even by a bull: he may preſs in the lateral branches; but the ſtems ſtand firm. For an inſtant proof that this method will anſwer, obſerve the thorns that from ſpace to ſpace are allowed to grow up above their fellows, in form of a hedge-row. Theſe thorns, though growing in the middle of a buſhy hedge, have ſtems far larger than the reſt. Beſide the ſtrength of ſuch a hedge, it is leſs expenſive than a hedge reared in the ordinary way: the weeds are ſooner choaked; and it requires much leſs pruning. When ſo much labour is ſaved, one will the leſs grudge the price of the beſt thorns that can be procured. Good thorns are indeed more eſſential in this manner of training up a hedge than in any other: they ought all to be of an equal ſize, and equally vigorous, that they may not overtop one another. The intermixing of ſtrong and weak plants is of leſs importance, where the heads are cut off and all made to grow equally.

Plaſhing an old hedge, an ordinary practice in England, makes indeed a good interim fence; but at the long-run is deſtructive to the hedge:

and accordingly, there is ſcarce to be met with a complete good hedge where plaſhing has been long practiſed. A cat is ſaid among the vulgar to have nine lives: is it their opinion, that a thorn, like a cat, may be cut and ſlaſhed at will without ſuffering by it? Lucky it is, that the method here recommended renders plaſhing altogether unneceſſary.

A hedge ought never to be planted on the top of the mound of earth thrown up from the ditch. It has indeed the advantage of an awful ſituation; but being planted in bad ſoil, and deſtitute of moiſture, it cannot thrive: it is at beſt dwarfiſh, and frequently decays and dies.

To plant trees in the line of the hedge, or within a few feet of it, ought to be abſolutely prohibited, as a heterodox practice. It is amazing, that people ſhould fall into this error, when they ought to know, that there never was a good thorn-hedge with trees in it. And how ſhould it be otherwiſe? an oak, a beech, an elm, grows faſter than a thorn; when ſuffered to grow in the midſt of a thorn-hedge, it ſpreads its roots every where, and robs the thorns of their nouriſhment. Nor is this all; the tree overſhadowing the thorns keeps the ſun and air from them. At the ſame time, no tree takes worſe with being overſhadowed than a thorn.

It is ſcarce neceſſary to mention gaps in a hedge; becauſe they will ſeldom happen where a hedge is trained up as above recommended. But in the ordinary method of training, gaps are frequent, partly by the failure of plants, and partly by the treſpaſſing of cattle. The ordinary method of making up gaps is, to plant ſweet brier where the gap is ſmall, and a crab where it is larger. This method I cannot approve, for an obvious reaſon: a hedge ought never to be compoſed of plants that grow unequally: thoſe that grow faſt overtop and hurt the ſlow growers; and with reſpect in particular to a crab and ſweet brier, neither of them thrive under ſhade. It is a better method to remove all the withered earth in the gap, and to ſubſtitute freſh ſappy mould mixed with ſome lime or dung. Plant upon it a vigorous thorn of equal height with the hedge, which in its growth will equal the thorns it is mixed with. In that view, there ſhould be a nurſery of thorns of all ſizes, even to five feet high, ready to fill up gaps. The beſt ſeaſon for this operation is the month of October. I ſhould have added, that a gap filled with ſweet brier, or a crab lower than the hedge, invites cattle to break through and trample the young plants under foot; to prevent which a paleing on both ſides is far from being ſufficient, unleſs it be raiſed as high as the hedge.

Nothing hitherto has been ſaid about an incloſure for ſheep. To carry a farm to its perfection, every incloſure ought to be made ſo as to keep in ſheep, though not chiefly intended for them; for ſheep ought to be mixed with other cattle in every paſture-field: they eat what others leave, and others eat what they leave. But farmers generally take a humbler flight, and are ſatisfied with one or two incloſures for ſheep. In that view I premiſe, that of all animals ſheep naturally take the wideſt range in feeding; for which reaſon, an incloſure for them ought never to be under fifty or ſixty acres. Where they have ſo much room, any fence will keep them in: where confined to five, ſix, or even ten acres, the moſt awful fence is ſcarce ſufficient. I talk of the common run of ſheep; not of the large Lincolnſhire breed, habituated to incloſures, which have no genius for leaping.

Where ſtones are to be had, the cheapeſt and moſt effectual is the ſtone fence above deſcribed. If a farm cannot afford an incloſure ſo large as that now mentioned, the deepneſs of the ditch ought to be in a reciprocal proportion to the ſize of the incloſure: in a ſmall incloſure, the fence ought at leaſt to be ſix feet high. If the farmer be reduced to a quickſet hedge by want of ſtones, the ſcarſement muſt be eighteen inches broad, in order to receive a paleing between the root of the hedge and lip of the ditch; inclining to the ditch in form of a ſtocade, which will make it the more awful. This will fit the incloſure immediately for ſheep, without waiting the ſlow growth of the

dge. When the paleing fails, the ditch muſt
lined up with ſtones to the height of the
dge, to prevent the ſheep from making a road
the ſide of the ditch to come at the thorns ;
ich would ruin all, for no food is ſo palatable
them as the leaves of thorn. Where ſtones are
rce, two feet of ſtones may do, raiſing the li-
g to the height of the thorns with ſod.

One thing is never to be omitted in a large in-
ſure. Sheep require a ſhelter againſt heat, no
s than againſt cold. The ſtone fence recom-
nded, affords little ſhelter againſt either. There-
e, a ſhelter ought to be made ſomewhere in the
eſt part of the field. Plant ten or twelve rows
Scotch fir or ſpruce fir in a curve, ſemicircular,
eliptical, the concave fronting the ſouth, and

will have the benefit of fine crops of corn by removing ſucceſſively ſheep from one incloſure to another.

A word more before I end, which ſhall be on the gates of incloſures. The poſts upon which the gate is hung, though built of ſtone and lime, is apt to be ſhaken by a heavy gate, and to be torn to pieces by a careleſs driver running the axle of his cart againſt it. But inſtead of building a wall in the line of the incloſure, let it be built perpendicular to it, ſeven or eight feet long, thickeſt in the middle and tapering toward the ends. Such a wall or poſt will be proof againſt any force.

## CHAP. XIII.

## THE PROPER SIZE OF A FARM, AND THE USEFUL ACCOMMODATIONS IT OUGHT TO HAVE.

TO confine a tenant to that quantity of land which can be managed to the beſt purpoſe with the leaſt expence, is the ſureſt means of obtaining an adequate rent without oppreſſion. A farm ought never to contain a leſs quantity of land than ſufficient for a plough; and there is no medium between that quantity, and as much as will give full employment to two. Leſs than ſufficient for a plough, is an evident loſs to the te-

nt, and conſequently to the landlord: the ſer-
nts and cattle muſt at times be idle for want of
rk; or what is worſe, they will work indolent-
and make no progreſs. I have a ſtriking proof
this obſervation. The eſtate of Grange in the
rſe of Falkirk, containing about 360 Scotch
res, paid of rent L. 450. It was poſſeſſed by
fewer than eleven tenants; not one of the
ms ſufficient for a plough, ſeveral of them be-
een twenty and thirty acres. A map was made:
was clearly ſeen, that the eſtate could hold but
tenants; and it luckily happened, that there
re ſix houſes abundantly centrical for theſe te-
nts, without neceſſity of new buildings. The
ing of twenty horſes and ten ſervants, and the
intainance of five tenants and their families

the tenant. The reaſon is, that in an uncultivated country, the adding twenty or thirty acres more is little regarded. I could give many inſtances of a tenant beginning to thrive after being deprived of part of his farm. But it is unneceſſary to give inſtances, for they are known every where.

When one thinks of calculating what quantity of land is ſufficient for a ſingle plough, many circumſtances occur, that make it impracticable to determine the point with any preciſion. The difference between a light and a heavy ſoil, is conſiderable; and no leſs ſo, the nearneſs or diſtance of manure. The mode of cropping is capital: where all the different plants are ſown in ſpring and reaped in autumn, more ploughs are requiſite than when crops are diſperſed through the year, according to the preſent improved mode of culture. I venture only in general to ſay, that in moſt ſoils fifty acres of corn may be commanded by a ſingle plough, provided the crops be diſtributed through the year, to afford time for managing all of them with the ſame men and cattle. But where graſs is neceſſary for keeping the ſoil in heart, a farm ought to be enlarged in proportion to the quantity of graſs required; for there ought always to be as much land in tillage as fully to occupy a plough. If a third part in graſs be ſufficient, the farm ought to conſiſt of ſeventy-five acres: if a half be neceſſary, the farm ought to

be

100 acres ; and if the ſoil be ſo mean as to re-
ire two thirds in graſs, the extent of the farm
ght to be 150 acres. If the reader be curious
out further particulars, I refer him to the ſe-
nth chapter, in which a few examples are gi-
n of the number of acres that in different modes
cropping may be commanded by one plough.
eſe examples will pave the way to computations
rreſponding to other rotations.

I proceed to an intereſting article, which is to
mpare great and ſmall farms in point of utility.
all a ſmall farm what employs but a ſingle
ugh ; and a ſmaller there ought not to be. A
ddling farm is what requires two ploughs ; and
atever requires a greater number, I call a great
n. Theſe different farms I ſhall conſider with

ſaying no more, but that it is beneficial to have a large fund. The proper queſtion is, Whether with reſpect to farmers in general, it is not a convenience to have the choice of ſmall or great farms, according to their ſtock? In that view, ſmall farms are undoubtedly advantageous to thoſe who want to be farmers; becauſe in Scotland, at leaſt, the number is much greater of thoſe who can ſtock a ſmall farm, than of thoſe who can go farther. It may poſſibly be objected, that there is an inconvenience in a ſmall farm where two horſes only are neceſſary for a plough, in reſpect that two horſes make but a ſlow progreſs in carrying corn or dung. To this objection there is a ready anſwer: two horſes in two ſingle carts will make as much expedition in carrying out the dung, or carrying in the corn of a ſmall farm, as double that number will make in a middling farm, where the dung and corn are double in quantity. I ſay further, that if two horſes be not ſufficient, the defect may be readily ſupplied by two draught oxen, which add very little to the expence of the farm. Theſe at four years of age may be purchaſed for L. 10. They will give at ſeven L. 15; and this profit, with no more work than ſufficient to give them a ſtomach, will balance their ſummer-food of green clover. Their winter-food of ſtraw cannot enter into the computation, being the very beſt way of converting ſtraw into dung. Here there is a great convenience. Where a field, by drought or otherwiſe, is rendered too ſtiff for a pair, the oxen may be yoked in the plough with the horſes. In ground leſs ſtiff, the farmer has a choice of two oxen and a horſe, of two horſes alone, or of two oxen. Where ploughing happens to be retarded by bad weather, two ploughs may be employed, which is a ſignal convenience. Ploughing alſo and harrowing may go on at the ſame time; and the farmer has it always in his power to yoke two double carts. Even in carſe-ſoil this plan will anſwer; as there is ſeldom occaſion to employ the oxen but where the ground is ſufficiently dry for them.

With reſpect to the public, ſmall farms are undoubtedly the moſt advantageous. The number of ſervants, it is true, muſt be in proportion to the ſize of the farm: but in a middling farm there is but one tenant; whereas in two ſmall farms of no greater extent, there are two. And the difference is ſtill greater in large farms. This is a capital circumſtance. The children of tenants are taught to read and write; and in general are better educated than children of day-labourers, which qualifies them better for being artiſts and manufacturers. They are alſo commonly more numerous, being better nouriſhed during nonage, and better preſerved from diſeaſes. Small farms accordingly are not only favourable to population, but to the moſt uſeful population. I would not therefore indulge willingly any farm beyond a middle ſize. And to check thoſe of a larger ſize, I am clear for a tax of L. 3 or L. 4 yearly upon every farm that requires three ploughs; and ſo on according to the number. I except proprietors, who ought to be encouraged to improve their eſtates: let them employ as many ploughs as they find convenient, and not be ſubjected to any tax. If any undertaker be willing to lay out a large ſum of money upon farming, the profit of a long leaſe will enable him to pay the tax. This tax at the ſame time may be ſo contrived, as to anſwer a valuable purpoſe, that of exciting farmers to uſe oxen inſtead of horſes; which will be done by exempting oxen-ploughs from the tax. And the undertaker mentioned will be relieved from the tax altogether, if he employ ſuch ploughs only.

THE ſize of a farm being adjuſted, next in order are its accommodations. The firſt accommodation I ſhall mention is, an acre planted with trees proper for the farm; fir in particular and aſh. The worſt ſoil will anſwer the former, and moiſt ſoil the latter. Theſe are at hand for paleing and other purpoſes; and without ſuch a convenience a tenant's hands are in a meaſure bound up.

Another accommodation follows. However well adjuſted the ſize of a farm may be to the ſtrength employed upon it; yet to have a farm in perfection there ought always to be ſome bywork, about which the ſervants and horſes may be employed, when the ordinary culture of the farm does not require them. There is a great difference between good and bad weather, with reſpect to expedition. The farmer muſt provide againſt the latter, by ſufficiency of men and horſes, which in the former have not full employment. Therefore, to provide againſt want of work, there ought to be a reſource, ſuch as may be taken up or laid down as occaſion offers. The carrying lime to a farm, or marl, or dung from a neighbouring town, are excellent reſources.

The chief accommodation of all is, a fruitful kitchen-garden. Formerly, oat-meal was the only food of our labouring people; and when at five or ſix ſhillings per boll, there could not be cheaper food. A kitchen-garden was at that time a ſort of luxury, and our ſimple peaſants had no notion of luxury. By a great advance in the price of oats and oat-meal, a kitchen-garden has become an article of economy; and yet ſcarce more attended to than formerly. Well dreſſed and croped, it will afford half maintenance to a family; and will not coſt the half of oat-meal. But the ignorant are ſlaves to cuſtom; and no value is put on a kitchen-garden at preſent, becauſe it was of no value thirty years ago.

The extent of this garden depends on the manner of croping the farm. Where red clover is one of the crops in the rotation, a kitchen-garden need not exceed two or three acres. Where red clover enters not into the rotation, ſix acres are the ſmalleſt quantity even for a ſingle plough; becauſe it muſt yield food both for man and beaſt. Take the following rotation, which at the ſame time is capable of greater variety in a kitchen-garden of greater extent than ſix acres. Two acres are neceſſary for ſummer-food to the farm-cattle, cows, &c. Two acres more will be uſefully employed in cabbage, colewort, turnip, carrot, potatoes, leeks, onions, turky-beans, white peaſe, and other kitchen ſtuff, for food to the family. The remaining two acres muſt be ſown with barley and red clover. To give directions for the culture of the vegetables intended for the family uſe, would be a treatiſe on the kitchen-garden. I ſhall only ſlightly obſerve, that the early cabbage, termed *May cabbage*, may be ſet the end of February, or as ſoon after as the ſeaſon anſwers; and will be ready for eating in May and June. Scotch cabbage ought to be ſet in March; and a few ſet in June will be ready for eating next ſpring. The ſeaſon for ſowing carrots, onions, and leeks, is the ſame with that of oats. Onions require a rich ſoil; and if that be wanting, leeks may ſupply their place. Potatoes ought never to be neglected: they make a hearty food, and the cheapeſt of all: upon which account, as many ought to be raiſed as will ſerve the family the year round. Turnip is proper for cows after calving; and to turnip may be added what cabbage or colewort are ſaved from the family-uſe. This ſucculent food will produce plenty of milk for rearing calves, an article little regarded in Scotland. Careful culture may afford ſome reſidue for feeding an old cow or ox during winter; which in ſpring may be ſold to great advantage, inſtead of being ſold the beginning of winter for a trifle.

A kitchen-garden is always ſurrounded with trees, from the notion that it requires ſhelter. Young plants require ſhelter; but not thoſe that are advanced in growth. Plants long ſheltered in a kitchen-garden, are too tender for the field. And for evidence that they proſper greatly by a free circulation of air, they riſe in the field to a much greater ſize than in a ſheltered garden. I need ſcarce add, that the kitchen-garden ought to be as near the farm-houſes as may be, in order to ſave the carriage of dung to it, and of green food to the cattle.

There is one accommodation of a farm I reliſh greatly, becauſe it has a charitable view. Why not reſerve work for ſuperannuated labourers that requires little ſtrength, cutting down weeds for example, weeding hedges, filling up ruts in a road with ſmall ſtones, tending cattle in the houſe during winter, gathering dung, and ſuch like? Half-pay would help them to live; and gentle work would keep them in ſpirits, preventing a langour that ſits down heavy on the induſtrious, when reduced to idleneſs.

It will not be an unneceſſary addition, to examine what ſort of farm is proper for a wright, a ſmith, a maſon, or a weaver. A mechanic, it is true, makes more by his art than by huſbandry-work: but if he have no farm to depend on, he muſt go far to market for proviſions, and will be ill provided after all. At any rate, he muſt have a ſmall farm for maintaining a horſe and two cows: the former for carrying timber, iron, coals, &c.; the latter for milk.

The quantity of land neceſſary for ſupplying all his wants, cannot be leſs than ſix acres where the ſoil is good, and more where it is indifferent. To prevent the expence of winter-herding, the field muſt be incloſed; but diviſions are not neceſſary. It ought to be cropped as follows: a third part in red clover, with a ſmall proportion of ryegraſs to thicken the crop: a third part in oats, turnip, and potatoes; the remaining third in barley and lint; the lint to be ſown where the potatoes grew the former year.

To ſave the expence and trouble of carrying clover to the cattle in the houſe, and of carrying dung to the field, let a moveable trough be provided twelve feet long, the ſide ſpars eighteen inches high. Bind the horſe and two cows to ſtakes at the ſide of the trough, and let them have plenty of clover. To defend them from heat and from flies, cover them with a ſhed, the roof of which may be an old ſail, or any other coarſe cloth, ſupported upon wooden pillars. The trough and ſhed moved from place to place, will ſpread the dung equally, and ſave carriage of the clover. The wife or maid-ſervant, when ſhe milks the cows, fills the trough with clover; and the richneſs of the food will make it proper to milk them thrice a-day. The oat and barley crops need no inſtruction. The turnip is an excellent food for the cows in ſpring after calving; and there ought to be as many potatoes as to ſerve the family the year round. As for the flax, all the ground that can poſſibly be ſpared ought to be cropped with it; becauſe every perſon of the family may be profitably employed, upon dreſſing it in winter-evenings when no other work is on hand, and when otherwiſe they would be idle.

The oat and barley ſtraw, with what clover has been ſaved, will ſuffice for winter-food to the horſe and two cows. And the dung that can be thus gathered, will ſuffice for the turnip and potato crops. As the lint ſucceeds the potato-crop, it will require no dung.

The great loſs of a ſmall farm that cannot maintain a plough is, that the land is never dreſſed in ſeaſon. No neighbouring farmer will part with his plough, even for hire, till his own work be finiſhed. This loſs may be prevented by placing two mechanics together. If good-natured and ſociable,

ciable, they will go on pleaſantly with their two horſes in a plough, and will have always the ſeaſon at command for ploughing. The great advantage of ſuch a plan, both for frugality and profit, will ſubdue even bad humour, and make the neighbours go on cordially together.

With reſpect to a weaver, ſome Iriſh pamphlets declare againſt his having any land to cultivate; for the reaſon above mentioned, that there is more profit by weaving than by farming. But this reaſon is not ſatisfactory. Weaving, a ſedentary occupation, requires at times field-labour for ſake of health; and it is not conſiſtent with humanity, that profit only ſhould be the object, without regard to health or comfort. It may at the ſame time be doubted, whether it will not be profitable to preſerve a weaver a few years longer in health and vigour. Theſe conſiderations muſt weigh, even where there is a market at hand for proviſions, which is a rare caſe in Scotland. But as a weaver has no occaſion for a horſe, four acres are ſufficient for his purpoſe, to be cropped in three diviſions as above mentioned.

## CHAP. XIV.

## WHAT A CORN-FARM OUGHT TO YIELD IN RENT.

IN leaſing a farm, it appears an equitable bargain, that after a moderate allowance to the tenant for his ſkill and induſtry, and after deducting the expence of management, the remainder of the product, or its value in money, ought to go to the landlord as rent. In order then to aſcertain the rent of a farm, the particulars muſt be ſtated with which the crop ought to be burdened. This will be found not an eaſy taſk: but the following conſiderations, will pave the way to it.

The labour beſtowed on dreſſing land for a crop, is evidently a burden on the crop. But by what rule is that labour to be eſtimated? If the labour of every man and every horſe were to be ſtated at ſo much per day, it would encourage the tenant to loiter, inſtead of being diligent: the crop would be exhauſted by the expence, and nothing be left to the landlord. The nature of the agreement between landlord and tenant, ſuggeſts a more proper method of ſtating the account. The tenant furniſhes the ſervants and cattle; but as they labour for the landlord, the expence muſt be defrayed by him. The article for ſervants hired by the year or half-year, is ſimple: their wages muſt be ſtated as a burden on the product. The article for the labouring cattle is more intricate. Were the price of every beaſt to be ſtated, bought by the tenant during his leaſe in place of thoſe that fail, it would occaſion much trouble, and open a door to fraud. The only practicable way, is to allow the tenant a yearly ſum, for the uſe of his cattle, and for upholding them. For the former he cannot be offered leſs than five *per cent.*; becauſe that ſum he would be intitled to, upon converting his ſtocking into money. As to the latter, cattle are a periſhable commodity; and every farmer reckons upon the expence of renewing his ſtock every ten years. To anſwer this expence, the tenant ought to be allowed yearly ten *per cent.* of the value of his ſtock; which ſum in ten years amounts to no more but that value. But this is not all: a poor tenant who commonly has nothing to depend on but his ſtock, muſt be preſerved from riſk. His ſtock of labouring cattle ought to be inſured to him; and the inſurance cannot well be yearly under four or five *per cent.* Upon the whole, for furniſhing labouring cattle, and upholding them, he is well intitled to twenty *per cent.* yearly of their value; and this ſum is another deduction from the yearly product.

In this account muſt alſo be comprehended the farm-inſtruments, ploughs, carts, &c.; for theſe muſt be renewed from time to time, ſtill more frequently than the labouring cattle. But cows

d calves, and other particulars that are kept for
e benefit of the tenant ſolely, are not to be com-
ehended ; becauſe they produce nothing to the
ndlord.

What the tenant himſelf ought to be allowed
t of the product, for beſtowing his whole time
on the ſervice of his landlord, is far from being
vious. A tenant is in a higher claſs than a
ed ſervant or day-labourer; and may well rank
th a ſhopkeeper in a town, or a manufacturer
a village. To judge by that compariſon, his
owance ought not to be under L. 36 or L. 40
arly; ſuppoſing the corn, one grain with an-
ner, to give ten ſhillings per boll, which is the
ce to be underſtood in every branch of this in-
iry. Nor is this a high allowance,

places of Scotland, there are two, three, ſometimes four, tenants about a ſingle plough, in a poor farm that perhaps does not pay L. 5 yearly. Were it not the ambition of being tenants, better it would be for them to labour at 8 d. per day. By this ambitious propenſity in my countrymen, much leſs is made by farming, than the tenant is intitled to from the nature of his profeſſion. It is believed, that thoſe who are confined to one plough, do not at a medium clear more than L. 20 yearly; which exceeds not the wages of an ordinary mechanic, and is not far above what a day-labourer earns. The landlord indeed profits by this propenſity; becauſe the leſs that is drawn of the product by the tenant, the more is left to the landlord: but the profit is only temporary; for the landlord ſuffers in the main, by being obliged to lower his rent for the encouragement of more vigorous tenants.

However this be, the rent of ſmall farms determines the rent of every farm; for a landlord, who draws of rent L. 80 from two ſmall tenants, will not eaſily be perſuaded to ſet both farms to one tenant for L. 75. But it falls out luckily here, that there is encouragement to great tenants, without encroaching on the landlord's intereſt. A leaſe of ſix ſmall farms will intitle him to the ſhare of each of the former poſſeſſors, which is L. 120, without lowering the landlord's rent one farthing.

I need ſcarce mention, that the expence of ſeed is a burden upon the annual product; as alſo the expence of ſhearing, threſhing, &c. as far as theſe articles are performed by ſtrangers hired for that purpoſe. And to ſave a vague account, a lump ſum ought to be ſtated for theſe particulars.

It falls in here to be conſidered, whether the nature of the ſoil, good or bad, makes any difference upon the tenant's ſhare of the product. One thing is evident, that if he be not enabled to live by his farm, he muſt take himſelf to ſome other occupation; and to live with any degree of comfort, leſs he cannot have than L. 20 yearly, however mean the ſoil may be. On the other hand, he is intitled to no benefit from the fertility of the ſoil; becauſe it adds neither to the expence of culture nor of living. Fertility is a quality of land; and a ſubject belongs to the proprietor with all its qualities. As fertility depends not on the tenant's ſkill nor induſtry, he is intitled to no benefit from it.

For the ſame reaſon, any ſaving in the expence of culture ought to benefit the landlord only; as where, by the conſtruction of a plough, two draught-horſes are ſufficient inſtead of three or four: or where oxen are uſed inſtead of horſes: the gain of the tenant is not leſſened by ſuch ſavings.

On the other hand, where a tenant, by ſuperior ſkill or extreme diligence, raiſes on an acre a buſhel more than uſual, the profit ought to be his own: it is owing to himſelf, not to the fertility of the ſoil.

Laſtly, Suppoſe a lime-quarry, or a bed of ſhell-marl, to be diſcovered within a farm, or near it, it ought to be conſidered as an article for the landlord, in giving a new leaſe. The profit ought to be his, ſtating only an allowance to the tenant for the expence he lays out upon the manure. It is in effect adding to the fertility of the ſoil; which, for the reaſon above given, ought to benefit the landlord only.

Let us illuſtrate theſe general views, by ſtating an account of particulars. Take a farm of ſixty acres; which being partly in paſture, may be managed by a ſingle plough with four horſes. I begin with computing the rent of ſuch a farm, where the product in corn and graſs is at a medium equal to the value of five bolls per acre, or 50 s. amounting upon the whole farm to L. 150. Add the profit of ten winterers fed with ſtraw, which may be ſtated at L. 5. The whole ſum drawn out of the land is L. 155; from which is to be deducted the tenant's ſhare, and every other article of expence: the balance is the landlord's rent. Let us enter into the ſeveral articles of deduction.

Firſt, The ſeed, which ſhall be ſtated at L. 20 only, as a part is in paſture.

Second, The fifth part, or 20 *per cent.* of the value of the labouring ſtock, which by computation is L. 74, 10 s. *. *Inde*, L. 14, 18 s.

Third, The farmer's ſhare L. 20.

Fourth, As the farmer himſelf may ſtand for one ſervant, I ſtate only the wages and maintenance of another L. 12.

Fifth, The maintenance of the four horſes L. 24.

Laſtly, The money paid for ſhearing, threſhing, &c. lumped at L. 8.

Theſe deductions amount to L. 98, 18 s. But if the land can be managed with two horſes, the deductions will amount to L. 82, 2 s. only, beſide ſaving a driver.

N. B. Reparation of houſes, and other ſmall articles, are too minute to enter into a general view. But if any article be thought too high, they may ſerve to balance what is ſubtracted from that article.

---

| | | | |
|---|---|---|---|
| * Four horſes - - | L. 48 | 0 | 0 |
| Horſe-furniture - - | 2 | 0 | 0 |
| Two ploughs - - - - | 2 | 0 | 0 |
| Carts and wains - - - | 14 | 0 | 0 |
| Harrows and brake - - | 2 | 0 | 0 |
| Roller - - - | 1 | 0 | 0 |
| Fanner - - - | 2 | 0 | 0 |
| Forks, ſpades, ſcythes, rakes, wheelbarrows, hooks, &c. - - | 1 | 10 | 0 |
| Twelve harden ſacks - - | 2 | 0 | 0 |
| | L. 74 | 10 | 0 |

The account then ſtands thus.

| | | | |
|---|---|---|---|
| On the one hand the product - | L. 155 | 0 | 0 |
| Subtract on the other hand - | 98 | 18 | 0 |
| | 56 | 2 | 0 |

This balance of L. 56, 2 s. is the landlord's rent.

| | | | |
|---|---|---|---|
| Suppoſing the product to be but four bolls per acre, or 40 s.; *inde* the product | L. 125 | 0 | 0 |
| Subtract as before - - - | 98 | 18 | 0 |
| Rent | L. 26 | 2 | 0 |

| | | | |
|---|---|---|---|
| Suppoſing the product to be 3½ bolls per acre, or 35 s.; *inde* - - | L. 110 | 0 | 0 |
| Subtract - - | 98 | 18 | 0 |
| Rent | L. 11 | 2 | 0 |

Here an unexpected diſcovery is made of very great importance in farming; which is, that a farm yielding no more but an average of 3½ bolls per acre, had better be wholly ſet for paſture. For ſuppoſing it in that ſhape to yield no more but 5 s. per acre, which is L. 15 for the whole, the clear profit is greater than when the farm is in corn; and the landlord draws more rent: he draws the whole L. 15, as land ſet in paſture is not burdened with any expence. This diſcovery may be of uſe to many a poor tenant, who labours and toils at the plough from year to year, to his own loſs. If his farm produce not more than 3½ bolls per acre, better abandon the plough, turn his farm into paſture, and ſit idle.

But if a tenant can reduce his labouring cattle to two horſes or two oxen, the ſaving will be ſo conſiderable as to make it his own intereſt as well as that of the landlord to continue his corn-crops. The ſaving amounts to L. 16, 16 s. yearly, not to mention the driver; which throws the balance againſt paſture no leſs than L. 12, 18 s. ſuppoſing the farm in paſture to yield but 5 s. per acre. This ſaving benefits the tenant during his leaſe, and benefits the landlord in giving a new leaſe. But ſuppoſing the product to be but 3 bolls per acre, the balance turns clearly for paſture, after every ſaving that can be made when ſuch a farm is in corn.

At the ſame time, however fertile the ſoil may be, the man who takes in leaſe a made farm, cannot expect more but to live comfortably. If his heart be ſet on wealth, it is not to be found but in land recently broken up from the ſtate of nature, where there is ſcope for great and laſting improvements.

This ſpeculation ought to be a ruling motive with every gentleman of a land-eſtate, to encourage improvements with all his might. The expence of culture is not leſs in a mean ſoil than in the moſt fertile; and we now ſee, that the expence of the former cuts ſo deep into the corn-product, as to leave little or nothing to the landlord. In our corn-counties, it is not difficult, not extremely expenſive, to make the land carry two or three buſhels per acre more than the ordinary product; the value of which goes entirely to the landlord as rent.

Upon a review, the only doubtful article is the 5 *per cent.* ſtated for enſuring the tenant's labouring cattle. It appears to me, that a yearly ſum preciſely equivalent to the chance of loſing cattle, is not ſufficient; for if the chance go againſt the poor tenant, he is undone. Something for inſurance he ought to have; more or leſs is arbitrary. But ſuppoſing it to be 3 *per cent.* or 2 only, it will be eaſy to frame the computation upon that ſuppoſition.

# PART II.

## THEORY of AGRICULTURE.

THE operations of men can be eaſily traced: they are confined to the ſurface of bodies. The operations of nature, go-
g far out of ſight, reach even elementary par-
les. In explaining therefore natural effects, we
ght to reſt ſatisfied with the immediate cauſes,
ving the more remote to ſuperior beings. In
der to unfold the theory of agriculture, the na-

vances, eſpecially in Britain; and there are rules founded on experience, that ſeldom miſlead when applied by a ſagacious farmer. In theory, the deepeſt penetration preſerves not writers from wide differences. In practice, the ignorant only differ: ſagacious farmers generally agree; giving allowance only for varieties in ſoil and climate.

But admitting experience to be our only ſure guide, theory however ought not to be rejected, even by a practical farmer. Man is made for knowledge; and he has a natural curioſity to learn the reaſon of every thing. Why not indulge an appetite, that will amuſe, and may bring forth inſtruction? In dipping into theory, a complete ſyſtem is far from my thoughts, and far above my reach. I venture only to ſelect a few particulars, that have an immediate influence on practice. Theſe will be underſtood by every gentleman who joins reading to experience; and in doubtful caſes may help to direct his operations. I give warning before hand, that I pretend to no demonſtration. However poſitively I may happen to expreſs myſelf in the glow of compoſition, my beſt arguments are but conjectural. Thoſe that are here diſplayed appear to me highly probable; and if they appear ſo to the reader, I can have no farther wiſh.

The ſubjects handled in this part of my work are divided into three chapters. In the firſt are contained ſome preliminary obſervations that have

an immediate influence on practice. In the
cond are handled the food of plants, and fe
lity of ſoils. And the third is upon the means
fertilizing ſoils.

## CHAPTER I.

## PRELIMINARY OBSERVATIONS.

TO be an expert farmer, it is not neceſſary t
a gentleman be a profound chymiſt. Th
are however certain chymical principles relative
agriculture, that no farmer of education ought
be ignorant of. Such as appear the moſt ne
ſary ſhall be here ſtated, beginning with elec

tendency has a reſemblance to choice in voluntary agents, it is termed *elective attraction.*

The power of gravity extends as far as matter exiſts. Elective attraction, on the contrary, is confined within a very narrow ſpace: it operates not but between bodies in contact, or approaching nearly to it.

Even in the largeſt bodies, ſuch as the ſun and planets, every particle of matter operates by its power of gravity. But elective attraction has no ſenſible effect between large bodies, no particle operating but thoſe in contact, or near it. It has no ſenſible effect therefore but between bodies that mix together. The attraction of gravity between two bodies is in the direct proportion to the quantity of their matter; elective attraction is in the inverſe proportion; which in plain language is ſaying, that the leſs bodies are, the greater is their elective attraction. Between large bodies accordingly, elective attraction in oppoſition to gravity is as nothing: between very ſmall bodies in contact, or near it, it is far ſuperior to gravity.

The power of gravity in each particle of matter correſponds to the quantity of matter in the univerſe: double that quantity, and you double the power of gravity in every particle; annihilate the half, and the power of gravity is reduced to the half. Elective attraction, on the contrary, is invariable. It can hold but a certain quantity of

correſponding

eſponding matter: bring more within its
re of attraction, it has no effect. Thus, wa-
will hold ſalt till it be ſaturated; or, in other
ds, till every particle of the water be in con-
with a particle of ſalt. Add more ſalt: it is
attracted, but falls to the bottom of the veſſel.
ſame is obſervable in clay ſaturated with wa-
what water is added falls to the bottom.
lective attraction between ſome correſponding
ies, is more vigorous than between others.
ds and alkalis attract each other violently, and
intimately. Such is the caſe alſo of ſalt and
er: ſalt is ſo thoroughly diſſolved in water as
aniſh out of ſight, leaving the water tranſ-
nt as before *. There is an elective attrac-
between air and water: neither of them in

lective attraction prevails over gravity, which has not power to ſeparate the heavier body from the lighter. Water and clay attract each other, but with leſs vigour: powdered clay is ſuſpended in water; but the elective attraction is not ſo ſtrong as to diſſolve the clay: it continues viſible in the mixture, and makes the water turbid. Their mutual attraction yields by degrees to the repeated impulſes of gravity: the clay ſubſides, leaving the water tranſparent as originally. But each particle of clay draws along with it the particles of water with which it is in contact. And accordingly when the water is poured off, the clay remains moiſt and ſoft.

Both air and clay attract water; and when they act in oppoſition, it is of importance to know which of them prevails. Where clay is ſo wet as that many particles of the water are not reached by the attraction of the clay, ſuch looſe particles are attracted by the air without oppoſition. Even particles of water, barely within the ſphere of attraction of the clay, are drawn up by the ſuperior attraction of dry air. But the air muſt be both hot and dry, to carry off water that is in actual contact with the clay. This I conjecture never happens in pure clay, unleſs the heat be intenſe.

All ſorts of earth do not attract water equally: the attraction of clay is the ſtrongeſt, of ſand the weakeſt. Between theſe extremes, ſoils vary in every degree with reſpect to their power of attracting and holding water. Even clays differ. Some clays attract water vigorouſly, others leſs. This is manifeſted from the time that is taken in drying; as the clay that attracts the moſt vigorouſly will be the lateſt of parting with its water. I witneſſed an experiment of different clays put in ſhallow veſſels, and ſoaked with water. They differed in the times of drying at leaſt a fortnight. I take it for granted, that the clay which retains its water the longeſt, will turn the hardeſt after it is dry; for both effects depend on the force of the elective attraction.

It is laid down above, that elective attraction is the greateſt between the ſmalleſt bodies. Hence an important leſſon in agriculture, which may be juſtly eſteemed the corner-ſtone of the fabric, that the more pulverized clay is, the more water it will hold. A lump of dry clay immerſed in water, carries none away but what is attracted by the ſurface-particles. Pulverize this lump, and give free admiſſion to the water; let it be divided into a million of parts or into ten million: each particle however minute will hold a certain proportion of water; and this proceſs may be carried on as far as clay and water can be divided by the hand of man *. Now as earth ſerves only to

---

* Mr Evelyn dug a deep hole in the ground, reduced the earth to powder, and put it back into the hole. After a time, the powdered earth was found moiſt to the bottom, the ground round it remaining hard and dry.

retain moiſture, and to furniſh it gradually to its plants, the chief object of huſbandry is, by ploughing and harrowing to pulverize clay, and every other ſoil that requires it. Clay, it is true, is diviſible into ſo many parts as readily to unite with water into a very hard maſs; witneſs carſe-clay, of which afterward. But there is no danger of ſuch exceſs in common clay, which is compoſed of particles more groſs than thoſe of carſe-clay. In common clay, there is no other limit to beneficial pulveration, but the expence of the work.

There is alſo obſervable an elective attraction between earth and air. Much air is found in earth, becauſe gravity concurs with the elective attraction to bring down air. But very little earth is found in air; becauſe in that caſe gravity counteracts the elective attraction.

A plant attracts air and water, and is attracted by them. The latter attraction is without effect, becauſe plants are fixed to a place. The former is clearly diſplayed by Dr Hales in his ſtatical eſſays, containing the beſt conducted experiments that are known, next to thoſe of Sir Iſaac Newton upon light and colours. There is not the ſlighteſt evidence, that plants attract any dry matter, however pulverized. Set the moſt healthy vegetable in dried earth, or in duſt gathered from the highway: it dies, and the earth remains as weighty as before. It is clear then, that a plant can receive no nouriſhment but what is conveyed to it

y air or water ; and conſequently that nothing
n ſerve as its nouriſhment but what is ſoluble in
eſe elements. Clay is not ſoluble even in wa-
r : it is eaſily ſeparated from water by the force
f gravity ; and its particles are probably too
roſs to enter with water into the mouths of a
lant.

Black bodies attract and abſorb rays of the ſun.
black wall facing the ſun, is hotter even to the
uch than a wall of any other colour ; and hence
e practice of blacking fruit-walls. Soil made
ack by high culture, attracts and abſorbs rays
f the ſun in plenty ; and turns remarkably hotter
an ſoil of any other colour.

That there is a mutual attraction between par-
cles of water, appears from the globules it

evaporation is at an end, becauſe water is attracted more ſtrongly by clay, than by air in its ordinary ſtate; and the maſs hardens by degrees. A green turf from a moiſt ſoil, falls to pieces in handling. Let it lie a few days to dry, it becomes tough and firm. The like happens in a mixture of quick lime, ſand, and water. The water continues for a time fluid; and the maſs is ſoft and ductile. Upon evaporation of the ſuperfluous moiſture, the elective attraction operates; and the maſs turns hard like a ſtone. A mixture of clay and ſand moiſtened with water, continues long ſoft; but in time turns exceedingly hard: the pier of Eyemouth in Berwickſhire is built of a plumcake ſtone, compoſed of pebbles, clay, and ſand, cemented with water; yet no ſtone is harder, nor leſs affected with the ſea-air. Plaiſter of Paris is compoſed of gypſum and water; which are mixed together to a certain conſiſtence; and the maſs, ſtill fluid, is poured into a mould: in a few minutes it acquires a ſtony hardneſs. A compoſition of that kind is uſed for bridges in the iſland Minorca: no ſooner is one ſtone of the arch joined to another, than it bears a man to add a third. The cement here operates almoſt inſtantaneouſly: water operates ſlower in hardening clay; and ſtill ſlower in hardening a mixture of lime and ſand.

Theſe differences depend probably on the more or leſs vigour of the elective attraction. As the ſuperfluous moiſture evaporates, the correſponding bodies approach nearer and nearer to each other, and at laſt unite in one maſs. This operation is ſlow in proportion to the vigour of the elective attraction; and the ſlower the operation is, the maſs becomes the harder. Some ſorts of clay attract water more vigorouſly than others; and when the ſuperfluous moiſture is exhaled; which is done very ſlowly, the maſs turns hard in proportion. Carſe-clay affords a good inſtance. It is compoſed of the fineſt parts of natural clay, waſhed off by running water: it is depoſited in flat ground where the water ſtagnates; and is accumulated by degrees till the ground riſe above the ſtream. Carſe-lands are generally near the ſea, and the reflux of the tide contributes to the effect. By the minuteneſs of its parts, carſe-clay mixes ſo intimately with water as to give the elective attraction its utmoſt efficacy. Thus carſe-clay, which is extremely wet in winter, becomes ſo hard in a droughty ſpring as to yield but a very ſcanty crop, unleſs the ſummer be moiſt. In a dry ſummer, fiſſures are every where ſeen in it, ſome of them ſo wide as to admit a man's hand, Common clay, compoſed of groſſer parts, never hardens ſo much. Hence it is, that of all crops beans thrive the beſt in carſe-clay: the tap root puſhes vigorouſly into the hard ſoil; and finds more water locked up there than in common clay *.

This tendency to hardneſs in clay-ſoil, is a great obſtruction to fertility; and to counteract that bad quality, I know no means more effectual than frequent ploughing and harrowing. In that view partly, the harrows above deſcribed were invented: they divide the ſoil into minute parts: every part holds a particle of water ready for the nouriſhment of plants; and the ſoil at the ſame time is kept open, inviting the roots to extend themſelves in all directions.

The time that water takes to harden clay, will explain ſeveral articles. I mention firſt an article of importance, which is the different effects of ploughing clay wet or dry. The running a plough through clay ſoaked in water, produces no change. Upon evaporation of the looſer parts

---

* The clay in the Carſe of Gowry, of Falkirk, and of Stirling, is much of the ſame nature. When dry, it is white, leſs weighty than common clay, pure without ſand, and divides into very minute parts. The laſt-mentioned quality, which gives elective attraction its greateſt efficacy, makes it cake at the ſurface when ſtirred before winter. It makes it alſo in drought unite into very hard clods, harder than thoſe of common clay, compoſed of groſſer parts. As all clays hold water in proportion to the minuteneſs of their parts, froſt acts more vigorouſly upon carſe-clay than upon the ordinary ſort; becauſe froſt acts upon bodies in proportion to the quantity of water in them.

of the water, the vacuities left render the ſoft maſs compreſſible. To compreſs it in that ſtate would have the effect to keep in the remainder of the looſe water from evaporating, at the ſame time give the elective attraction its ſtrongeſt effect, and accelerate the hardening contrary to the very intention of ploughing. Let not the plough be applied till the air has performed its part by drawing off every particle of water that is not in contact with the clay. Nick that minute for applying the plough: the clay ſtill ſoft is eaſily divided: a new ſurface is laid open to the air: evaporation is renewed; and by every ploughing and harrowing the ſoil turns drier, and at the ſame time is preſerved free and open.

The next article I ſhall mention, is the making brick. Where air and water are brought into contact by elective attraction, the proceſs is completed: for they never harden into a ſolid body. But after clay and water are brought into contact, the proceſs goes on till they be firmly united. In the commencement of that proceſs, the air may be rendered ſo hot and dry, as to overcome the elective attraction, and ſuck up the whole moiſture, leaving the clay dry with little or no coheſion. Wet clay put into a hot fire, does not harden, but falls into a burnt powder. The ſuperfluous moiſture muſt be evaporated, and the coheſion be conſiderably advanced, before it can be hardened into a brick by fire. In that condition,

tion, the elective attraction prevails over the hotteſt air. Form dough into a thin cake, and lay it upon a plate of iron over a fire: the moiſture ſuddenly evaporates; and no more is left but what is barely ſufficient to keep the parts ſlightly together. Give the elective attraction time to operate: the cake turns hard like a brick.

Nature operates by elective repulſion as well as by elective attraction; but as agriculture ſeems to depend little upon the former, I ſhall ſay but a word upon it. There is an elective repulſion in the particles of air, which gives them a tendency to recede from each other; and this operation is greatly invigorated by heat. Heat therefore pulverizes the ſoil by rarifying the air contained in it, which moves the particles of earth out of their place. Froſt has a ſimilar effect, by rarifying the water contained in a ſoil. Black, as obſerved above, attracts and abſorbs rays of the ſun; and therefore black is the beſt colour of ſoil. The more parts clay or loam is divided into, the blacker it is. Whatever be the colour of the ſoil where potatoes are ſet, it is rendered black by that crop. A potato-crop is a powerful pulverizer: the bulbous roots ſwelling without intermiſſion, keep the ſurrounding earth in conſtant motion, and divide more effectually than a plough or a harrow. White repels the rays of the ſun; and upon that account is a bad colour for ſoil. Pulverizing by dunging, ploughing, and harrowing, is a ſure means to

nvert white ſoil into black; which is an addi-
nal motive for being diligent in theſe opera-
ns.

## PLANTS HAVE A FACULTY TO ACCOMMODATE THEMSELVES TO THEIR SITUATION.

ALL trees are provided by nature with a tap-
ot, fit for piercing the hardeſt ſoil; and a tree
owing in clay exerts great energy on that root.
leſſens in vigour and ſize where a tree grows in
am; and lateral roots prevail more, which are
ead all around for procuring food. In very
ht ſoil, the tap-root is very ſmall; and a tree
owing in water has many roots, but not the

tution accommodated to that ſoil; and its nature is ſo far altered, as in a meaſure to diſqualify it for being tranſplanted into a looſe ſoil. Take a vegetable that has been reared in water, and plant it in a ſoil even the moſt proper for it by nature: it will infallibly die. In general, plants reared in water will not grow in earth; and plants reared in earth will not grow in water. Hence it is, that where water ſtagnates ten or twelve inches under the ſurface, the plants reared in that ground turn ſickly when their roots reach the water. Yet theſe plants would have flouriſhed in pure water, had they been accuſtomed to it early.

But may not a plant acquire a conſtitution, fitting it for growing partly in earth partly in water? Trees grow vigorouſly on the brink of a river, where ſome of the roots muſt be in water. At the ſeat of Mr Burnet of Kemnay, ten miles from Aberdeen, a kitchen-garden, a flower-garden, a wilderneſs of trees indigenous and exotic, are all in a peat-moſs, where water ſtagnates from one foot to two under the ſurface.

The ſame faculty is exerted to remedy an inconvenient ſituation. A tree that grows without ſhelter, reſiſts wind by the length of its roots: the roots of the ſame tree, are commonly much ſhorter in a ſheltered place. In the Leeward iſlands, the eaſt wind is almoſt conſtant; and the trees there, extend their roots much farther to

ıt quarter, than to any other. A tree overtop-
by neighbouring trees, directs its courſe to a
pace that is free; and then mounts up perpen-
ularly according to its nature. Set a plant in
oom that has no light but from a ſingle hole in
wall: inſtead of riſing perpendicularly, it di-
ts its courſe toward the light, paſſes through
hole into open air, and then mounts upward.
ıe power of remedying a bad ſituation, is re-
markable in ſeed of every kind. A ſeed con-
ns the plant in miniature, with a *plumula* that
nds upward, and a *radicle* that tends down-
rd. Put a ſeed into the ground with its plu-
ıla above and its radicle below as the plant
ows, the former aſcends and the latter deſcends,
th perpendicularly. Invert the poſition of the

ſoil the ſeed is ſown, and have early flowers. Plants from ſeed produced in a cold ſtiff ſoil, are late of growing, even in a warm ſoil. Plants from ſeed produced in a very rich ſoil, grow vigorouſly in a poor ſoil. Plants from ſeed of a poor ſoil, grow weakly even in the richeſt ſoil, and produce ſmall ſeed. In the rainy harveſt 1744, oats that grew in a warm light ſoil, ſprouted in the ſhock ten days more early than oats that grew in a cold ſoil; though both were produced from the ſame ſeed, and both were cut down the ſame day. Hence the advantage of changing ſeed from a warm to a cold ſoil. It may be true, that ſeed from a warm ſoil will not grow ſo quickly in a cold ſoil as in a warm ſoil; but it will always grow more quickly than ſeed from a cold ſoil. To rear trees in a middling ſoil, it is certainly right to take the young plants from a richer ſoil. But is it right to tranſplant them from a rich ſoil to one that is poor? They have, it is true, a tendency to grow vigorouſly. But will they not be dwarfiſh in the poor ſoil, which cannot afford them ſufficiency of nouriſhment to ſupport their vigour?

That a plant may change its conſtitution by being tranſplanted into a climate a little warmer or colder, is certain; and the change of conſtitution is ſtill more eaſy when the plant is raiſed from ſeed. Thus plants of one climate may, by gradual change of place in ſucceſſive generations, proſper in a very different climate. When Galen

phyſician lived, the peach was too delicate for
air of Italy. It has been creeping northward
wly; and, even in Britain at preſent, it is of a
od flavour, if artfully cultivated. The cherry
e was brought by Lucullus from the Leſſer
ia to Rome, as a great rarity; and now it bears
od fruit even in Scotland. The bleſſings of
ovidence are diſtributed with an equal hand.
e are enabled to remedy by induſtry the natu-
defects of our ſoil and ſituation: are we leſs
ppy than thoſe who owe all to ſoil and ſitua-
n? If wheat, if fruits, if cabbage, if *colly-*
wer, were confined to their native climates,
at would Britain be? Iceland would be not
ich inferior.

But though a change of conſtitution is produany flower till April. Dr Walker ſays, that were he to ſee a *laurustinus* flowering with us in winter, and had never heard of the ſhrub, he would without ſcruple pronounce it no native of this country; and that for the ſame reaſon he would deny the *arbutus* to be a native of Ireland, or the whin, of Scotland. He adds pleaſantly, that the flowering of theſe ſhrubs with us, is an outlandiſh faſhion; and that no ſenſible Scotch plant will ever think of ſuch a thing.

## 3. CHANGE OF SEED, AND OF SPECIES.

THE reaſon for changing ſeed from a warm to a cold ſoil, is explained in the foregoing ſection. But ſkilful farmers are not ſatisfied with that ſingle change: they frequently change ſeed from a cold to a warm ſoil; and they ſeldom venture to ſow twice ſucceſſively the ſame grain in the ſame field. Such changes of ſeed, as well as of ſpecies, are general; yet I know not that the reaſon has been fairly explained by any writer. I wiſh that what follows may give ſatisfaction.

Every ſpecies of animals has a climate adapted to it, where it flouriſhes, where it grows to perfection, and where it never degenerates. Propagation will go on in a leſs proper climate; but the ſpecies degenerates, if not kept up by frequent recruits from the original climate. In that view, Arabian and Barbary horſes are from time to time imported into England. Nor is this alone ſufficient: animals procreated of the ſame breed quickly degenerate; for which reaſon, great attention is given to mix different breeds. In theſe particulars, plants reſemble animals. Britain is not the native climate of melons: they degenerate quickly, if ſeed be not procured from the native climate. Where wheat grows naturally, ſeed dropping from the mother plant arrives at perfection, though neither ſeed nor ſoil be changed. But as wheat is not a native of Britain, it has a tendency to degenerate here, eſpecially in the northern parts; and it degenerates rapidly, if the ſeed be ſown year after year where it was produced. It is not ſufficient, that the ſeed be taken from a different field: it ought alſo to be taken from a different ſoil. Nor is this all: the greateſt care in changing ſeed will not prevent degeneracy, where the ſame ſpecies is ſucceſſively propagated in the ſame field. It is accordingly a rule univerſally practiſed in cropping a field, that not only ought ſeed to be brought from a different ſoil, but that the ſpecies alſo ought to be changed; or, in other words, that there ought to be a rotation of crops. This rule holds in barley as well as in wheat; and ſtill more in red clover, which degenerates quickly when ſown without intermiſſion in the ſame field. It is more common to ſow oats after oats; and if that plant be a native of Britain, the practice may eſcape cenſure, eſpecially if care be taken to change the ſeed. White clover is a native of Britain, and requires little precaution in cropping. By Tull's mode of huſbandry, tolerable crops of wheat have been raiſed in the ſame field, fifteen or ſixteen years ſucceſſively; but toward the end, the degeneracy became viſible. Artful culture will do much; but it is not alone ſufficient to prevail over the laws of nature. This is an objection to Tull's huſbandry which that ingenious author did not foreſee. His mode however ought not to be totally rejected; to raiſe by artful culture, without manure, ten or twelve crops of wheat ſucceſſively in the ſame field, is a capital improvement in farms where manure is ſcarce.

The degeneracy of plants and animals in climates where they are not natives, depends on cauſes beyond the reach of human inveſtigation. But to a perſon whoſe curioſity is not boundleſs, it may be ſufficient to obſerve, that if every ſpecies of animals and plants have a climate fitted for them, there is no reaſon to expect perfection in an improper climate.

If what is ſaid hold true, an extenſive rotation of crops in the ſame field muſt be good huſbandry. In a clay ſoil, wheat after fallow without change of ſpecies, is not uncommon. I ſhould imagine, that in Scotland a crop of wheat every other year in the ſame field, would be apt to degenerate. There is an additional reaſon againſt that practice,

at it requires a larger ſtock of working cattle
an a more varied rotation. A ſkilful farmer
ltivates his wheat-land in October, his beans in
nuary, his oats in March, his barley in April
May, and his turnip in June or July, all with
e ſame cattle.

The particulars above ſet forth, are what I
dge the moſt eſſential in the theory of agricul-
re, and what will be found neceſſary for under-
nding the ſubjects handled in the following
apters. Many other particulars, leſs extenſive
ough perhaps no leſs material, are introduced
ere there is occaſion for them. Upon the
ole, in order to eaſe the reader, I have avoid-
every article of theory that is not cloſely con-

thoughts, that his ſyſtem ought to be ſubjected to the rigid touchſtone of facts and experiments: ſo grievous a torture he cannot ſubmit to. This reflection will be juſtified by what follows. And to pave the way, a general view of the nouriſhment of plants ſhall be premiſed.

Juices imbibed through the roots and leaves of a plant, are by an internal proceſs converted into ſap, which, not improperly, may be called the *chyle* of vegetables. Sap is in a continual oſcillatory motion, aſcending during the heat of day, and deſcending during the cold of night.

The ſap of a plant is nearly the ſame, in whatever ſoil the plant grows. Homberg filled a pot with earth containing a portion of ſaltpetre: he filled another pot with pure earth well waſhed. The creſſes that grew in theſe pots were entirely of the ſame nature, equally alkaleſcent; what grew in the firſt pot as little acid as what grew in the ſecond. In other two pots, prepared in the ſame manner, he planted fennel, an acid plant. The difference of earth made no difference in the two plants. I advance a ſtep farther. If we can judge of ſap from what of it perſpires from the plant, it is nearly the ſame, even in different ſpecies. Dr Hales collected the liquor perſpired from trees of different kinds. It was very clear: its ſpecific gravity was nearly the ſame with that of common water; and no difference of taſte could be perceived in the different liquors. Theſe facts are confirmed by many other experiments; all of them evincing, that however different the juices may be that are imbibed by a plant, yet that the ſap into which theſe juices are converted is the ſame, or nearly the ſame, even in plants of different ſpecies. If ſo, every plant muſt be endowed with proper powers; firſt, to imbibe juices; next, to convert into ſap the juices imbibed; and laſt, to convert that ſap into its own ſubſtance. With reſpect to the two firſt powers, all plants appear to be ſimilar. The difference of ſpecies is carried on by the laſt power only, that of converting ſap into the ſubſtance of a plant. Hence a peculiar texture, colour, ſmell, taſte, in each ſpecies. "Thus," ſays Dr Hunter of York, "a maſs of innocent earth can give life and vigour to the bitter aloe and to the ſweet cane, to the cool houſe-leek and to the fiery muſtard, to the nouriſhing wheat and to the deadly night-ſhade." In what manner or by what means the changes mentioned are produced, will for ever remain a ſecret: they depend on energies impenetrable by the eye, and beyond the reach of experiment. Nor ought the farmer to repine at the being denied the knowledge of ſuch matters. The province of agriculture is, to cultivate ſoils in ſuch a manner as to furniſh juices in plenty: the reſt muſt be left to nature; and may ſafely be left, for ſhe never errs in her operations.

Thus prepared, we proceed to examine the moſt noted opinions concerning the food of plants. A number of writers hold, that oil and ſalt are capital ingredients in vegetable food; and that the richeſt ſoils are what contain the greateſt quantity of theſe ſubſtances. Oil and ſalt are found in vegetables. "*Ergo*," ſay theſe writers, "oil "and ſalt in the ſoil make the nouriſhment of "plants." It may as well be reaſoned, that as all animals have blood, *ergo*, blood is the nouriſhment of animals. The ſame doctrine applied to manures, has led Dr Hunter, mentioned above, to propoſe a manure conſiſting chiefly of oil, termed by him the *oil compoſt*; upon which he lays great weight. Every attempt to enlighten is praiſe-worthy; but ſuch attempts ſeldom are ſucceſsful, unleſs to miſlead the credulous huſbandman. From what is ſaid above, it may be pronounced with certainty, that the oil and ſalt which enter into the compoſition of vegetables, are not imbibed from the earth or air; but are formed from more ſimple materials, by the internal proceſs above mentioned. A number of plants of different kinds, may find room for growing in thirty or forty pounds of earth. Each of them has an oil and a ſalt peculiar to itſelf; though there may not be in the earth the ſmalleſt particle of either. Nay, by repeated experiments it has been found, that plants raiſed in water are compoſed of the ſame parts with thoſe raiſed in earth.

Led by this erroneous opinion, ſeveral writers have conjectured, that clay-marl, a potent manure, muſt contain a large proportion of ſalt and oil. But it being found on trial, that it contains neither, they were reduced to another conjecture, that when mixed with the ſoil, it attracts ſalt and oil from the air. And now from Dr Ainſlie's accurate and elegant experiments *, that ſuppoſition appears to have as little foundation as the others mentioned.

Had due attention been given to the mouths of roots, ſo ſmall as not to be diſcernible by the naked eye, it muſt have been obvious, that oil is a ſubſtance too groſs for entering theſe orifices. Chymiſts hold, that all oils are compoſed of inflamable matter, mixed, by means of an acid, with earthy and watery particles. Nay, it is held in general, that every ſubſtance ſuſceptible of a chymical operation, is a compound; and it is natural to think ſo, for elementary particles are ſurely too minute for our handling. Now, as oil, far from being an element, is compoſed of various parts, it is certainly too groſs for the mouths of plants. Its component parts may be ſufficiently minute for admiſſion: but then theſe parts are not oil; though by an internal proceſs they may be converted into oil, or converted into any other ſubſtance. Salt indeed is ſoluble in water, ſo as to

---

* Edinburgh Phyſical Eſſays, vol. 3. article 1.

to become inviſible; and with water conſequently it may be imbibed by plants. But ſalt is too acrid to be a nouriſhment for plants; and if imbibed in any quantity, will be deſtructive.

I have given the ſtricteſt attention to this doctrine, in order to put the ſpeculative farmer on his guard. If he aſſent to what is here delivered, it may ſave him much time, that would be loſt in peruſing certain huſbandry-books, and much labour in proſecuting idle experiments. And here I muſt ſay again, for it cannot be too often ſaid, that the province of agriculture is, to prepare the ſoil ſo as to furniſh plenty of juices, leaving the reſt to nature.

Tull is one of the boldeſt theoriſts that have come under my inſpection. He pronounces without heſitation, that all plants live on the ſame food or *pabulum*, which he ſays is pulverized earth; and upon that foundation, he pretends to raiſe perpetual crops of wheat in the ſame field, by the plough alone, without manure. This indeed would reſtore the golden age of eaſe and indolence; as there is no ſoil ſo barren, but what may readily be pulverized. Tull was a man of genius, but miſerably defective in principles. Plants imbibe water plentifully at the leaves, bark, and roots; and with water they imbibe whatever is diſſolved in it. But earth is not ſoluble in water; and accordingly, by an experiment of Van Helmont it appears, that earth makes no part of the

e food of plants. He put into a veſſel two hun-
ed pounds of dry earth; which he moiſtened
th rain-water, and planted in it a cutting of
llow, weighing five pounds. The mouth of
e veſſel, to keep out duſt, was covered with a
-plate, having many ſmall holes, through which
n or diſtilled water was poured from time to
ne, for keeping the earth moiſt. The willow
eighed at the end of five years a hundred and
ty-nine pounds and about three ounces; and
e weight would have been much greater, had
e leaves that fell the firſt four years been com-
ted. At the end of the fifth year, the earth
s taken out of the veſſel; and, when dried,
s found to have loſt none of the original weight
cepting two ounces. Mr Boyle made a ſimilar

lucky: of all ſubſtances, earth appears to be the leaſt fitted for nouriſhing plants; and from Van Helmont's experiment it is clear, that if at all it enter the mouths of plants, the quantity is inconſiderable: of the great quantity of earth, two ounces only were loſt; and ſuppoſing theſe two ounces to have been diſſolved in the water and ſucked in by the plant, it was next to nothing, conſidering the weight of the whole plant, which was a hundred and ſixty nine pounds.

Other writers, more cautious, avoid ſpecifying any particular ſubſtance as the food of plants; but hold, that every ſpecies of plants require a peculiar nouriſhment; and that roots imbibe thoſe juices only which are fitted for nouriſhing the the plant. The refutation of this hypotheſis will not require many words. It is ſufficient to obſerve, that it is refuted by unconteſtable experiments. Plants take in with air and water whatever is diſſolved in them, without diſtinguiſhing the ſalutary from the noxious: there is not the leaſt appearance in any plant of a choice. Barley has been poiſoned with brimſtone, and mint with ſalt water. Mr George Bell ſtudent of phyſic in the college of Edinburgh, an ingenious young

earth put into the phial was diminiſhed. But ſuch particles are not earth; and therefore the Doctor's experiments contradict not thoſe of Van Helmont and Mr Boyle.

gentleman, made the following experiments, which he obligingly imparted to me. A number of Jeruſalem artichokes were ſet in pots filled with pure ſand. One plant was kept as a ſtandard, being nouriſhed with common water only. Other plants of the ſame kind, were nouriſhed with water in which ſalt of tartar, a fixed alkali, was diſſolved. Theſe grew more vigorouſly than the ſtandard plant. But by reiterated waterings, there came to be ſuch an accumulation of the fixed alkali among the ſand, as to make the plants decay, and at laſt to die. Some plants were nouriſhed with water, in which ſal ammoniac, a volatile alkali, was diſſolved. Theſe grew alſo well for ſome time; but, like the former, were deſtroyed by the frequent reiteration of it. Weak lime-water promoted the growth of its plants more than common water. But water completely ſaturated with quick-lime, proved more noxious than that which contained a ſolution of fixed alkali; though leſs than that which contained a ſolution of volatile alkali. Hence appears the hurt of overdoſing a field with quick-lime. Urine promoted, for a long time, the growth of its plants; and the moſt putrid appeared to have the ſtrongeſt effect: but at laſt, it totally deſtroyed them. Water impregnated with putrid animal and vegetable ſubſtances, did more effectually promote the growth of its plants than any other ſolution; and in every ſtage of the progreſs appeared to be ſalutary.

Rotation of crops in the ſame field, univerſally practiſed, is what probably has promoted the opinion of a ſpecific nouriſhment. It has been urged, that if all plants live on the ſame food, the ſoil muſt be exhauſted by a ſucceſſion of different plants, as much as by a ſucceſſion of the ſame plant. This argument for a ſpecific nouriſhment has a formidable appearance; and in order to obviate it, I found it neceſſary to give peculiar attention to that branch of huſbandry, which is done above *. It is there made evident, that change of ſpecies is neceſſary, not for food, but for preventing degeneracy. It is not want of food that makes a horſe degenerate in Britain; and as little want of food that makes wheat degenerate, where ſown without intermiſſion in the ſame field. Plants native to Britain never degenerate, though always growing in the ſame ſpot; white-clover, for example, nettles, broom, whins, ruſhes, couch-graſs, &c. &c. A bull-dog never degenerates in Britain.

Animals from their food are divided into two kinds, carnivorous and graminivorous. But I diſcover no ſuch diſtinction among plants. All of them live upon the ſame food; and it muſt be ſo, if the opinion of a ſpecific nouriſhment be rejected.

---

* Part 2. chap. 1. § 3.

Certain ſubſtances are provided by nature for the nouriſhment of plants. It is highly probable, that a quantity was lodged originally on the ſurface of this earth, for nouriſhing the firſt plants: whence the fertility of virgin ſoils, ſuch as have never been cultivated. This vegetable matter diſſolved in water, and imbibed by plants, is communicated to animals that feed on plants, and ſet free again by the death and putrefaction of theſe animals. The more volatile parts are attracted by the air: ſome are ſucked in with air at the leaves of plants: ſome are waſhed down to the ground by rain; and with it are ſucked in at the roots. The leſs volatile parts, which the air does not attract, are diſſolved in water, and with it are alſo ſucked in. And thus the proceſs is continued without end. This propoſition of a common nouriſhment, is firmly ſupported by the following facts. Firſt, Plants of different kinds growing in the ſame ſpot, rob and ſtarve each other; which could not be, if each drew from the ſoil a ſeparate nouriſhment. Second, Grafting and inoculating demonſtrate a common nouriſhment. If the roots of the ſtock imbibe thoſe juices only that are proper for its own nouriſhment, the grafted plant muſt ſtarve. The juices imbibed by the former, nouriſh both; and theſe juices are by each plant converted firſt into ſap, and then into its own ſubſtance. Third, Dung of putrefied vegetables, of whatever kind they be, is one homogeneous ſubſtance; and yet vegetable dung prepares the ſoil equally for every ſort of plant. I add a conſideration of a kind that to me is always perſuaſive: a common nouriſhment is not only a more ſimple but a more wiſe diſpenſation of Providence, than a peculiar food for each ſpecies: every plant grows not every where; and if each ſpecies required a peculiar food, a vaſt ſtock of vegetable food would remain unuſed; which is not conformable to the frugality of nature, nor to the wiſdom of Providence, which makes nothing in vain.

But though all plants imbibe indifferently, every ſubſtance that is diſſolved in water; it follows not, that every ſuch ſubſtance, even where innocent, is equally nouriſhing. Some ſubſtances may be proper nouriſhment, ſome not: and it may rationally be ſuppoſed, that the latter is thrown off as excrement; which will ſo far juſtify the notion of a ſpecific nouriſhment. Why may there not be a reſemblance in this particular, between plants and graminivorous animals? A horſe, an ox, a ſheep, a goat, live all of them on graſs; but each of them have favourite graſſes, which they prefer before other kinds. Let experiments be made, to try what is the moſt ſalutary food for plants. A few experiments of that kind are mentioned above; but to give ſatisfaction, they ought to be multiplied and extended to plants of different kinds.

It is an opinion univerſally received, that the fertility of a ſoil, depends on the quantity it contains of the food provided by nature for the nouriſhment of plants, whether ſpecific or common; that when the quantity contained in any field is exhauſted by cropping, it is reſtored by the plough, by dung, or by other manure; and that to reſtore an exhauſted field by ſuch means, is the ſole object of agriculture. This opinion has a fair appearance: nor had I ever a doubt about it, till the following conſiderations happened to occur. I do not much reliſh the notion, that the number of plants growing at any time on this globe, muſt be limited by the quantity of vegetable food created originally for their nouriſhment, nor that the quantity of graminivorous animals muſt be alſo ſo limited; and yet this muſt neceſſarily follow, if plants have no other food but what was thus originally provided for them. But ſuppoſing this conſideration not to weigh with others as with me, there are other conſiderations that cannot fail to make an impreſſion. Some countries produce corn and cattle, not only for the inhabitants, but for exportation. According to the preſent doctrine, theſe countries muſt long ago have been reduced to abſolute barrenneſs. Egypt and Sicily were of old the granaries of Italy; and vaſt quantities of vegetable food, converted into corn, were annually exported from theſe countries, never to return. Yet we do not find that they are leſs prolific than formerly. Sicily at preſent does not conſume at home above the ſeventh part of its wheat: the remainder is exported; and yet not the leaſt ſymptom of approaching barrenneſs. Conſider the endleſs quantity of beef exported every year from Corke in Ireland: whatever quantity of vegetable food may originally have been ſtored up in that part of the iſland, it muſt long ago have been totally exhauſted. I urge another objection more general. Where-ever burying under ground is the practice, the vegetable food contained in the bodies of human beings is totally loſt, not to mention thoſe who periſh at ſea. At that rate, there muſt be a gradual diminution of vegetable food, ſo as that in time the whole will be exhauſted. I add a fact that alone may be thought ſufficient to convince any thinking perſon, that plants muſt be provided with ſome food beſide that originally created. In Scotland, there are fields that paſt memory have carried ſucceſſive crops of wheat, peaſe, barley, oats, without a fallow, and without manure. And that there are ſuch fields in England and elſewhere, is not to be doubted. A field of nine or ten acres on the river Carron, is ſtill more extraordinary. Upon it I ſaw a good crop of oats almoſt ripe; and by information it was the hundred and third crop of oats without intermiſſion, and without manure, as far as was known. Now, whatever be the nature of ſuch a ſoil, its unremitted fertility cannot be accounted for, from any ſuppoſed quantity of vegetable food originally accumulated in it. It is eaſy by manure to make ſoil too rich for corn: it vegetates without end, and the ſeed has not, before winter, time to ripen. But ſuppoſing the richeſt ſoil to be proper for corn; yet that vegetable food, however great the quantity, muſt in time be exhauſted by cropping. Some other proviſion therefore muſt be made by nature for the nouriſhment of plants, beſide the vegetable food originally created.

Immenſe is the quantity of corn and ſtraw, that during a century is produced in a ſoil perpetually fertile. It is a puzzling queſtion, whence proceeds ſuch a quantity of matter; for a new creation cannot be admitted. A perpetual effect muſt have a perpetual cauſe: the ſoil muſt receive additions without end, to reſtore what is taken away in corn without end. I am aware, that the ſmalleſt portion of matter may by diviſion be made to occupy ſpace without bounds. But obſerve, that the difficulty ariſes from weight, not from bulk. Corn is a weighty ſubſtance; and the corn produced on this globe from the beginning, muſt amount to a weight above computation: the ſmall portion reſtored to the ground in manure, is a mere atom in compariſon. I have endeavoured above to evince, that earth is not converted into corn: and here is an additional proof; for ſuch converſion would exhibit a very new ſcene: inſtead of the hills ſinking down gradually into the vallies, the vallies would ſink rapidly down from the hills. A perpetual effect, I have obſerved, muſt have a perpetual cauſe: to preſerve a ſoil perpetually fertile, there muſt be a continual influx of vegetable food, to ſupply what is taken away by cropping. Whence comes that vegetable food? where is it ſtored up?

Air and water contribute to vegetation: let us try to build on that foundation. Suppoſing air and water to be the food of plants, not meaning to exclude what may be diſſolved in them, the difficulty vaniſhes, as air and water are inexhauſtible. And why may not that ſuppoſition hold in fact? I begin with air. Many plants grow to perfection, without having any nouriſhment that can be diſcovered but air only. The houſe-leek grows from choice on a dry mud-wall, which ſurely affords no nouriſhment. A ſpecies of the ſedum, requiring a hot-houſe in winter, is never watered. The wall-flower grows luxuriantly in the ſeams between large ſquare ſtones in old buildings, from which all moiſture is excluded but what is in the air. Various kinds of moſs grow upon hard ſtones, where they can have no nouriſhment but from the air. It is an univerſal opinion, that leguminous plants, before they ſeed, draw moſt of their nouriſhment from the air. Conformable to that opinion, Dr Hales, in his curious Statical Eſſays, has made it evident, that every vegetable contains a quantity of air, which adds to the weight as well as to the bulk. The fixed air in a green pea, makes no leſs than a third part of the weight. In wood, however old or dry, air is found, very obſervable when ſet looſe by fire. Here is one inexhauſtible ſtore of matter for compoſing plants.

Water is a ſtill larger ſtore. A plant regularly watered, will grow vigorouſly in the moſt barren ſoil, even in dead ſand. In Perſia, very little rain falls during ſummer, and the land is burnt up; not a pile of graſs to be ſeen. But plants there regularly watered, grow exceſſively. There are many experiments of plants ſet in glaſſes upon moſs or ſpunge, which grow well when watered. Some cotton was ſpread on water in a phial: a pea dropped on it ſprung, and puſhed roots through the cotton into the water. The plant grew vigorouſly, and bears at preſent large pods full of ripe ſeed. There is a noted experiment of an oak growing in pure water to the height of eighteen feet. Water is attracted by vegetables of every kind; and is ſucked in at the roots, at the leaves, and even at the bark. The quantity imbibed during a ſpring and a ſummer, is amazing. The quantity exhaled every day, is accurately meaſured in the Statical Eſſays mentioned; which muſt be leſs than what is imbibed, becauſe plants do not throw off all they imbibe, part being converted into their ſubſtance, and adding to their bulk and weight *. The drieſt wood accordingly yields, by diſtillation, a large proportion of water. A ſtream occupies the loweſt ground, without regard to ſoil; and yet the graſs on its borders is always more rich and verdant than at a diſtance. A tree grows no where more vigorouſly than at the ſide of a brook. About a large ſtone fixed in the ground, the graſs is generally the beſt in the field: for what other reaſon, than that the rain which falls on the ſtone runs off to the ſides? I do not ſay, that the heat of the ſtone during ſummer may not contribute ſomewhat. The north ſide of a hill, is obſerved to be commonly better ſoil than the ſouth ſide: if there be truth in the obſervation, it muſt proceed from moiſture, leſs being evaporated from the former than from the latter. Black ſolid peat-moſs retains moiſture like a ſpunge: trees grow vigorouſly in it, provided they be ſheltered from wind; for their roots cannot reſiſt wind in a ſoil ſo tender and looſe. On the other hand, no ſoil is more barren than a gravelly or ſandy moor that holds no water; upon which the foot makes no

---

* The emiſſion of water from plants, is the occaſion that a country abounding with trees, is more ſubject to damps, humid air, and frequent rain, than a bare country where no trees grow. The exceſſive moiſture of the American air was a great annoyance to our firſt ſettlers; but the air became more dry, and the weather more conſtant, as the ground was cleared of trees.

impreſſion, not even after a heavy ſhower. I am buſy at preſent in cultivating a moor of that kind, upon which are ſcattered ſome dwarfiſh plants of heath and bent, that leave half of the ſurface bare. I judged that manure would not anſwer, till the field ſhould be made to retain moiſture; for which reaſon I incorporated with it a quantity of ſoft ſpungy earth. I added lime and dung; and now it carries a rich crop of turnip and cabbage. The alteration of the ſoil is obvious to the eye; and alſo to feeling, as the foot dips in it after every ſhower. Lord Bacon long ago gave his opinion, that for nouriſhing vegetables, water is almoſt all in all; and that the earth ſerves but to keep the plant upright, and to preſerve it from too much heat or too much cold.

To ſupply the endleſs quantity of moiſture neceſſary for vegetation, nature has made ample proviſion. The continual circulation of water upon this globe, from its ſurface to the atmoſphere, and down again to the ſurface, is juſtly admired for the ſimplicity of its cauſe, no leſs than for its bountiful effects. An elective attraction between air and water, is the *primum mobile* of theſe effects *. Water is eight hundred times heavier than air; and yet by that ſingle power, an immenſe quantity of water is ſuſpended in air; and falls down from time to time in rain, dew, and ſnow, impregnating the earth with moiſture. Dr Hales, in a dry July, dug up a cubic foot of brick-earth, weighing one hundred and four pounds, which contained ſix pounds and eleven ounces of water. Under the former he dug up another cubic foot, weighing one hundred and ſix pounds and ſix ounces, which contained ten pounds of water. Under this he dug up a third cubic foot, weighing one hundred and eleven pounds and one third, which contained eight pounds and eight ounces of water. Here is a conſiderable ſtock of moiſture, ſufficient without rain to afford vegetable nouriſhment ſeveral weeks; not to mention what may be attracted from below, by the upper ſtratum when its moiſture is exhauſted. Evaporation goes on ſo rapidly between the tropics, that to preſerve plants alive, moiſture muſt be attracted from below; for, as mentioned in the firſt chapter of this part, there is an elective attraction between earth and water; and where a portion of earth is ſaturated with water, it readily yields its ſuperfluous water to a dry body in contact with it. This aſcent of moiſture is promoted by the heat of the ſun, which pierces deeper into the earth than two feet, according to experiments made by Dr Hales. Were not plants thus ſupplied with moiſture in the torrid zone, where no rain falls for many months, they would be deſtroyed by the ſcorching heat of the ſun. The evening dew that falls in a hot ſummer, is ſucked up the following day, without ever ſinking to the roots of plants.

---

* Edinburgh Phyſical Eſſays, vol. 3. art. 4.

But though air and water are allotted by nature as the conſtant and inexhauſtible food of plants, there ſeems to be little doubt but that this food may be inriched by various ſubſtances diſſolved in them. We have ſeen above, that water impregnated with rotten animal and vegetable ſubſtances, makes rich nouriſhment for plants; and from experiments, other ſubſtances may probably be diſcovered, equally efficacious. Plain water may be ſufficient for the ſtem, branches, and other groſs parts; but we have reaſon to think, that richer nutritive matter is neceſſary for perfecting the ſeed. Hence the imperfection of ſeed in a rainy year, where the rich matter bears no proportion to the quantity of water that paſſes through a plant.

Moderate rain in a kindly ſeaſon, warms tilled land, and produces a ſlight fermentation. It is here as in a dunghill: a very little quantity of moiſture has ſcarce any effect: a great quantity chills the ground, inſtead of warming it. Different plants require different quantities of moiſture. Graſs is benefited by all it receives; provided the moiſture exceed not ſo much, as to chill the ground and the roots of the plants *. So far corn reſembles

---

* A graſs plant cannot retain ſo much as to hurt it: whatever is imbibed more than ſufficient for nouriſhment, perſpires

ſembles graſs, as to be ſlunted by lack of moiſture, and conſequently to blanch early. The ſeed has more than time to ripen; but it is lank and ill filled. Corn differs in being hurt by much moiſture: it vegetates continually; and winter comes on before the ſeed begins to ripen. Holland is a moiſt country: there is ſcarce a foot of dry ground in it. Trees, graſs, and vegetables, grow there luxuriantly: but its fruits ſeldom ripen: and where ripe, have little taſte.

Thus from air and water, with what they contain, there is an inexhauſtible ſupply of vegetable nouriſhment, which fairly accounts for the immenſe quantity of corn that is annually produced.

The ſun joins with air and water in nouriſhing plants. The green colour of plants is occaſioned by an oily ſubſtance, which can be ſeparated by a chymical operation; and that oily ſubſtance is owing to the ſun, for no plant is green where the ſun is excluded. The ſun therefore contributes to advance plants to perfection. And it is one of the properties of leguminous plants, that their broad leaves abſorb more of the ſun's rays, than the narrow leaves of culmiferous plants.

---

perſpires at the leaves. There is a conſiderable latitude in the quantity of healthy perſpiration; which, in the ſun-flower, by an experiment of Dr Hales, appears to be from ſixteen to twenty-eight ounces in twelve hours day. And he adds, that the more it was watered the more it perſpired.

According to the foregoing theory, the only uſe of a ſoil, is to fix the roots of plants, and to hold water for nouriſhment. But at that rate, where lies the difference between a rich and a poor ſoil? This globe is ſurrounded with air, and rain pays not homage to one field in preference to another? The ſolution of this queſtion will, if I be not groſsly miſtaken, confirm the foregoing theory, and evince that it is founded on truth. Soils originally may have been very different with reſpect to fertility, ſuppoſing vegetable food to have been unequally diſtributed by the hand of nature. A virgin ſoil may be extremely rich; witneſs the ſurpriſing fertility of America, when agriculture was introduced there. But cultivated grounds muſt long ago have been deprived of that original food, in the courſe of cropping; after which, it does not enter into my conception, what other circumſtance can remain to make a ſoil fertile, but the holding water in ſufficient quanity for its plants. A clay ſoil holds a great quantity; a ſandy ſoil, very little. Some ſoils there are ſingularly retentive of moiſture, and that quality makes them long of drying: ſuch ſoils are favourable to vegetation; for though they reſiſt drought, they yield to the attraction of plants *. Other ſoils are very little retentive

---

* May it not be thought, that the quantity of moiſture which gives to a ſoil its higheſt fermentation, is at the ſame

retentive of moiſture: they dry in an inſtant, and the nouriſhment they can afford is very ſcanty. Here the myſtery is unfolded. The richeſt ſoil is what gives the greateſt reſiſtence to a drying air, and at the ſame time furniſhes to its plants their proper quantity of moiſture. I have a thorough conviction, that this property belongs to a ſoil perpetually fertile: and it is to me a ſtrong confirmation of the preſent theory, that I cannot form even the ſlighteſt conception, how perpetual fertility can otherwiſe be accounted for; and as little can I form a conception, how otherwiſe countries, like Poland or Livonia, out of which great cargoes are annually exported of corn and flaxſeed, ſhould ſuffer no diminution of fertility.

To recruit with vegetable food a ſoil impoveriſhed by cropping, has hitherto been held the only object of agriculture. But here opens a grander object, worthy to employ our keeneſt induſtry, that of making a ſoil perpetually fertile. Such ſoils actually exiſt: and why ſhould it be thought, that imitation here is above the reach of art? Many are the inſtances of nature being imitated with ſucceſs: let us not deſpair while any hope remains; for invention never was exerted upon a ſubject of greater utility. The attempt may ſuggeſt proper experiments: it may open new views;

---

ſame time the fitteſt for perfecting ſeed. However pleaſing this conjecture may be, I dare not vouch it for truth: it muſt be left to experiment.

and if we fail in equalling nature, may we not however hope to approach it? A ſoil perpetually fertile, muſt be endowed with a power to retain moiſture ſufficient for its plants; and at the ſame time muſt be of a nature that does not harden by moiſture. Calcarious earth promiſes to anſwer both ends: it prevents a ſoil from being hardened by water; and it may probably alſo envigorate its retentive faculty. A field that got a ſufficient doſe of clay marl, carried above thirty ſucceſſive rich crops, without either dung or fallow. Doth not a ſoil ſo meliorated draw near to one perpetually fertile? Near the eaſt ſide of Fife, the coaſt for a mile inward is covered with ſea ſand, a foot deep or ſo; which is extremely fertile, by a mixture of ſea ſhells, reduced to powder by attrition. The powdered ſhells, being the ſame with ſhell-marl, make the ſand retentive of moiſture; and yet no quantity of moiſture will unite the ſand into a ſolid body. A ſoil ſo mixed ſeems to be not far diſtant from one perpetually fertile. Theſe, it is true, are at beſt but faint eſſays; but what will not perſeverance accompliſh in a good cauſe?

A ſoil is denominated fertile, that affords plenty of nouriſhment to its plants; and accordingly it is ſuch a ſoil only that has been the ſubject of the foregoing inveſtigation. Plants that live moſtly on air, require not ſuch a ſoil; witneſs the houſeleek mentioned above. Juniper thrives on the top of a mountain, in the pooreſt and drieſt ſoil;

becauſe, in that ſituation, it is ſufficiently ſupplied with moiſture from the air. If planted in a dry climate, it requires a moiſt ſoil, to ſupply the want of a moiſt atmoſphere. The nature of the yew is the ſame. Planted in a valley, it requires a damp ſoil. It will grow in the drieſt ſoil, as in the cleft of a rock; but then it muſt be at ſuch a height, as to enjoy a very humid air. Theſe are a ſpecimen of plants, that affect to grow in a ſoil commonly reckoned barren. A ſoil that a mere farmer would pronounce barren, is for many plants excellent. How otherwiſe could the earth be every where cloathed with beauty? How great muſt be the diverſity of ſoil, climate, and ſituation, that can riſe to perfection above 20,000 kinds of plants, to each of which is requiſite ſome peculiarity of ſoil, of climate, or of ſituation!

Whether the theory here exhibited will occaſion any material alteration in the practice of agriculture, muſt be left to the diſcovery of time. Of one thing I am firmly convinced, that the inſtructions above delivered, are in every particular conformable to that theory. Take the following ſlight ſpecimen. Plants, like animals, cannot live long in the ſame air: a circulation is to both equally requiſite. For that reaſon, the growth of plants under cover, is ſlow; and ſeed ſprings ſlowly in ſtagnated air. Conformable to this obſervation, a free circulation of air for corn is warmly recommended; and there is a caveat againſt ſmall incloſures, ſurrounded with ſtrips of planting, becauſe they occaſion a ſtagnation of air. Impure air imbibed, renders a plant unhealthy: the grain has a bad taſte, and tends to generate diſeaſes; which holds remarkably in a fruit-orchard, if the trees be crouded, and the walls high. Even graſs, where the air ſtagnates, is unpalatable and unwholeſome. Next, with reſpect to moiſture. No branch of huſbandry is more ſeduloufly inculcated, than that of dividing and pulverizing earth by the plough, by the brake, by harrows, and by manure: it is the very life of agriculture. And from what is laid down above, it appears, that fertility depends greatly on that practice *: it increaſes the capacity of ſoil to contain water: it envigorates its retentive power; and it prevents the ſoil from hardening: to theſe ends manure greatly contributes; and in that view it makes the ſubject of the following chapter.

To aid the fertility of ſoil, the pickling ſeed has been much practiſed. We liſten readily to the marvelous, eſpecially where any great advantage is promiſed. The boaſted effects of the Abbé de Valemont's prolific liquor, found many believers, by which vaſt crops were to be reaped, without manure, and almoſt without ploughing. (See Duhamel's treatiſe on the culture of land, vol. 6.)

---

* Part 2. ch. 1. ſect. 1.

And the Baron de Haac's powder, is at preſent no leſs ſucceſsful in England. The credulity of farmers might in ſome meaſure be excuſable, were ſuch bold pretenſions within the verge of poſſibility. In every ſeed there is an embryo plant; and the reſt of the ſeed ſerves to feed that plant, till it acquire roots for drawing its nouriſhment from the ſoil. The pulp is thus exhauſted, and there remains only the uſeleſs huſk. What advantage then can be derived from a prolific liquor or powder? It may poſſibly render the pulp fitter to feed the young plant, till it ſtrike root. That it can have no other effect is evident; firſt, becauſe it is exhauſted with the ſeed; and, next, that ſuppoſing any of it to remain, it can be of no benefit to roots that are ſpread an inch, two, or three, from the place where the ſeed was laid. Yet books of agriculture are ſtuffed with ſuch receipts.

I cloſe this chapter with a reflection of the juſtly-eſteemed Dr Hales. "Though I am ſenſible, "that from experience chiefly we are to expect "the moſt certain rules of practice; yet the "likelieſt method for making the moſt judicious "obſervations, and for improving any art, is to "get the beſt inſight we can into the nature and "properties of what we are deſirous to cultivate "and improve."

## CHAP. III.

## MEANS OF FERTILIZING SOILS.

AS theſe means are ploughing and manuring, they ſhall be treated in their order.

### 1. PLOUGHING.

THERE are mutual connections between man and the ground he treads on, that fit them for each other. The dry part of this globe, is every where covered with a *ſtratum* of earth, producing vegetables for the nouriſhment of man and of other animals. Some *ſtrata* there are, ſo barren as not to bear vegetables; and ſome vegetables there are, that afford no nouriſhment: but both are rare, and intended probably for other purpoſes.

This *ſtratum* is commonly ſufficiently deep for a free courſe to the roots of plants: or it may be made ſo by art, it being one of the many purpoſes of agriculture to deepen a ſhallow ſoil. A deep ſoil, beſide giving free courſe to roots, retains much water to nouriſh them. In Scotland, partly from ignorance, partly from defect of ſtrength, it is the general practice to plough with a ſhallow furrow, commonly under four inches;

and hitherto the progreſs toward a better mode has been ſlow. It is never difficult to invent reaſons for juſtifying what we are accuſtomed to. "If we plough deep, we are afraid of till." And what is till? Where ground is ſtiff, rain ſettling at the bottom of the furrow cements the earth under it, which in time is hardened to a ſtone; and it is this hardened earth which is named till. The earth is hardened as far as the water penetrates, which may be one or two inches; but after till is formed, every drop of rain reſts upon it without making any impreſſion. To ſubdue till is an important object; and luckily the undertaking is ſeldom difficult: a ſtrong plough, raiſing it to the ſurface, lays it open to the ſun, air, and froſt, which reſtore it to its original ſtate. One precaution is neceſſary. Certain earths, as hinted above, are averſe to vegetation. Theſe muſt be avoided, however ſhallow the ſoil be: but as ſuch earths are rare, they ought not to be an excuſe for ſhallow ploughing.

The advantages of deep ploughing, are manifold. In the firſt place, roots extend far where they meet no reſiſtance; and the growth above the ſurface correſponds to that below: roots cramped in a ſhallow ſoil, are dwarfiſh; and conſequently ſo is the tree. Dr Hales juſtly obſerves, that the greater proportion the ſurface of the roots bears to that of the tree, the greater is the vigour ur of the tree, and the better able to reſiſt the acks of an unkindly ſeaſon.

In the next place, a deep ſoil affords not only ce for roots, but holds a due proportion of ter for nouriſhing the plant. If more rain fall an the ſoil can retain, it deſcends to the bottom the furrow, where it lies lower than the roots, but barely touches their extremities: the ſea- must be very wet, that raiſes the water ſo high to do much damage. The diſadvantage of a llow ſoil is in that reſpect very great. Roots cuſtomed to earth are unqualified to grow in ter: they ſuffer when ſoaked in water; which ſt often happen in a ſhallow ſoil, and is viſible ve ground by a ſickly yellow hue *. Upon be laid ſo deep as to be ſufficiently covered, it approaches the hard bottom, unkindly to tender roots.

So much for a deep ſoil. I proceed to other advantages of ploughing. Stiff ſoil is not penetrable by water: looſe ſoil does not retain it. Ploughing diminiſhes the tenacity of the former, and opens it to receive water: it makes the latter more compact, and increaſes its power of retaining water. Some earths fill not the hole out of which they were dug: ſome do more than fill it. Poroſity occaſions the former: the pores are diminiſhed by handling, which makes it more compact. Solidity occaſions the latter: clay ſwells by ſtirring; and continues ſo, till its former ſolidity be reſtored by the power of gravity *.

Another advantage of ploughing regards clay chiefly, which by moiſture turns hard if not duly ſtirred. This is an important article. Sand has

---

* This experiment ought to be tried upon ground that has reſted many years. Among the cauſes of poroſity, one is, the great number of inſects that have their dwelling under ground, and are expert miners. I ſpeak not of moles and mice, whoſe ſubterranean walks and alleys are obvious to the eye; but of worms, beetles, ants, waſps, &c. whoſe works eſcape obſervation. Their excavations may in a long tract of time render the ſoil extremely porous. The fine earth they dig out, is left upon the ſurface, and blown away by the wind.

no cohesion; and dry clay very little, if any *. It is water that cements clay; and in ploughing makes it riſe in lumps or clods, great or ſmall in proportion to the degree of coheſion. Ploughing prevents water from binding a clay-ſoil: the ſuperfluous moiſture is exhaled by frequent ploughing, and no more left but to give the clay a degree of coheſion ſufficient for fixing the roots. The nice point is, the time of applying the plough after much rain. To plough wet, kneads the parts together: on the other hand, the ground muſt not be ſuffered to turn hard. Between ſoft and hard is the proper condition for ploughing; which may be known by the mouldering of the earth that is raiſed by the plough. During winter, clay may be ſtirred in a moiſter ſtate, than during ſummer: froſt prevents coheſion: heat promotes it. The management of light ſoil is very different. It is eaſily pulverized; but the difficulty is to preſerve its moiſture. A long drought, by extracting much of its moiſture, renders it the leſs fit for vegetation; and to plough it in that ſtate in dry weather, would render it entirely unfit. The only remedy is rain; and if drought ſet in, it ought to be rolled immediately after ploughing.

The proper time of ſowing and harrowing, is when there is no more moiſture than ſufficient to

---

* Part 2. chap. 1. ſect. 1.

give the ſoil a proper conſiſtence; and I conjecture, that the ſame degree of moiſture is the fitteſt for making the ſeed ſpring. Reflect upon the making of malt: a certain degree of moiſture is neceſſary for fermentation: too much checks it. Let rolling immediately follow, to prevent as much as poſſible any more evaporation. Where ſeed is to be ſown in winter, or early in ſpring, it is right to plough ſometime before, in order that the ſuperfluous moiſture may evaporate; for at that ſeaſon there is no fear of exhauſting the moiſture. But late in the ſpring, if the ſeaſon be dry, ſow the ſeed immediately after ploughing. The plants in their courſe of growing, return to the ſoil, during night, part of the moiſture they draw from it during day. Their roots at the ſame time, ſpreading in every direction, keep the ſoil in conſtant motion, and prevent it from turning hard.

I cloſe this ſection with an effect of ploughing the moſt important of all, becauſe it holds in all ſoils leſs or more. Ploughing keeps the ſoil looſe for roots to take their natural courſe, and open for admitting air, dew, and rain. Dew in particular, which falls in plenty during ſummer, when moſt wanted, is loſt upon hard ſoil, being exhaled by the next ſun; but it ſinks deep into looſe ſoil, and is ſheltered from the ſun's power. Ground ſtirred before winter, is not only laid open to the action of the ſun, wind, and froſt, but is early ready for a ſpring crop, beans for example. It ſoon wets indeed, but it dries as ſoon. To drench in water ground left unſtirred, may require a month or two; but then, equal time is required to dry it. The more earth is pulverized, the more water it holds *; and the more parts water is divided into, the more readily it is imbibed by plants. If the ground be rendered too looſe, rolling not only makes it ſolid to ſecure the plants againſt wind, but alſo prevents evaporation.

How beneficial it is to keep ſoil open for the admiſſion of nutritive matter, will appear from the following facts. Stiff ſoil gains little by reſt; for as rain and dew get no admittance, they are ſoon carried off by evaporation. But ſoil, if tolerably open, improves by reſt. I ſuſpect that it gains little by the paſturing of cattle; for what they take away in fat with what they perſpire, will nearly balance the dung they leave: but it gains by the nutritive matter that rain and dew depoſit in it: the rain may evaporate, but it leaves the nutritive matter. This caſe reſembles ſalt depoſited in the ſea by rivers: water is evaporated from the ſea, but the ſalt is left behind; and hence the ſaltneſs of the ſea. The nutritive matter thus left in the earth, is again deluted in rain-

---

* Part 2. chap. 1. ſect. 1.

water; and though not attracted by the air, is attracted by plants, and enters into the orifices of the roots along with the water in which it is diſſolved. There is another cauſe that has a ſhare in the improvement of an open ſoil, and that is air, which, with its contents, enters into the boſom of an open ſoil by attraction *. The operation is indeed ſlow, becauſe the attraction has no effect but in contact or near it; yet in time, the quantity of nutritive matter attracted with air, may be conſiderable. Du Hamel reports, that the rubbiſh of a mud wall made good manure, though the mud had been taken from a very poor ſoil. Graſſy ſod, uſed as a covering for cottages, turns good manure when it has lain long upon a houſe. The walls of a fold for ſheep, being compoſed of ſod, make good manure: when thrown down and mixed with the ſoil, they afford a better crop than the fold within, though enriched by the dung of the ſheep. Among many advantages of fallowing, the expoſing to the air a new ſurface from time to time, is one; by that means, every part of the ſoil draws air with the vegetable food it contains.

## 2. MANURES.

THE operations of nature, hid from the ignorant, and not always obvious to the learned,

---

* Part 1. ch. 1. ſect. 1.

ak out ſometimes into broad day-light. Did
mal bodies after death wither and dry without
ſolving, this earth could not long have been
abitation for men: their utmoſt efforts would
ve been inſufficient to remove dead carcaſes out
the way. Happily putrefaction comes to their
ief: dead bodies diſſolve and mix with the ſoil,
hout leaving a trace behind. Putrefaction is
urious proceſs of nature: air, moiſture, heat,
of them, contribute; but too much, or too
le, is an impediment to the proceſs.

On the ſurface of this globe, a proceſs is conti-
lly going on, unregarded by the vulgar, being
familiar to draw their attention; and yet, il-
trious among the works of Providence for its
neficial effects. Plants and animals are

ſoil naturally ſtiff turns free and open, in proportion to the quantity of dung beſtowed on it. Reduce clay into a dry powder: moiſten it with water, and form it into a ball: repeat the operation at pleaſure, it ſtill returns to its original hardneſs. But moiſten it once or twice with the juice of a dunghill, it becomes mellow, and never recovers its hardneſs. Dung therefore renders clay fertile, by opening it and giving admiſſion to water. It does more: it makes every ſoil retentive of water. Examine a kitchen-garden that has been often dunged in the courſe of cropping: it will be found moiſt above any neighbouring ground of the ſame original ſoil.

As dung is compoſed of putrefied vegetables or of animal excrements, it is natural to think that it contains more or leſs vegetable food. This however goes not beyond a conjecture: a plant or an animal may contain abundance of vegetable food; but we are not certain that this is the caſe after putrefaction: it may by that proceſs be converted into a different ſubſtance: ſuch converſions in natural operations, are far from being rare. But if vegetable food be contained in dung, which is the moſt likely, another uſe of it is to depoſit in the ground its vegetable food, which, being diſſolved in water, is imbibed by plants, and converted into their ſubſtance. And from an experiment mentioned above it appears, that water impregnated

with

th dung, is of all the greateſt nouriſher of
nts.

A third uſe of dung is, to promote vegetation
raiſing a kindly heat in the ground. The ſun-
ys produce the ſame effect upon ground render-
black by culture; for it is a property of all
ck bodies to attract and abſorb rays of the
n *. Heat is beſt promoted by hot dung;
ich therefore ſeems the moſt proper for corn.
hether hot dung be the beſt for making a ſoil
entive of moiſture, remains to be aſcertained
experiments. But I incline to think, *that*
ng thoroughly putrefied, and conſequently cool,
in its beſt condition for graſs; as it can be e-
ally ſpread to give every plant its ſhare. It is

comes in time to be moſtly vegetable: were it inferior to natural earth, corn-countries would long ago have been rendered barren and unfit for agriculture.

From dung I proceed to other manures. Limeſtone, ſhell-marl, clay-marl, ſtone-marl, are all of them a compoſition of calcarious earth with other ſubſtances. Sand with calcarious earth makes limeſtone *. The ſhells of fiſh are almoſt entirely calcarious; and theſe ſhells ſoftened and reduced to powder in water, are called *ſhell-marl*. Clay-marl is a compoſition of calcarious earth and clay. Stone-marl is a compoſition of clay, ſand, and calcarious earth: it is the ſand that hardens it; and according to the proportion of ſand, it approaches to limeſtone or to clay-marl †.

It is obſerved above, that powdered clay is ſuſpended in water, till by the ſuperior force of gravity it fall to the bottom ‡. But, as far as I know, water has not the power of diſſolving any ſort of earth, calcined limeſtone alone excepted. A ſmall quantity of calcined limeſtone, a pound for example, will impregnate a vaſt quantity of water, with no loſs of bulk, and with a loſs of weight ſcarce perceptible. Calcined limeſtone thus impregnated, called *lime-water*, diſcovers itſelf to the taſte, though not to the eye. But this effect is confined to calcined limeſtone; for between water and calcarious earth in its natural ſtate, there appears no elective attraction: water poured on ſhell-marl comes off pure, carrying nothing along with it. Nor do clay or ſtone marl differ, even when reduced into powder.

---

* I have heard of limeſtone almoſt entirely calcarious, with little or no mixture of ſand.

† See Dr Ainſlie's accurate eſſay on marl. Edinburgh Eſſays phyſical and literary, vol. 3. art. 1.

‡ Part 2. chap. 1. ſect. 1.

Vegetation is more promoted by weak lime-water than by pure water. Two beans every way equal were ſet in pots filled with earth from the ſame heap: the one was moiſtened with lime-water, the other with pure water: the firſt was by far the quickeſt grower, and the moſt vigorous. Hence one benefit of quicklime: it converts rain into lime-water, which is a great fertilizer. This effect however is but temporary, as will thus appear. Quicklime is limeſtone deprived of its air, by the force of fire: but quicklime expoſed to the air, attracts air; and in time becomes again limeſtone as originally; conſequently unfit to make lime-water *.

Quicklime may have an effect on land as well as on plants. It is highly probable, that it opens clay-ſoil to admit water that formerly reſted on the ſurface. How otherwiſe can it be explained, that liming renders clay-ſoil drier? May it not alſo have the effect to increaſe the retentive power of a looſe ſoil? This ſeems probable, if what Young the itinerant farmer ſays hold true, that lime has a much greater effect upon looſe moor than upon any other ſoil.

---

* Edinburgh Eſſays phyſical and literary, vol. 2. art. 8.

Salt is powerful; and an overdoze of it does more miſchief than of any other manure. It is ſoluble in water, and by that means enters the mouths of plants. Its effect then muſt be the ſame with that of lime-water; and conſidering how ſparingly it ought to be laid on land, it is not obvious what other effect it can have.

As nothing can enter the mouths of plants but what is diſſolved in air or water, calcarious earth in its natural ſtate cannot enter. Yet ſhell-marl, clay-marl, ſtone-marl, compoſed moſtly of calcarious earth, contribute undoubtedly to fertility. If theſe manures cannot furniſh nouriſhment to plants directly, they muſt produce that effect indirectly, by fitting a ſoil to retain moiſture, or by preventing moiſture from acting as a cement, or by both. They certainly have the effect to keep land from hardening: they render clay looſe and ductile, and prevent its being hardened by water. Whether they increaſe the power of any ſoil to retain water, is left to experiment.

An overdoſe of ſhell-marl, laid perhaps an inch and an half or two inches thick, produces for a time large crops. But at laſt it renders the ſoil a *caput mortuum*, capable neither of corn nor ſs ; of which there are too many inſtances in otland : the ſame probably would follow, from overdoſe of clay-marl, ſtone-marl, or pounded eſtone. How is this to be accounted for ? Of e thing we are certain, that by ſuch overdoſe, ht ſoil is rendered ſo looſe, as to be moved by e wind ; and that even clay-ſoil is rendered ſo ſt, as to receive the impreſſion of the lighteſt foot every ſtep. Is it not then probable, that the l is rendered ſo open, as to retain little or no ater ? But then, how comes the land to bear y crop at all ? I am reduced to another con-cture, that ordinary ploughing once a-year, is t ſufficient to mix with the ſoil ſuch a quantity of anure ; and that an intimate mixture requires of moiſture, the conjecture will be converted into a certainty.

Quicklime is of a nature very different from calcarious earth in its natural ſtate: by the latter, land is rendered ſo looſe by an overdoſe as to hold no water: by an overdoſe of the former, it is hardened to ſuch a degree as to be impervious to water or to the roots of plants. Several ſpots in the Carſe of Gowry, are thus rendered ſo hard as to be unfit for vegetation.

The quantity of calcarious earth in clay-marl, is frequently a half, and ſometimes more. Five hundred cart-loads of clay-marl laid on an acre, are found not to be an overdoſe. Suppoſing the half to be calcarious earth, and reckoning a cart to hold ſix bolls; here are fifteen hundred bolls of calcarious earth laid on an acre. Yet a far leſs quantity of ſhell-marl has been known to render the ſoil a *caput mortuum*; though there is not diſcovered any chymical difference, between the calcarious earth in clay-marl and that in ſhell-marl: they both equally are converted into lime by the force of fire. Ignorance of nature, betrays us at every turn to doubts and difficulties. May it not be conjectured, that calcarious earth, by entering into the compoſition of an animal body, becomes a more powerful manure than when mixed with earth? There is an argument from analogy to ſupport that conjecture. Calcarious earth changes its nature by the action of fire;

and why may it not ſuffer ſome change by being made part of an animal body?

Every particular in the preſent chapter, whether relative to the plough or to manure, is perfectly agreeable to the general propoſition, that air and water with what is diſſolved in them, make the nouriſhment of plants. To cultivate land in ſuch a manner as to retain a proper quantity of air and water, is in all probability the chief or only means for making it fertile. In that view, I have all along warmly recommended pulverization; becauſe the more a ſoil is pulverized, the more water it will hold, and the more retentive it will be of it. No mode of huſbandry tends more to pulverization than horſe-hoeing; nor any inſtruments more than the brake and the harrows above deſcribed. Soils are very different with reſpect to their power of attracting and retaining air and water. Let the diligent farmer make accurate experiments for aſcertaining that difference, and for increaſing that power: no inquiries tend more to the improvement of agriculture. Our attempts to make a ſoil perpetually fertile, will probably fail; but our hopes of approaching it, may be crowned with ſucceſs.

With reſpect to the contents of this Part in general, I have to obſerve, that in natural philoſophy, of which the ſcience of agriculture is a branch, queſtions occur of two kinds. Firſt, will a certain event happen in given circumſtances?

ſtances? Second, ſuppoſing the event, what is the cauſe? To queſtions of the firſt kind, the anſwer is *fiat experimentum.* All that can be done with reſpect to the other kind, is from a number of analogous facts, to form a general rule or law of nature. Such rules at the ſame time ought to be admitted with caution, even after the cooleſt induction. But thoſe who are ardent for knowledge, cannot eaſily ſubmit to the ſlow progreſs of philoſophy: they are always in a hurry to draw concluſions, and hurry commonly leads them into error. Lord Bacon fancifully compares knowledge to a ladder. Upon the firſt ſtep particular truths are diſcovered by obſervation or experiment. The next ſtep is to collect theſe into more general truths; from which the aſcent is to what are ſtill more general. There are many ſteps to be taken before we arrive at the top; that is, at the moſt general truths. But impatience makes us endeavour to leap at once from the loweſt ſtep to the higheſt: we tumble down, and find with regret that the work muſt begin anew.

To conclude. Here is my theory of agriculture, diſplayed at full length; which is freely ſubmitted to the public, againſt whoſe judgement there lies no appeal. But let it be kept in view, that it is ſubmitted as probable only, not as certain. It would require the life of an antedeluvian, to make all the experiments that are neceſy, for piercing to the foundation, and for reving all into clear principles. My life at any e is too far advanced, for an undertaking ſo tenſive. I found an impulſe to expoſe this eory, naked as it is; and I gave way to the pulſe, becauſe I flatter myſelf, that it may afrd ſome light in tracing the operations of nature. e advantage it has above ſeveral other theos, that it can be ſubjected to the touchſtone of periments, many of which are ſuggeſted above. ſuch experiments, ſagaciouſly conducted, it ſt ſtand or fall.

# APPENDIX.

## ARTICLE I.

### IMPERFECTION OF SCOTCH HUSBANDRY.

A Man can never have thorough confidence in his road, till he be made acquainted with the by paths that miſlead him; and to be made acquainted with the errors of our neighbours, is the high way to good huſbandry. My preſent purpoſe, is to delineate the imperfect ſtate of Scotch huſbandry, not only as formerly practiſed every where, but as practiſed at preſent in moſt places. To contemplate the low ſtate of their country in the moſt important of all arts, cannot fail to excite ambition to excel in the few who are ſkilful, and to rouſe imitation in others.

Our crops in general are very indifferent; and how can it be otherwiſe, conſidering our inſtruments of huſbandry, which are ſadly imperfect? What can be expected from them in a poor ſoil, when they perform ſo little even in the richeſt? Our crops accordingly correſpond to our inſtruments.

From many examples it is made evident, that
ır ſoil and climate are capable of producing
aught horſes, patient of labour, and ſingularly
ırdy. Yet the breed is ſo much neglected, that
ey are commonly miſerable creatures, without
ength or mettle. Did landlords attend to their
tereſt, they would be diligent to improve the
eed. Why do they not reflect, that the ſame
rm-ſervants with better horſes, would double
e ordinary work? By improving the breed,
ey would draw more rent from their tenants,
thout laying any additional burden upon them.
ith reſpect to oxen, there is no care taken either
the breeding or feeding. How eaſy is it for a
ntleman to procure a good bull for his tenants?

horſes, cannot avoid ſmiling. With his goad the driver beats the horſes, and pricks every ox as he advances. He then runs forward twenty yards to beat the horſes a ſecond time and prick the oxen. Some of the oxen in the mean time, inſtead of drawing, are found hanging on the yoke, and keeping others back. It is indeed next to impracticable, to make ten weak oxen in a plough, draw all at the ſame time. Nor is this the only inconvenience. A great number of oxen by ſuch management, is requiſite for ſtocking a farm; which is not always within the reach of the moſt induſtrious. In a year of ſcarcity beſide, the beaſts are actually ſtarved. And what is worſt of all, the tenant, in order to get ſtraw for his cattle, is commonly neceſſitated to threſh out his corn, without waiting for a market, or having a granery for it.

Our farmers, led entirely by cuſtom, not by reflection, ſeldom think of proportioning the number of their working cattle, to the uſes they have for them. Hence, in different counties, from ſix to twelve oxen in a plough, without any regard to the ſoil. Seldom it is, that more than four good beaſts can be neceſſary, if the proper time for ploughing be watched.

The diviſion of a farm into infield and outfield, is execrable huſbandry. Formerly, war employed the bulk of our people: the remainder were far from ſufficiently numerous for cultivating even

t ſmall proportion of our land which is capable
the plough. Hence extenſive farms, a ſmall
rt of which next the dwelling, termed *in-*
*ld*, was cultivated for corn: the remainder,
med *outfield*, was abandoned to the cattle, in
pearance for paſture, but in reality for ſtarving.
e ſame mode continues to this day, without
ny exceptions, though neceſſity cannot be
aded for it. But cuſtom is the ruling princi-
that governs all. Sad is the condition of the
ouring cattle; which are often reduced to
ſtles, and withered ſtraw. A ſingle acre of
clover would give more food than a whole out-
ld; yet how common is the complaint of te-
nts, that they are diſabled from carrying on
ſummer-work, for want of food to their

ſtones, thrown oft the tilled land; and huſbandmen were led by imitation to leave ſuch ſtrips, even where there were few or no ſtones.

The proper time for ploughing or harrowing, is when the ſoil upon ſtirring moulders into ſmall parts. This is not obſerved by farmers, ſo carefully as it ought to be. How common is it to ſee even a clay ſoil ploughed, when ſoaked in water; or when hard like a ſtone. Little attention is given to what may be termed *the froſt-preparation*; which is, to open the ground before winter, in order that froſt may pierce deep and mellow the ſoil.

Shallow ploughing is univerſal, without the leaſt regard to deepneſs of ſoil. The temperance of our people may be a proper ſubject for ironical praiſe; for though nature affords commonly ten or twelve inches of ſoil, they are humbly ſatisfied with a half or third.

Ribbing is a general practice, though the ſlighteſt reflection is ſufficient to make it evident, that to leave half of the land untilled, muſt be wretched huſbandry.

Summer-fallow has of late years crept in, and is now common in three or four counties. In the reſt of Scotland, for want of ſummer-fallow, there is a continual ſtruggle for ſuperiority, between corn and weeds. Do not ſuch provoking farmers ſee, that it is fruitleſs to manure land over-run with weeds? Do they not obſerve, that manure they beſtow encourages weeds as ch as corn; or rather, that it envigorates the ds to deſtroy the corn? Make a progreſs ugh Scotland, you ſee ſtubborn weeds in e-y corner ſcattering their ſeed, and fouling the und more and more. It is an eaſy work to down weeds before they go to ſeed. Would one think, that work ſo eaſy would never neglected? and yet it is never done. A tch farmer behaves worſe than Eſau: the lat-got a meſs of pottage for his birthright; the mer ſurrenders his to weeds, without any re-npenſe.

There is ſcarce ſuch a thing practiſed, as to row before ſowing. The ſeed is thrown into gh uneven ground, and the half is buried.

the ſheaf ſo cloſe, as with difficulty to admit his finger. The weather muſt be extremely favourable, if it be ſufficiently dry in a fortnight, to be ventured in a ſtack; it commonly muſt ſtand in the field three weeks. Let any one conſider the riſk of the crop in brittle weather, ſuch as happens ordinarily in autumn. Nor is this all. Such ſheaves are not only unhandy, but are apt to break looſe in carrying to the ſtack, or from the ſtack to the barn. A ſheaf ſhould never exceed what can be ſlightly bound together with a ſingle length of the corn: it is fitter to be ſtacked in a week, than ordinary ſheaves in three.

No branch of huſbandry is leſs underſtood, than manure. A dunghill is a very improper bed for corn: lime and marl are ſtill more improper; for nothing will grow on them. Hence it is apparent, that the intimate mixture of manure with the ſoil, is the great circumſtance for vegetation. In order to that end, the ſoil ought to be highly pulverized, and the manure divided into its ſmalleſt parts. With reſpect to dung in particular, it ought to be carefully mixed in the dunghill, not neglecting to divide by the hand any lumps that may be in it. Let our farmers ſay, whether they are ſo accurate. Nothing more ordinary, than heaps of dung withering in the field, incapable to be intimately mixed with any ſoil. Nothing more ordinary, than dung laid on the dunghill in barrowfuls, without being ſpread or mixed with what was there before.

A potato is a moſt uſeful plant, and, when properly cultivated, affords a plentiful crop. It is a great reſource to the labouring poor, being a nouriſhing food that requires very little cooking. We have been afflicted of late years with very bad ſeaſons, which, but for that reſource, muſt have driven many of our people from their native country. Yet potatoes to this day continue to be propagated in lazy-beds. Expert farmers, not many in number, raiſe them with the plough at the twentieth part of the expence. This method has beſide two other advantages: it leaves the ſoil in the beſt ſtate for ſubſequent crops; and the potatoes are more palatable than what are raiſed in a lazy-bed.

Swine make a profitable article of huſbandry, very little attended to in Scotland. They are fed at a ſmall expence, and yet make moſt nouriſhing food. Every perſon who has a cow, ought alſo to have a pig. This is univerſal in England: it is creeping into Berwickſhire, but in few other places as far as I know.

Very few farms in Scotland are juſtly proportioned: ſome are too ſmall; the bulk of them too large. The former lead to a habit of idleneſs; the latter into a habit of ſlovenlineſs, by want of power to do juſtice to every part. There is not an article in huſbandry more eſſential, than to adjuſt a farm to the ſkill and ability of the tenant.

## ARTICLE II.

### A BOARD FOR IMPROVING AGRICULTURE.

IT is a maxim in politics, that every country will be populous in proportion to the fertility of its ſoil; upon which account, agriculture is the moſt uſeful of all arts. And yet it is a ſad truth, that in Scotland, that art has not advanced far beyond the firſt ſtage of its progreſs. In England indeed, it has made a much greater progreſs; and yet far inferior in perfection to Engliſh manufactures and commerce. Agriculture is carried on every where without a ſchool; and for that reaſon, it is commonly thought to require no ſchooling. Can a Britiſh miniſter embrace any meaſure more patriotic, than to encourage agriculture and its profeſſors? No other meaſure would ſo effectually aggrandize Britain. A ſmall ſhare of the money and attention beſtowed on raiſing colonies in America, would have done wonders at home. And yet, mark the ſtriking difference: our arts are our own, which we never can be deprived of while induſtry remains: in the very conſtitution of our colonies, on the contrary, there are cauſes of ſeparation, that grow daily

ly ſtronger and ſtronger; a wide-extended
ntry, a fertile ſoil, navigable rivers, and a
wing population. I diſregard the preſent re-
lion of our Americans: for they will ſoon be
uced to obedience. But as they derive from
tain high notions of liberty and independence,
l as they are daily growing into power and o-
ence, the æra of their total ſeparation, cannot
at a great diſtance: it is indeed abſurd to
k, that a great nation, in the vigour of pro-
ity and patriotiſm, can be kept in ſubjection
a nation not more powerful, enervated by lu-
y and avarice. Let us not however deſpond;
if agriculture be carried on but to the perfec-
that our ſoil and climate will readily admit,
ill amply compenſate the loſs of theſe colo-

fore the union of the two kingdoms, our people were ſo benummed with oppreſſion, that the moſt able director would have made no impreſſion. Freedom has braced their nerves, and has made them take heart to be induſtrious. They liſten to inſtruction: let them perceive their intereſt, and they will chearfully practiſe what they are taught. A board for agriculture, would among us have wonderful ſucceſs in many important articles. Conſidering the quantity of waſte land even in our beſt-cultivated counties, it is not too ſanguine to hope, that our corn-crops might be doubled. What a bleſſing would this be to Scotland, which for many years has been reduced to import great quantities? Our horſes and horned cattle, are far inferior to what may be produced by good management. Our ſheep weigh not above ten pounds a quarter, nor their wool above two pounds. The ſoil by good culture would feed ſheep to the weight of twenty-four pounds a quarter; carrying from ſix to ten pounds of wool, which would be a valuable acquiſition to the woollen manufacture. Lambs, in ſeveral inſtances, have been advanced to twelve ſhillings a-head, and wedders to forty ſhillings. Theſe are but a ſpecimen of the various improvements that might be perfected by ſuch a board.

The plan I have in view, is ſimple. Let the board conſiſt of nine members, the moſt noted for ſkill in huſbandry, and for patriotiſm. As I

ppoſe no reward to theſe gentlemen, but the
nour of ſerving their country, the choice will
be difficult : in lucrative employments, perſo-
connections have much greater influence than
rſonal merit ; and it is avarice only that ſets peo-
at variance. Where perſonal merit is the ſole
ject of choice, there is ſeldom much difference
opinion. To eaſe the board in the laborious
anch of their buſineſs, they ought to be pro-
led with an able ſecretary, to minute their pro-
edings, to write their diſpatches, and to carry
their correſpondence, foreign and domeſtic.
punctual attendance is neceſſary, the good be-
viour of ſuch an officer may well intitle him to
alary of L. 100 yearly ; with the addition of

The things neceſſary to be undertaken by this board, at the commencement of their operations, will require much labour and ſagacity. The firſt is, to make out a ſtate of the huſbandry practiſed in the different counties; in which notice muſt be taken of the climate, of the ſoil, of the mode of cropping, and of the inſtruments of huſbandry, noting the prices of all the particulars that enter into farming. The next is a paper of inſtructions for improving huſbandry, ſuited to the ſoil and ſituation of every diſtrict; with ſpecial reference to the preſent practice, ſhowing where it is defective or erroneous, and propoſing the cheapeſt and moſt effectual corrections. Theſe preliminaries being ſettled, the ordinary buſineſs of the board, may be carried on eaſily and comfortably. In the firſt place, there is a neceſſity for an inſpector, named by the board, to make a progreſs from time to time in ſucceſſive places, for reporting the progreſs of the improvements directed, and for giving inſtruction in caſes that cannot ſo clearly be put in writing. In this progreſs, ſpecial notice ought to be taken of the beſt-conducted farms, whether by landlords or tenants. A few ſilver medals beſtowed on the moſt deſerving, will rouſe emulation in all, and promote induſtry. Second, this board will conſider it as a capital branch of buſineſs, to anſwer queries, and to ſolicit a correſpondence with men of ſkill. Third, they ought carefully to inform

emſelves of every invention that tends to im-
ove the art, and to publiſh what they think uſe-
l. Fourth, premiums ought to be propoſed,
d diſtributed among thoſe who profit the moſt
the inſtructions of the board. Theſe premi-
ns ought to be ploughs, harrows, carts, con-
ucted after the beſt models; which beſide ex-
ing induſtry, would be a means to introduce
e beſt huſbandry-inſtruments. Fifth, in no o-
er reſpect would a board of agriculture be ſo
eful, as in directing proper experiments. A-
iculture, though the prime of arts, is far from
rfection in any country. This in part is ow-
g to its complex nature; but chiefly, to the
ngth of time that is neceſſary to aſcertain, by a

buſineſs, premiums ought to be propoſed, lucrative as well as honorary.

To make the board proceed with ſpirit, a book or pamphlet ought to be publiſhed annually, containing the tranſactions of the board, during the preceding year. The profit of the work, is a perquiſite to the ſecretary; which will encourage him to beſtow his utmoſt ſkill in the compilation.

To procure public favour, men of character and knowledge may be introduced by the members at their monthly meetings, to aſſiſt in their deliberations.

The choice of proper members, is the capital point: the whole depends on it. The choice is the more difficult, as it muſt be confined to gentlemen who reſide in Edinburgh, ſome part of the year; becauſe from others, punctual attendance cannot be expected. It would be unſafe to leave the choice to members of parliament; who, even againſt their private ſentiments, are obliged to ſolicit for their friends and voters, without regard to merit. The choice muſt not be left abſolutely to the chief miniſter; who, at ſuch a diſtance, is ſeldom perſonally acquainted with the beſt qualified. The ſafeſt method I can think of is, that the juſtices of peace of each corn-county, ſhould at a quarter-ſeſſions name one. Out of theſe, the miniſter chuſes the nine members.

The choice of a member to ſupply a vacancy, is a matter no leſs delicate. A ſociety of gentle-

men,

n, who ſerve for honour not for profit, appear
intitled to chuſe their companion. But to a-
faction, which would be ruinous in ſuch a
ety, the choice ought to be unanimous. The
ent of a ſingle member, need not be regarded;
if two diſſent, the choice muſt be in the
wn. If a member be abſent three ſucceſſive
nthly meetings, without an excuſe approved
the board, he is to be held as having deſerted
office, to make way for the election of a new
nber.

The election of a ſecretary is a point ſtill more
cate. The board ought naturally to have the
ice of their own ſecretary; but in caſe of a di-
on, the diſſent of three from the other ſix,
transfer the election to the crown.

ſum would be a temptation to miſapply it. Therefore, no more ought to be put into their power, than what is barely ſufficient to carry on the management with ſucceſs. Beſide the ſecretary's ſalary, L. 500 yearly diſcreetly diſtributed may be ſufficient. And I boldly affirm, that ſuch a ſum cannot be laid out with more advantage, whether the public be regarded, or the good of a valuable portion of our people.

The houſe poſſeſſed by the truſtees for manufactures, will afford good accommodation to both ſocieties; and ſeveral of the acting truſtees, are qualified to make a figure in both.

Zeal for the proſperity of Britain, makes me ardently wiſh to have this plan extended to England. The Engliſh enjoy the reputation of being excellent farmers; and ſo they are, compared with their neighbours in France, Italy, and Spain. They are however far, very far, from the perfection of the art. A board for agriculture is indeed leſs neceſſary in England, than in Scotland; but that England would be greatly profited by ſuch an inſtitution, will be acknowledged by every one who is acquainted with Engliſh agriculture. I appeal to Mr Young for the following facts, extracted from his different tours; which, at the ſame time, are but a ſpecimen of much wrong practice mentioned by him.

Seldom is a plough ſeen in England with fewer than four horſes, nor is it always confined to that number;

nber ; and yet, ſeldom are more than two
ſes neceſſary, if the plough be well conſtruct-
A great ſum is thus expended upon ſuper-
ous horſes, which wounds the public by unne-
ſary conſumption, is hurtful to landlords by
ening their rent, and retards the progreſs of
bandry. Among numberleſs inſtances, I men-
n the Iſle of Thanet, where the ſoil is a light
m on a chalky bottom ; and yet with four
ſes in each plough, they ſeldom pierce deeper
n three inches, which is ſcratching inſtead of
ughing.

The number of draught-cattle is ſeldom pro-
tioned, with any accuracy, to the extent of
farm. Frequently, no fewer than *eight*
ſes and as many oxen, are employed in a farm

Alſo, fallow, wheat, oats, barley. Alſo, barley, oats, oats. Alſo, turnip, barley, oats, oats. Even the beſt ſoils muſt be exhauſted in time, by ſuch oppreſſive cropping.

The great advantages of horſe-hoeing, are a crop, and at the ſame time a ſubſtantial fallow. And yet, horſe-hoeing, though invented in England, is not practiſed there. Many farmers do not even hand-hoe their turnip-crop; and many neglect to hand-hoe their bean-crop, after being ſown in drills.

The proper management of artificial graſſes, is far from being common. Of all graſſes, red clover is the moſt beneficial; and yet there are farmers, not a few in number, who baniſh red clover, as hurtful by foſtering weeds. It has indeed that effect, if allowed to grow three or four years; but why not change it every year? It is not unfrequent to ſee a field left to be covered with natural graſs. By this ſlovenly practice, the crops are not only ſcanty, but of a bad kind. In Derbyſhire particularly, a field, after three ſucceſſive crops of oats, is abandoned to nature. Worſe huſbandry is not to be met with, among the moſt ignorant farmers in Scotland.

Draining indeed is common, but conducted with little ſkill. There is no ſuch thing known in England as drains at the ſurface made with the plough; though ſuch drains poſſeſs the advantages of being cheap, effectual, and perpetual.

e foregoing errors and imperfections, with
dleſs number more, would be remedied by
ard, eminent for patriotiſm, and for ſkill in
ulture; and farmers would fairly be direct-
the road that leads to the perfection of their
Population and induſtry would be the con-
nces, with a great increaſe of the public re-
e. England would become ſo proſperous
powerful, as to ſuffer little diſtreſs from the
f its American colonies, ſhould that ungrate-
eople ſucceed ultimately in a total defection.

## ARTICLE III.

## ERAL HEADS OF A LEASE FOR A CORN-

be truſted with unlimited powers. But ſuch powers would be no leſs deſtructive to the generality of tenants themſelves, than to their landlords. Tenants, therefore, like kings, muſt be fettered; but in what manner, is a queſtion no leſs difficult than uſeful. They ought not to be ſo fettered as to bar improvements; nor left at liberty to do miſchief.

Before entering into particulars, it muſt be obſerved, that different ſituations with regard to manure, ſoil, and climate, require different modes of huſbandry. All that can be done in an attempt like the preſent, is to ſuggeſt a few general rules, for a landlord to chuſe upon in granting leaſes. It is his buſineſs to judge which of theſe rules will beſt fit his ſituation.

The firſt reſpects the time of endurance, which, though an important article, is unneceſſary to be enlarged on here. It is believed to be now the univerſal opinion, that without a long leaſe, it is vain to hope for an improving tenant. The moſt approved time of endurance, as the likelieſt to prevent waſte, is to fix a time certain, ſuppoſe nineteen or two nineteen years; and to add the life of the tenant who is in poſſeſſion at the expiry of the time certain. A man never loſes hope of living longer; and he will never run out ground, that he hopes yet to be long in poſſeſſion of. By this means, the tenant is deluded into a courſe of management, equally profitable to himſelf and to his landlord. But what, if, after liming or other expenſive manure, the tenant happen to die ſuddenly before reaping any profit? With a view to that event, let there be a clauſe in the leaſe, for paying to his repreſentatives what ſum the tenant's profit has fallen ſhort of the expence.

Second, Aſſignees and ſubtenants ought to be excluded. For where a tenant has it in his power to make his leaſe a ſubject of commerce, he will be ſparing in laying out money on improvements.

Third, Whether the rent ought to be paid in corn or money, depends on circumſtances. Corn-rent cramps the tenant in his management; for it obliges him to ſow yearly corn of the ſame kind with what he pays. Money-rent, on the contrary, promotes good culture, in order to produce the weightieſt grain, the benefit of which accrues entirely to the tenant. There is an additional reaſon for money-rent, that the tenant, by prudence and patience, can draw a better price for his corns at the home-market, than his landlord can. The rent therefore ought to be paid in money, unleſs where there is a ſuperfluity of corn for exportation; which can be managed with more advantage by the landlord, who has all his farm-victual to export, than by a tenant who has but a ſmall quantity.

Fourth, In this country, the profit of graſs is to this day not underſtood, but by a few. Corn is the object of the generality; and that wrong bias ought to be rectified, by a clauſe confining the tenant to a certain proportion of his ground in corn, a third, for example, or a half. There cannot be a general rule; becauſe it varies with the nature of the ſoil, and ſtill more with the opportunity of manure. But to give room for extraordinary improvements, an addition to the proportion of corn may be indulged, upon condition of paying ſhillings additional rent for every acre above the proportion originally agreed on.

Fifth, A clauſe prohibiting white corn-crops to be taken in immediate ſucceſſion, will be an effectual bar againſt impoveriſhing the land. Peaſe, beans, turnip, cabbage, and potatoes, are profitable crops; and red clover may be more profitable than any of them, by feeding all the farm-cattle upon it, which will ſave many acres of paſture. This and the foregoing rule, without any other precaution, will in all events ſuffice to keep the ground in good heart.

Sixth, The following, or ſome ſuch clauſe, will excite a tenant's higheſt induſtry to improve his farm to the utmoſt, ſuppoſing it to be only for nineteen years. At expiry of the leaſe, the tenant ſhall be intitled to a ſecond nineteen years, upon paying a fifth part more of rent; unleſs the landlord give him ten years purchaſe of that fifth part. The rent, for example, is L. 100. The ant offers L. 120. He is intitled to continue poſſeſſion a ſecond nineteen years at the advan- rent, unleſs the landlord pay him L. 200. If offer a ſtill higher rent, the landlord cannot n him out, unleſs he pay him ten years pur- ſe of that offer.

Seventh, As both landlord and tenant are con- ned in preſerving the fences, both ought to cur in the expence. Therefore, let the care the fences be truſted to the landlord's hedger; whatever work is beſtowed on the tenant's ces, ſhall be paid to the hedger at ſo much per . Where the preſervation of the fences is left rely to the tenant, he turns careleſs, and does gs by halves; where it is left entirely to the for what are left at the tenant's removal, or to allow him to diſpoſe of them.

Ninth, In a tenant two things are required; firſt, ſkill and induſtry for managing the farm; and, next, money for ſtocking it ſufficiently, without which, ſkill and induſtry avail not. With reſpect to both, our common law errs groſsly. As to the firſt, a farm can never be prudently managed by a plurality; for there it holds, ſo many men ſo many minds; and yet, by law heirs-portioners ſucceed in a leaſe, as well as in other heritable ſubjects. To remedy the common law in leaſes that go to heirs, let it be provided, that the eldeſt heir-female ſhall ſucceed without diviſion; or that the landlord ſhall have it in his power to chuſe any of the heirs-female he pleaſes.

With reſpect to the other, our common law is altogether injuſtifiable, as it gives the whole ſtocking to the other children, leaving the bare leaſe to the heir; without means to ſtock the farm anew, unleſs other heritable funds be left beſide the leaſe, which ſeldom is the caſe. This is cruelly unjuſt, both to the heir and to the landlord. The heir has not even the benefit of collation, becauſe it would bring a plurality of conjunct leſſees upon the landlord. The heir therefore is in effect totally diſinherited; as a bare leaſe is of no ſignificancy without money or credit. The injuſtice with regard to the landlord is no leſs flagrant, who has thus a tenant impoſed on him,

from

m whom no rent can be expected. To pre-
ve the leaſe and ſtocking united, which muſt
done by paction ſince law is defective, let a
n be ſpecified in the leaſe, ſuch as may be ſuf-
ent for ſtocking the farm; which ſum the heir
ll be intitled to demand from his predeceſſor's
reſentatives, unleſs the farm be left to him
h a ſtocking equivalent in value. And the
uſe may be conceived in ſome manner like
at follows. "And conſidering that if the ſaid
A. B. die during the currency of this tack, his
whole moveables, not excepting the ſtocking
of his farm, fall by law to his other children,
by which it may happen, that nothing is left to
the heir but the naked tack, without a ſtock-
ing or money to purchaſe it; therefore, to

a leaſe for nineteen years to be agreed on at a rent of L. 50, let one, two, or three years be added, binding the tenant to pay an additional rent for theſe years, a half more for example, or double. But with a proviſo, that the tenant ſhall be at liberty to remove at the end of the nineteen years, upon notifying to his landlord, three months before, his intention to remove.

## ARTICLE IV.

### Plants and Animals compared.

ANimals are provided with various powers correſponding to their deſtination; ſome for ſupporting the animal frame, ſome for gratifying deſire. Plants, in all appearance, have no feeling of pleaſure nor of pain; and conſequently no deſires. But they are endowed with powers for preſerving vegetable life, as animals are for preſerving animal life. Doth not the ſpringing of the ſeed, the motion of the ſap, the production of leaves, flowers, fruit, &c. proceed from a power in plants; as the beating of the heart, the circulation of the blood, &c. proceed from a power in animals? There is not an argument for the latter that does not equally conclude for the former.

Next, as to the power of loco-motion. That
ver is more perfect in animals; but plants poſ-
a ſhare of it, ſuch as is neceſſary for their
l-being: they grow both upward and down-
rd; and in their progreſs to maturity, they
continually occupying new parts of ſpace.
nts, it is true, cannot, like animals, go out of
rms way; but it is curious to obſerve, how
y exert that ſhare of loco-motion they are en-
wed with, to avoid harm. Upon the ſlighteſt
ich, the ſenſitive plant ſhrinks back and folds
its leaves, ſimilar to a ſnail, which on the
hteſt touch retires within its ſhell. A new ſpe-
s of the ſenſitive plant has been lately diſcover-
If a fly perch upon one of its flower-leaves,
cloſes inſtantly, and cruſhes the inſect to death.

cloſes them at ſunriſing. All the trefoils may ſerve as a barometer to the huſbandman: they always contract their leaves on an impending ſtorm. Some plants follow the ſun, ſome turn from it. Moſt diſcous flowers follow the ſun; which has been long obſerved of the ſun-flower, while young and tender. The leaves of the mallow tribe, follow daily the courſe of the ſun, from eaſt by ſouth to weſt. Many plants on the ſun's receſs vary the poſition of their leaves; which is ſtiled the *ſleep of plants*. Every botaniſt, after Pliny, has obſerved this in a field of clover. A ſingular plant was lately diſcovered in Bengal. Its leaves are in continual motion all day long; but when night approaches, they fall from an erect poſture down to reſt.

A plant has a power of directing its roots for procuring food. A quantity of fine compoſt for flowers, happened to be laid at the root of a full grown elm; where it lay neglected three or four years. When moved, in order to be carried off, there appeared a net-work of elm-fibres ſpread through the whole heap. No fibres had before appeared at the ſurface of the ground. The red whortleberry, a low evergreen plant, grows naturally on the tops of our higheſt hills, among ſtones and gravel. This ſhrub was planted as an edging to a rich border, under a fruit-wall. In two or three years, it over-ran the adjoining deep-laid gravel-walk; and ſeemed to fly from the

border, in which not a ſingle runner appear-
. Were our London aldermen equally tem-
rate, they might partake of turtle and veniſon
h ſafety. An effort to come at food in a bad
ation, is extremely remarkable in the follow-
inſtance. Among the ruins of Newabbey,
merly a monaſtery in Galloway, there grows
the top of a wall, a plane-tree about twenty
t high. Straitened for nouriſhment in that
ren ſituation, it ſeveral years ago directed roots
wn the ſide of the wall, till they reached the
und ten feet below; and now, the nouriſh-
nt it afforded to theſe roots during the time of
ir deſcending, is amply repaid, having every year
ce that time made vigorous ſhoots. From the
of the wall to the ſurface of the earth, theſe

to their natural poſition. What better can an animal do for its well-fare? A root of a tree, meeting with a ditch in its progreſs, is laid open to the air. What follows? it alters its courſe like a rational being, dips into the ground, ſurrounds the ditch, riſes on the oppoſite ſide to its wonted diſtance from the ſurface, and then proceeds in its original direction. Lay a wet ſpunge near a root laid open to the air: the root will direct its courſe to the ſpunge. Change the place of the ſpunge; the root varies its direction.

Such animals as are naturally weak, exert their ſelf-motive power to remedy that defect, by joining in ſociety. Plants are not capable of ſociety; but ſeveral of them ſupply their natural weakneſs, by exerting their ſelf-motive power in a manner that would do honour to an animal. The economy of ſcandent plants is in that reſpect admirable. Obſerve how they direct their courſe to any thing that can ſupport them. Thruſt a pole into the ground, within a moderate diſtance: a ſcandent plant directs its courſe to the pole, lays hold of it, and riſes on it to its natural height. A honeyſuckle proceeds in its courſe, till it be too long for ſupporting its weight; and then ſtrengthens itſelf by ſhooting into a ſpiral. If it meet with another plant of the ſame kind, they coaleſce for mutual ſupport; the one ſcrewing to the right, the other to the left. If a honeyſuckle twig meet with a dead branch, it ſcrews from the right to the left. The claſpers of briony ſhoot in a ſpiral, and lay hold of whatever comes in their way for ſupport. If after completing a ſpiral of three rounds they meet with nothing, they try again by altering their courſe.

Nature has alſo provided a remedy for trees that grow too faſt in a fruitful ſoil. Some form the upper part of the weak and tender ſtem into a ſort of ſcrew; which is ſtronger than a ſtreight line. This among others is the caſe of the larix. A tree bent by too faſt growing, puſhes out all its lateral branches on the convex ſide, in a direction between perpendicular and horizontal, as if it were expanding wings to raiſe itſelf up. There are at Kames, elms that when twenty feet high were bent down by overgrowing, the top almoſt touching the ground. In that poſition they continued ſeveral years, till they were raiſed by lateral branches as above deſcribed; and they are now perfectly erect.

The economy of ſome water-plants is ſingular. As the *farina fœcundans* cannot operate under water, a water-lillie, be the water deep or ſhallow, puſhes up its flower-ſtems till they reach the ſurface, and then flowers in open air.

The compariſon between plants and animals, may be carried a great way farther. There are powers in every animal, to ſtruggle for health by expelling diſeaſes. All that a ſurgeon can do in the caſe of a broken bone, is to reſtore it to its natural poſition. Nature performs the cure, by pouring into the broken part a liquid matter, which, hardening into bone, unites the parts firmly together. Sydenham, prince of phyſicians, defines a fever to be an effort of nature to throw out of the body what is noxious. The proviſion of nature for reſtoring a maimed animal, is remarkable in the lobſter and crab. The feeling of theſe animals is at the tip of their claws. When the tip of a claw is bruiſed or broken, the whole claw falls off, and another in its ſtead quickly arrives at maturity *. Are not yawning, ſtretching, ſighing, weeping, efforts of nature to throw off a burden? There are ſimilar powers in plants to remedy what is noxious. A wound in a tree is cured like a wound in an animal: the ſeparated parts unite; and the tree is covered with bark as formerly. If part of a branch or of a root be cut off, the want is ſupplied by a number of ſmall ſhoots, iſſuing from the place where the cut was made.

The foregoing facts exhibit a ſtrong reſemblance between plants and animals, with reſpect

---

* Bonnet is ſtrangely puzzled to account for this fact. He ſuppoſes, that numberleſs embryos of every portion of every claw of a lobſter, were originally created; that every lobſter is full of ſuch embryos, ſo artificially placed, as that when part of a claw is broken off, an embryo correſponding to that part is at hand, which is put in motion in order to repair the loſs.

the ſelf-motive power. The motion of the
art in animals, of the arteries, of the inteſtines,
the lungs, cannot be explained by any known
w of mechaniſm; and as little, the ſpringing of
e ſeed in plants, the oſcillatory motion of the
p, the production of leaves, flowers, fruit, &c.
heſe various effects proceed from a ſelf-motive
wer in plants, as well as in animals; and by
at power chiefly, are organized bodies diſtin-
iſhed from brute-matter. A plant exerts this
wer without conſciouſneſs, becauſe conſciouſ-
ſs is not the property of any plant. But ſo far
e reſemblance holds, that an animal, though
dowed with conſciouſneſs, exerts the ſame power
ndly, without being conſcious of the exertion.

eat, and cold to take ſhelter, without reflection or foreſight. Inſtinctive actions differ from thoſe above mentioned, being attended with conſciouſneſs, though not with foreſight: a duckling, even where hatched by a hen, goes inſtinctively into water: it knows where it is going; but knows not for what end. To inſtinctive powers in animals, there are no reſembling powers in plants: we admit not in plants any knowledge or conſciouſneſs. Far leſs do plants exert any actions that reſemble voluntary actions in animals.

After much labour beſtowed on botany, and many volumes compoſed on that ſubject, it appears very little advanced above infancy: no other ſcience has made ſo ſlow a progreſs. I praiſe the diligence of our botaniſts: ſome of them have great merit. But, as far as I underſtand, their ſtudy has been moſtly confined to give names to plants, and to diſtribute them into claſſes; not by diſtinguiſhing their powers and properties, but by certain viſible marks. This is an excellent preparation for compoſing a dictionary: but it leaves us in the dark as to the higher parts of the ſcience, ſuch as are the moſt proper to engage a thinking and rational mind. No perſon who has given attention to the conduct of Providence, can entertain any doubt, that the powers and properties of plants are given for beneficial purpoſes. Have we not reaſon to hope, that theſe purpoſes will be unfolded, when botaniſts, tired of dictio-

ry-making, ſhall direct their enquiries to the
her branches of the ſcience. Then will botany
come an intereſting ſcience, not inferior to any
ıer in dignity and importance: then ſhall we
ve occaſion to admire more and more the wiſ-
m of the creation. How pleaſant to have it ob-
ved, that the humbleſt plant is framed with no
s ſkill, than the moſt elevated animal!

So much upon a compariſon between plants
d animals with reſpect to motion. Another
mpariſon occurs, no leſs curious, and ſtill more
ereſting, that the external frame is nicely ad-
ted to the internal, ſo as to accompliſh in per-
tion the ends of Providence. No one who has
died natural hiſtory, but muſt be ſenſible of this

would be a miſerable creature: he would always be contriving, but without power to execute *.

This truth would be equally evident in plants, were their nature and qualities as well known as of animals. A plant is an organized being, as well as an animal: if the external frame of the latter be adapted to its internal frame, can we doubt of the ſame economy with reſpect to the former? In whatever manner particles of matter are formed into an organic body, of which we know nothing, one thing is certain, that the organic body acquires a nature very different from that of its conſtituent particles, and alſo new powers qualifying it for acting according to its deſtination. The power of gravity, of reſiſtance, of continuing motion, eſſential to matter in general, will never by any combination produce any thing but motion; but the power of producing a body ſimilar to itſelf, inherent in all organic bodies, is far ſuperior to the powers mentioned; and therefore muſt be a new power added in the formation of every organic body.

As plants were originally created of many ſpecies, each ſpecies has powers peculiar to itſelf, which preſerve the different ſpecies diſtinct, and

---

* Wonderfully ſhallow is the reflection of Helvetius, that the only excellency of a man above a horſe, is his having fingers.

nſequently preſerve uniformity among the indi-
luals of the ſame ſpecies. Theſe powers, va-
ouſly modified in every different ſpecies, are ex-
ted in the propagation of new plants, with leaves,
wers, ſeed, &c. peculiar to each ſpecies. And
a perfect agreement between the external and
ternal frame of plants, as well as of animals, is
ndoubtedly the plan of nature, incapable of de-
ct or overſight, it may be taken for granted,
at each external part contributes to the well-
ing of the plant, and that any alteration would
hurtful: to exchange, for example, the leaves
an oak and an aſh, would be prejudicial to
th, perhaps deſtructive. Were we acquaint-
l with the nature of different plants, we ſhould

conjectures, which we may hope for, will give ſome entertainment to the curious inquirer. If we deſpair of acquiring ſuch knowledge in the internal conſtruction of plants, as to explain all the differences above mentioned, we may at leaſt hope to diſcover facts that will illuſtrate the agreement between external and internal ſtructure. I venture to ſuggeſt an inſtance or two. Some plants draw moſt of their nouriſhment from the ſoil, ſome from the air. Do not ſmall leaves correſpond to the former, and large leaves to the latter? I have ſeen a houſe-leek growing vigourouſly on a dry mud wall, excluding rain entirely from the roots. But it has thick leaves, and many in number, which fit it for drawing its nouriſhment from the air. It is not the light, nor the ſun, that make plants grow erect, but the appointment of nature. A ſcandent plant has a tendency to grow erect like other plants; but as it is too weak to ſtand erect, it has tendrils or claſpers, to lay hold of any ſupport within reach. Why do certain trees never ſhed the leaf, even in this country? Is it not a rational conjecture, that they are fitted by nature to bear cold, and that the cold of this climate does not ſuſpend their power of drawing nouriſhment all the year round?

Were this important branch of botany diligently ſtudied, I fondly hope, that conſiderable

inſight

ight might be obtained into the nature of nts, and poſſibly into their medicinal effects. that ſtudy, the natural hiſtory of plants may come no leſs inſtructive and entertaining, than at of animals.

## ARTICLE V.

## PROPAGATION OF PLANTS.

EQuivocal generation is by all philoſophers exploded from animal life; but ſome continue heſitate with reſpect to vegetable life. Ani- ls, ſay they, wandering from place to place, ſtock the earth with their progeny; but plants

To account for theſe ſingular facts, it is held, that both plants and animals were originally organized atoms or embryos, having all neceſſary parts in miniature; that the earth, the water, the air, are full of ſuch atoms, which begin not to unfold themſelves into plants or animals, till they happen to meet with a proper *matrix* or *nidus*; that in their original ſtate, they are too minute for any of our ſenſes, but that they become viſible by expanſion.

What means were employed at the creation to cover the earth with plants, may be conjectured, but is far beyond the reach of evidence. It is to me a natural conjecture, that a number of plants and animals were originally created, and endued with proper powers of generation; and that from theſe, all the plants and animals exiſting in the world are deſcended. In that belief, I cannot ſubmit to organized atoms, becauſe there is no evidence of them, and becauſe they are unneceſſary. To illuſtrate this conjecture, I add the ſubſtance of a letter I had the pleaſure to receive from an eminent naturaliſt *.

"The doctrine of equivocal generation was
" univerſally admitted, till about 130 years ago;
" not, however, ſo much by the ancients, as by
" the half-enlightened moderns. They ſaw
" mites in cheeſe; and myriads of flies and creep-

---

* Dr Walker miniſter of Moffat.

ing things in a dunghill, or a putrid marſh. Ignorance of the natural hiſtory of theſe animals, made way for the conjecture, that they were mere ſpontaneous productions, the effect, not of generation, but of corruption. This doctrine indeed was confined to theſe poor inſects, and never was extended to a lion or a horſe. They did not advert, that to form a maggot and an elephant, require equal power and wiſdom. The ſame diſtinction was carried into the vegetable kingdom. Becauſe no ſeed appeared to the naked eye in a fern, a muſhroom, or in any of the moſs-tribe, it was aſſerted, that none exiſted; and while the oak and the laurel were dignified with generative

" imitated by art, in cuttings, grafting, and ino-
" culation. Some late experiments are mention-
" ed of propagating trees by planting their leaves;
" but I do not believe it.

" Plants, it is true, are deſtitute of locomo-
" tion; and by means of ſuckers and layers, they
" can only cover contiguous ſpots. But nume-
" rous and wonderful are the expedients, practi-
" ſed by nature to diſſeminate plants. Some ſeed-
" veſſels burſt with an exploſive force, and throw
" the ſeed to a diſtance. This is the caſe of our
" whin: did the ſeeds fall perpendicularly down,
" they would be ſuffocated in the heart of an im-
" penetrable buſh. Some ſeed-veſſels open not
" till wet with rain; but the ſeeds are found to
" ſuffer by drought, and to require immediate
" moiſture when ſown. The aſh, and the plane,
" have heavy ſeeds; but theſe ſeeds are ſupplied
" with wings: a gale of wind carries them from
" their lofty ſituation to a diſtance, and they re-
" main on the tree till the gale comes. The ſeeds
" of humble plants, that they may riſe and re-
" move, ſpread more ſail to the wind: the thiſtle
" ſpreads his beard; and away he travels to fix
" his reſidence in remote parts. A plant of this
" kind, *Erigeron Canadenſe*, was imported from
" Canada about one hundred years ago, into the
" Paris garden. It is now ſpread as a wild plant
" over France, Holland, Germany, Italy, and

it is ſaid over Sicily. It is ſpread to ſuch a degree over the ſouth of England, as to be inliſted among the indigenous plants. Some ſeeds, ſuch as our clot-bur, are of an adheſive nature: they lay hold of animals that come near them, and are ſpread far and near.

“ Many other agents are employed by nature, to ſtock the earth with plants. The ſea and rivers waft more ſeeds than they do ſails, from one part of the world to another. I have found ſeeds caſt aſhore in the Hebrides, that had been dropt accidentally into the ſea among the Weſt-India iſlands. The iſland of Aſcenſion, is the droſs of a volcano of a recent date. Its immenſe diſtance from land, renders its ac-

“ ſemination of plants. Many birds live on fruits
“ and berries: the pulp is their aliment; and
“ they diſcharge the ſeeds unimpaired, and ſpread
“ them every where. Theſe ſeeds are heavy,
“ and unprovided with any *apparatus* for flight;
“ but the birds ſerve them for wings. Hence
“ may be ſeen plantations of holly, yew, white-
“ beam, rowan, ſpindletree, hawthorn, and ju-
“ niper, formed by the birds of the air, upon im-
“ pending clifs and inacceſſible precipices. Be-
“ cauſe the miſſelto grows upon trees, and has no
“ flower that can be perceived; it was reckoned
“ formerly a product of equivocal generation.
“ It was concluded, that its large, round, heavy,
“ berries, were not the ſeeds of the plant, be-
“ cauſe they might fall to the ground, but never
“ could mount up into trees. No berries are
“ more palatable to birds of the thruſh kind; and
“ it is they who plant them on high and diſtant
“ trees. It is extremely remarkable, that the ve-
“ getating power of ſeeds, inſtead of being im-
“ paired in the ſtomach of birds, ſeems to be
“ fortified. The ſeeds of the magnolia, import-
“ ed from America, commonly refuſe to vegetate
“ under the management of the moſt ſkilful gar-
“ deners. But I have heard, that theſe ſeeds,
“ when voided by turkies, never fail to grow.
“ It is well known, that the dung of domeſtic a-
“ nimals, while it fertilizes a garden, fills it
“ with weeds. It approaches to a miracle, that

ſeeds ſhould withſtand the power of animal digeſtion, which no other vegetable ſubſtance can do. Here is a meaſure laid down by Providence for the preſervation and diſſemination of ſeeds, that I cannot reflect upon without wonder.

" In order to fill the earth with plants, any other method except by ſeeds, ſuckers, and layers, appears to me unneceſſary, and therefore improbable. Farewell then to equivocal generation. I can ſcarce write of it, without being a little ruffled; ſo ill it correſponds with the more auguſt and comfortable ideas of creation, which have made a principal article of happineſs in my life."

So far my correſpondent. I join heartily with nally, not plants or animals, but embryos of thoſe incloſed in an egg or ſeed, which when depoſited in a proper *nidus* or *matrix*, grow up to a plant or animal, and then decay. And to account for future generations, it is held, that every embryo contains within it ſmaller embryos without end, like cups of different ſizes caſed one within another. Theſe philoſophers muſt go ſtill farther. To account for each ſeed producing a tree, and that tree producing ſeed, it muſt alſo be held, that the embryo incloſed in a ſeed contains ſmaller embryos decreaſing in ſize without end; and that each of theſe ſmaller embryos contains another ſeries of decreaſing embryos, alſo without end. Here are infinites upon infinites, without end. To avoid the intricacy of infinites upon infinites, ſome philoſophers have varied the ſyſtem a little, with a view to render it, as they think, more ſimple, by recurring to organized atoms, exploded above *. But this ſyſtem, not to repeat what is ſaid againſt it above, is only in appearance more ſimple: it reſolves into infinites upon infinites like the former, and is in reality no leſs intricate. Take any of the ſuppoſed embryos, hovering in air, ſwimming in water, or fixed in earth: give it a proper *matrix*, and let it become a tree with ſeed. As each ſeed may produce a tree, and each tree produce ſeed which may alſo become trees, it is

---

* See Bonnet upon organized bodies.

anifeſt, that an infinite number of embryos muſt
ve been contained in the firſt embryo, and an
finite number in every one of that infinite num-
r.

That every ſeed contains an embryo-plant, is a
luable diſcovery in natural hiſtory; but that there
a decreaſing ſeries of embryos within every
ed, is a mere conceit, aſſumed without the leaſt
pearance of truth. So far from future plants
bſiſting in a ſeed without end, that even the
ant immediately produced from a ſeed, does not
bſiſt in the ſeed with all its parts entire. The
ume and radicle alone ſubſiſt in it; and the o-
er parts are produced in the courſe of growing.
it let us give way to the ſuppoſition of an in-
ite ſeries, to ſee what can be made of it. Wri-

Unleſs theſe particulars can be accounted for mechanically, in vain are embryos created in the brain of viſionary writers. They muſt admit a power even in the ſmalleſt embryo, to expand itſelf into a plant or animal, where it happens upon a proper nidus. I ſay, they muſt admit that power; and yet the admiſſion deſtroys their hypotheſis, root and branch. A ſeed thrown into the ground would reſt there for ever, were it not endued with a power, to begin vegetation, and to continue it. It grows into a tree: why may not that tree be endued with a power to form its own ſeed? If ſo, there is no neceſſity to go farther back: organized atoms or embryos muſt vaniſh, becauſe there is no uſe for them. Power in a tree to form its ſeeds, is no more extraordinary than that of ſucking juices from the earth, and converting them into its own ſubſtance, a power that every plant is admitted to have. And if plants have power to form ſeed, there ſurely can be no heſitation in aſcribing the ſame power to animals. Can any thing be more ſimple, or more agreeable to the analogy of nature, than that the Almighty, who created plants and animals,

---

theſe two parts, but to get into the air and earth. As ſeeds are generally depoſited on or near the ſurface of the ground, the plume aſcends and the radicle deſcends. But place a ſeed in an inverted flower-pot: the radicle aſcends and the plume deſcends: the firſt purſues his road into the earth; and the other into the air.

ſhould

ould endue them with a power to propagate
eir kind? Are we not informed of this by eye-
ght; and can any ſolid argument be urged a-
inſt what we ſee? Thus the operations of na-
re, when underſtood, turn out no leſs illuſtri-
ıs for their ſimplicity than for their extenſive
fects.

I ſhall cloſe this eſſay with a paſſage of another
tter from my correſpondent above mentioned.

> As for the doctrine of organized atoms diffuſed through the univerſe in order to be converted into animals and vegetables, it is not countenanced by any thing within the ſphere of my knowledge. No facts are adduced, nor do I recollect any, to ſupport it. I adhere more and more to this plain truth, that all plants and a-

“ tion, is obvious to every eye. By what means
“ it is performed, ſeems to be that high legerdemain
“ which nature will never reveal. But if
“ by this power bread and water can be changed
“ into fleſh and blood, into bones and ſinews,
“ into the Argus' eye on the peacock's tail; if by
“ this power ſimple water can be converted into
“ the hardeſt wood, into aromatic flowers and
“ rich fruits; I then ceaſe to wonder, that the
“ ſame water ſhould be converted into a ſeed, capable
“ of unfolding itſelf into a future plant. I
“ require no aid from vagrant organized atoms;
“ I ſee no aſſiſtance they can afford. I diſlike a
“ hypotheſis that appears not to have any foundation
“ in truth, or even in probability.”

F I N I S.

Plate 1

## Chain Plough



## Brake





Models of the Instruments here delineated are ready for public inspection at the work yard of M$^{r}$ Crichton Coachmaker Edin$^{r}$.

Plate.

Firſt Harrow



Second Harrow



Third Harrow



Cleaning Harrow



Grass seed Harrow



# BOOKS printed for and ſold by W. CREECH, Edinburgh, and T. CADELL, London.

Eſſays relating to Agriculture and Rural Affairs, illuſtrated with copperplates. By James Anderſon, 2 vols. The 2d edition, 12 s. bound.

A Diſſertation on Quick-lime, as a cement, and as a manure. By the ſame Author. 5 s. in boards.

A Treatiſe on Agriculture. By the late Reverend Dr Adam Dickſon. The 2d edition, 2 vols, with plates, 12 s.

Small Farms deſtructive to the country in its preſent ſituation. By the ſame, 6 d.

The Principles of Agriculture and Vegetation. By Dr Francis Home. The 3d edition, 2 s. 6 d. bound.

Evelyn's *Sylva*; or, A Diſcourſe upon Foreſt-Trees; a new edition, with additions, and notes, by Dr Hunter of York, with elegant engravings of all the foreſt-trees. L. 3, 3 s. the large paper, and L. 2 : 12 : 6 the ſmall.

Georgical